1 2 3 4 5

D C B A

INSTALL 1146 LF OF ACCESS CONTROL FENCE ON RIGHT-OF-WAY

REMOVE EXISTING FENCE

REMOVE ALL TREES WITHIN THE LEVEE RIGHT-OF-WAY AND ANY TREE THAT WILL CONFLICT WITH NEW FENCE INSTALLATION.

LEVEE D

I - 135

REMOVE ALL TREES WITHIN THE LEVEE RIGHT-OF-WAY, UP TO AND INCLUDING ANY TREES IN THE CHAIN LINK FENCE.

LEVEE D

FC20

FC21

FC22

FC23

BEGIN PROPOSED FENCE

END PROPOSED FENCE

RDLB Holdings, L.L.C. Tract "72"
KEY # B-13970

BRIDGEPORT CIR

MATCHLINE - SEE SHEET LM-2.03

THIS SHEET:
FENCE TO BE DEMOLISHED: 676 LF
NEW FENCE TO BE INSTALLED: 1146 LF

NOTES:

1. TREES TO BE REMOVED THAT ARE GREATER THAN 15' FROM THE TOE OF THE LEVEE MAY BE CUT FLUSH WITH GROUND SURFACE AND TREATED TO PREVENT FUTURE GROWTH. SEE SHEETS G-1.02 AND G-1.03.
*2. COORDINATES PROVIDED ARE IN NAD83 STATE PLANE, SOUTH ZONE AND SHALL ONLY BE USED FOR THE INITIAL LOCATION OF FENCE TO BE INSTALLED. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING THE CURRENT LEGAL RIGHT-OF-WAY AND PLACING THE PROPOSED FENCE THEREON.

FENCE COORDINATES*		
POINT NAME	NORTHING	EASTING
FC20	1710909	1652069
FC21	1711067	1652440
FC22	1711140	1652611
FC23	1711359	1653122

N

50' 25' 0 50'
GRAPHIC SCALE

MARK	DESCRIPTION	DATE	APPR.

amec
AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-4630
Fax: (785) 272-4676

CITY OF WICHITA

SYSTEMWIDE VEGETATION MAINTENANCE - PHASE 3
WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

LAWRENCE J. SAMPLE
LICENSED
13855
5-20-2011
KANSAS
PROFESSIONAL ENGINEER

DESIGNED BY: Larry Sample, PE		DATE: 5-20-2011
DWN BY: RES	CKD BY: LBK	APP BY: L. SAMPLE
FILE NAME: 10_TREE REMOVAL PLAN.dgn		
AMEC PROJ. NO. 5-6150-0001		

TREE REMOVAL PLAN

LM-2.04

SHEET 10 OF 42