FENCE COORDINATES*		
POINT NAME	NORTHING	EASTING
FC29	1712365	1648237
FC30	1712365	1648268
FC31	1712566	1648363
FC32	1712722	1648409
FC33	1712797	1648423
FC34	1712860	1648432
FC35	1712860	1648404
FC36	1712660	1647705
FC37	1712675	1647754
FC38	1712776	1647801
FC39	1712861	1647821
FC40	1712927	1647836
FC41	1712925	1647856
FC42	1713006	1647865
FC43	1713066	1647876

NOTES:

1. PROPERTY LINES SHOWN ARE POST AQUISITION. WHERE PROPERTY ACQUISITION IS EVIDENT, THE CONTRACTOR SHALL VERIFY WITH THE CITY OF WICHITA THAT THE PROPERTY HAS BEEN ACQUIRED PRIOR TO COMMENCING WORK IN THE AREA.
2. TREES TO BE REMOVED THAT ARE GREATER THAN 15' FROM THE TOE OF THE LEVEE MAY BE CUT FLUSH WITH GROUND SURFACE AND TREATED TO PREVENT FUTURE GROWTH. SEE SHEETS G-1.02 AND G-1.03.
*3. COORDINATES PROVIDED ARE IN NAD83 STATE PLANE, SOUTH ZONE AND SHALL ONLY BE USED FOR THE INITIAL LOCATION OF FENCE TO BE INSTALLED. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING THE CURRENT LEGAL RIGHT-OF-WAY AND PLACING THE PROPOSED FENCE THEREON.

50' 25' 0 50'
GRAPHIC SCALE

BEGIN PROPOSED FENCE
FC36
ADD ALTERNATE #2 INSTALL 51 LF OF IN-KIND FENCE UPON ADDITIONAL RIGHT-OF-WAY ACQUISITION AND AT THE DIRECTION OF THE CITY OF WICHITA.
END PROPOSED FENCE
FC37
TRACT "43"
ADD ALTERNATE #2 UPON ADDITIONAL RIGHT-OF-WAY ACQUISITION REMOVE TREES TO NEW RIGHT-OF-WAY AND PROCEED WITH FENCE INSTALLATION, AS DIRECTED BY THE CITY OF WICHITA.
LEVEE M
BEGIN PROPOSED FENCE
FC38
TRACT "42"
60' R/W
REMOVE ALL TREES TO EXISTING RIGHT-OF-WAY.
FC39
FC40
ADD ALTERNATE #2 INSTALL 319 LF OF IN-KIND FENCE UPON ADDITIONAL RIGHT-OF-WAY ACQUISITION AND AT THE DIRECTION OF THE CITY OF WICHITA.
FC41
FC42
FC43
END PROPOSED FENCE
N FAIRVIEW
ADD ALTERNATE #2 REMOVE EXISTING FENCE UPON CONFIRMATION THAT ADDITIONAL RIGHT-OF-WAY HAS BEEN ACQUIRED BY THE CITY.
ADD ALTERNATE #2 REMOVE EXISTING FENCE UPON CONFIRMATION THAT ADDITIONAL RIGHT-OF-WAY HAS BEEN ACQUIRED BY THE CITY.
REMOVE ALL TREES TO EXISTING RIGHT-OF-WAY.
REMOVE ALL TREES TO EXISTING RIGHT-OF-WAY.
LEVEE M
LEVEE M
ADD ALTERNATE #2 UPON ADDITIONAL RIGHT-OF-WAY ACQUISITION REMOVE TREES TO NEW RIGHT-OF-WAY AND PROCEED WITH FENCE INSTALLATION, AS DIRECTED BY THE CITY OF WICHITA.
ADD ALTERNATE #2 UPON ADDITIONAL RIGHT-OF-WAY ACQUISITION REMOVE TREES TO NEW RIGHT-OF-WAY AND PROCEED WITH FENCE INSTALLATION, AS DIRECTED BY THE CITY OF WICHITA.
REMOVE/CUT ALL TREES BETWEEN LEVEE TOE AND N. FAIRVIEW ROAD.
W 41ST ST N
W 42ND ST N
LONGLANE RD
FC29
FC30
LEVEE N
ADD ALTERNATE #4 MOVE EXISTING FENCE TO PROPERTY LINE. THE CONTRACTOR SHALL USE AND RESET THE EXISTING FENCE ON THE EXISTING PROPERTY LINE, AND SHALL INSTALL NEW MATCHING FENCE MATERIAL AS NECESSARY.
ADD ALTERNATE #3 RELOCATE/DEMO STORAGE SHED OR PORTIONS THEROF THAT ARE ENCROACHING ON THE EXISTING FLOOD CONTROL RIGHT-OF-WAY
REMOVE ANY TREES BETWEEN LEVEE AND FENCE. TRIM ALL TREES BACK TO FENCE.
FC31
FC32
FC33
FC34
FC35
ADD ALTERNATE #4 ALL RECLAIMED RIGHT-OF-WAY SHALL BE SEEDED TO GRASS.
REMOVE ALL TREES AND DEBRIS
LEVEE N
TRACT "69"
TRACT "68"
TRACT "67"
TRACT "66"
TRACT "65"
ADD ALTERNATE #4 ANY DEBRIS IN THE AREA BETWEEN THE EXISTING AND NEW FENCE ALIGNMENT SHALL BE MOVED TO THE ADJACENT LANDOWNER OR DISPOSED OF (AS DIRECTED BY THE CITY OF WICHITA).
N BROADWAY ST

THIS SHEET:
(ADD ALTERNATE #2)
FENCE TO BE DEMOLISHED: 377 LF
NEW FENCE TO BE INSTALLED: 369 LF

(ADD ALTERNATE #4)
SUPPLEMENTAL QUANTITIES:
FENCE TO BE MOVED: 525 LF
NEW FENCE TO BE INSTALLED: 61 LF

MARK	DESCRIPTION	DATE	APPR.

amec
AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-4830
Fax: (785) 272-4878

CITY OF WICHITA

SYSTEMWIDE VEGETATION MAINTENANCE - PHASE 3
WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

LAWRENCE J. SAMPLE LICENSED 18855 5-20-2011 KANSAS PROFESSIONAL ENGINEER

DESIGNED BY: Larry Sample, PE		DATE: 5-20-2011
DWN BY: RES	CKD BY: LBK	APP BY: L. SAMPLE
FILE NAME: 12_TREE REMOVAL PLAN.dgn		
AMEC PROJ. NO. 5-6150-0001		

TREE REMOVAL PLAN

LM-2.06

SHEET 12 OF 42