MATCHLINE - SEE SHEET LM-3.03

APPLY SURFACING MATERIAL IN ACCORDANCE WITH NOTE 3 AND LEVEE SURFACING DETAIL 3 ON SHEET G-1.04. SPECIFIED MINIMUM ELEVATION=1330.8

N= 1,714,131.21
E= 1,648,039.33

APPLY SURFACING MATERIAL IN ACCORDANCE WITH NOTE 2 AND LEVEE SURFACING DETAIL 2 ON SHEET G-1.04. SPECIFIED MINIMUM ELEVATION=1330.6

N= 1,712,785.60
E= 1,647,863.20

APPLY SURFACING MATERIAL IN ACCORDANCE WITH NOTE 2 AND LEVEE SURFACING DETAIL 2 ON SHEET G-1.04. SPECIFIED MINIMUM ELEVATION=1330.4

N= 1,712,477.49
E= 1,647,659.15

MATCHLINE - SEE SHEET LM-3.01

LEVEE P

LEVEE D

N= 1,711,403.78
E= 1,653,105.83

N= 1,710,790.91
E= 1,651,663.02

APPLY SURFACING MATERIAL IN ACCORDANCE WITH NOTE 1 AND LEVEE SURFACING DETAIL 1 ON SHEET G-1.04

N= 1,710,702.74
E= 1,651,453.31

NEW LEVEE ACCESS ROAD. REFER TO SHEET LM-4.04 FOR SURFACING DETAILS.

LEVEE P

LEVEE D

LEVEE D

N= 1,710,017.07
E= 1,649,226.39

APPLY SURFACING MATERIAL IN ACCORDANCE WITH NOTE 1 AND LEVEE SURFACING DETAIL 1 ON SHEET G-1.04

N

300' 150' 0 300'

GRAPHIC SCALE

NOTES:

1. UPON COMPLETION OF ALL TREE REMOVAL ACTIVITY IN THIS AREA, THE TOP OF THE LEVEE SHALL BE RESURFACED WITH RECYCLED ASPHALT PRODUCT (MINIMUM 8-INCH THICK LAYER). REFER TO SHEET G-1.04, LEVEE SURFACING DETAIL 1.
2. UPON THE COMPLETION OF ALL TREE REMOVAL ACTIVITY IN THIS AREA, ALL MAJOR RUTS (GREATER THAN 4-INCHES DEEP) SHALL BE FILLED AND COMPACTED. ONCE RUTS HAVE BEEN FILLED THE TOP OF THE LEVEE SHALL BE GRADED AND AN 8-INCH THICK LAYER OF RECYCLED ASPHALT PRODUCT SHALL BE APPLIED, COMPACTED AND GRADED TO A SMOOTH SURFACE. THE RESURFACED TOP OF LEVEE ELEVATION SHALL BE AT OR ABOVE THE ELEVATION SPECIFIED. SEE SHEET G-1.04, LEVEE SURFACING DETAIL 2.
3. UPON COMPLETION OF ALL TREE REMOVAL ACTIVITY IN THIS AREA, ALL MAJOR RUTS (GREATER THAN 4-INCHES DEEP) SHALL BE FILLED AND COMPACTED. ONCE RUTS HAVE BEEN FILLED THE TOP OF THE LEVEE SHALL BE RAISED TO 8-INCHES BELOW THE ELEVATION SPECIFIED WITH COMPACTED FILL ON 2:1 SIDE SLOPES. AFTER EARTHFILL HAS BEEN COMPACTED AND GRADED TO THE PROPER ELEVATION, AN 8-INCH THICK LAYER OF RECYCLED ASPHALT PRODUCT SHALL BE APPLIED, COMPACTED AND GRADED TO A SMOOTH SURFACE. THE FINISHED TOP OF LEVEE SURFACE SHALL BE AT OR ABOVE THE ELEVATION SPECIFIED. SEE SHEET G-1.04, LEVEE SURFACING DETAIL 3.

MARK	DESCRIPTION	DATE	APPR.

amec
AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-4630
Fax: (785) 272-4678

CITY OF WICHITA

SYSTEMWIDE VEGETATION MAINTENANCE - PHASE 3
WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

LAWRENCE J. SAMPLE
LICENSED
No. 18855
5-20-2011
PROFESSIONAL ENGINEER
KANSAS

DESIGNED BY: Larry Sample, PE		DATE: 5-20-2011
DWN BY: RES	CKD BY: LBK	APP BY: L. SAMPLE

FILE NAME: 15_LEVEE SURFACING PLAN.dgn

AMEC PROJ. NO. 5-6150-0001

LEVEE SURFACING PLAN

LM-3.02

SHEET 15 OF 42