

The following Earthwork Quantities were figured using the Average End Area Method. No quantity adjustment factors were included.

Excavation - 8,335 Cu. Yds.
 Fill - 115 Cu. Yds.

These Earthwork Quantities reflect the excavation to the existing ground, including the existing curb at the time of the survey. The Bid Quantities have been reduced by the volume of the existing curb that is to be removed. See Quantity Recap Sheets for more information.

