

RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
LUMP SUM BID ITEMS (707027)		
Mobilization	1	LS
Field Office and Lab (Type A)	1	ea
Site Clearing	1	LS
Removal of Existing Structures	1	LS
Concrete &/or Asphalt Pavement Removed	9461	sy
Excavation	1448	cy
Compacted Fill (95% Density)	1038	cy
Concrete Pavement (5") (for Curb Sawcuts)	420	sy
Concrete Pavement (7") (Reinf.) (Mid-Block Crosswalks)	111	sy
Concrete Pavement (8") (Reinf.) (Alley Entrances)	1865	sf
Concrete Pavement (9") (Reinf.) (Intersections)	2238	sy
Concrete Pavement Header (11") (Reinf.) (Mid-Block Crosswalks)	44	sy
Concrete Sidewalk Flume	2	ea
AC Pavement 2" (BM-2, PG 70-28)	8614	sy
AC Pavement Milling	8614	sy
Crushed Rock Base 6", Reinforced	4594	sy
Crushed Rock Base 7", Reinforced (Alley Entrances)	192	sy
Concrete C & G, Comb. Type I Mod. (6" & 1-1/2")	4005	lf
Wheelchair Ramp w/ Detectable Warnings	12	ea
Inlet, Curb (Type I) (L=5', W=3')	5	ea
Inlet, Curb (Type II) (Double) (L=5', W=2')	2	ea
Inlet, Curb (Remove & Reset)	2	ea
Inlet, Grated Driveway, Single	2	ea
Inlet Hookup	11	ea
MH, Reinforced Concrete (4' x 5')	3	ea
Pipe, PVC 4", Perforated (Inlet Underdrain)	99	lf
Pipe, RCP 12"	242	lf
Pipe, RCP 15"	14	lf
Pipe, RCP 18"	10	lf
Pipe, HERCP (42"x27")	85	lf
Fill, Sand (Flushed & Vibrated)	350	lf
Signing	1	LS
Pavement Marking	1	LS
Traffic Signal Modification (St. Francis & 1st St.)	1	LS
Traffic Signal Modification (St. Francis & 2nd St.)	1	LS
Traffic Control	1	LS
Streetlighting	1	LS
LUMP SUM BID ITEMS - LANDSCAPE (707027)		
Brick Pavers (Concrete), Crosswalk	538	sy
Brick Pavers (Concrete), Sidewalk Band	402	sy
Trash Receptacle	25	ea
Bicycle Rack	38	ea
Steel Bench	49	ea
Sodding, Bermuda	1	LS
Tree, Chinese Pistache - 2.5" caliper	10	ea
Tree, Lacebark Elm 'Allee' - 2.5" caliper	24	ea
Tree, Japanese Zelkova 'Green Vase' - 2.5" caliper	28	ea

RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
MEASURED QUANTITY BID ITEMS (707027)		
Concrete Sidewalk 4"	33046	sf
Concrete Driveway 8" (Reinf.)	10589	sf
AC Pvmf 6", Temp for Patching	90	sy
Small Tree Removal	5	ea
Large Tree Removal	1	ea
MH Ad Justed	27	ea
Valve Box Ad Justed	22	ea
Meter Box Ad Justed	25	ea
Fire Hydrant Ad Justment	6	ea
Roof Drain Connection	2	ea
Sign, Electronic Portable Message	50	day
MEASURED QUANTITY BID ITEMS - BMP's (707027)		
BMP, Curb Inlet Protection	11	ea
BMP, Silt Fence	4000	lf
MEASURED QUANTITY BID ITEMS - WATERLINE (636249)		
Pipe, PVC 8"	471	lf
Pipe, D1CL 8"	17	lf
Pipe, D1CL 6"	2	lf
Fill, Sand (Flushed & Vibrated)	490	lf
Fire Hydrant Assembly	1	ea
Fire Hydrant Removal	1	ea
Service Meter Setter, 1"	3	ea
Pavement Removal	515	lf
AC Pvmf 2", Temp for Patching	348	lf
AC Pvmf 6", Temp for Patching	167	lf
Concrete Base 6"	348	lf
MEASURED QUANTITY BID ITEMS - SANITARY SEWER (620576)		
MH Removed	3	ea
MH, Type P, Standard (4')	1	ea
Fill, Sand (Flushed & Vibrated)	712	lf
Pipe, PVC 8"	712	lf
Pavement Removal	706	lf
AC Pvmf 2", Temp for Patching	375	lf
AC Pvmf 2" (BM-2, PG 70-28)	75	lf
AC Pvmf 6", Temp for Patching	256	lf
Concrete Base 6"	450	lf
Service Connection Reconnection	1	ea
Pipe Connection	2	ea

See Sh. No. R40 for Summary of Landscape Quantities.
 See Sh. No. R47 and R49 for Traffic Signal Bill of Materials.
 See Sh. No. R52 for Summary of Pavement Markings.
 See Sh. No. R55 for Sign Assembly Tables.
 See Sh. No. R71 for List of Traffic Control Devices.
 See Sh. No. E2 for Summary of Electric Lighting System Quantities.

No.	Revision	By	Date
ST. FRANCIS STREET			
RECAPITULATION OF QUANTITIES			
JAMES L. ARMOUR, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-84920			
Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	JPS	Job No.	10310
Drawn by	DRP	Date	July, 2011