

CERTIFICATE OF SURVEY

I, Gregory J. Allison, a registered land surveyor in Kansas, do hereby certify that I have been in responsible charge of surveying and plating of "MONARCH LANDING THIRD ADDITION", an addition to Wichita, Sedgwick County, Kansas, into Lots, Blocks, Reserves and Streets, the same being accurately set forth in the accompanying plat and described herein:

A tract of land lying in the Southeast Quarter of the Southeast Quarter, Section 1, Township 27 South, Range 2 East, of the 6th Principal Meridian, Wichita, Sedgwick County, Kansas, said tract being more particularly described as follows:

COMMENCING at the southeast corner of the Southeast Quarter of said Section 1; thence along the east line of said Southeast Quarter on a Kansas coordinate system of 1983 south zone grid bearing of N00°38'46"W, 650.02 feet to the POINT OF BEGINNING, thence parallel with and 650.00 feet north of the south line of said Southeast Quarter, S88°55'31"W, 790.00 feet; thence S01°04'29"E, 275.00 feet; thence S88°55'31"W, 354.04 feet; thence N37°18'14"W, 106.46 feet to a point on the east right-of-way line of Flutter Lane, said point being a point on a non-tangent curve to the left; thence along said curve and said east right-of-way line, 182.95 feet to a reverse curve, said curve to the left having a central angle of 50°23'40", a radius of 208.00 feet, and a long chord distance of 177.11 feet, bearing N28°48'47"E; thence along said reverse curve continuing along said east right-of-way line, 102.66 feet to the southwest corner of Lot 1, Block 3, Monarch Landing Addition, an addition to Wichita, Sedgwick County, Kansas, said curve having a central angle of 15°59'03", a radius of 368.00 feet, and a long chord distance of 102.83 feet, bearing N11°36'28"E; thence along the south line of said Block 3 for the next two courses, S87°42'19"E, 128.47 feet; thence S73°24'04"E, 97.51 feet to the southeast corner of said Block 3; thence along the east line of said Block 3, N16°46'34"E, 120.09 feet to the south right-of-way line of Boxthorn Street, being a point on a non-tangent curve to the right; thence along said curve and said south right-of-way line 16.60 feet, said curve having a central angle of 01°47'51", a radius of 529.00 feet, and a long chord distance of 16.60 feet, bearing N76°07'04"W; thence N14°46'52"E, 58.00 feet to the north right-of-way line of said Boxthorn Street, being the southeast corner of Block 4, said addition; thence along the east line of said Block 4, N01°03'01"W, 280.20 feet to the south right-of-way line of Camden Chase Street; thence along said south right-of-way line, S88°58'38"W, 22.83 feet; thence N01°01'22"W, 64.00 feet to the north right-of-way line of said Camden Chase Street, being the southeast corner of Block 5, said addition; thence along the east line of said Block 5, N01°03'01"W, 131.86 feet to the northeast corner of said addition, being a point on the north line of said Southeast Quarter of said Southeast Quarter; thence along said north line, N88°56'59"E, 866.12 feet to the east line of said Southeast Quarter of said Southeast Quarter; thence along said east line, S00°38'46"E, 677.23 feet to the POINT OF BEGINNING.

All streets, easements, setbacks, access controls, dedications, together with that portion of a Drainage Easement recorded Doc.#/FLM-PG: 28857837, and any other public dedications all within the above described property are hereby vacated and replatted by virtue of K.S.A. 12-512(b).

I hereby certify that the details of this plat are correct to the best of my knowledge and belief. this ___ day of _____, 2011.

Gregory J. Allison, PE, LS #1257
MKEC Engineering Consultants, Inc.
411 North Webb Road
Wichita, Kansas 67206

OWNER'S CERTIFICATE

Know all men by these presents that the undersigned property owner of the land above set forth in the Registered Land Surveyor's Certificate, has caused the same to be surveyed and platted into Lots, Blocks, Reserves and Streets the same to be known as "MONARCH LANDING THIRD ADDITION", an addition to Wichita, Sedgwick County, Kansas.

Easements for the construction and maintenance of public utilities and drainage, as indicated on the accompanying plat are hereby granted to the public. Private screening fences, walls, and associated appurtenances may cross drainage and/or utility easements. The wall easements are hereby platted for the construction and maintenance of a private wall. Utilities and drainage may cross the wall easement.

The streets are hereby dedicated to and for the use of the public.

Reserves "A", "B", and "C" are platted for drainage, utilities confined by easements, sidewalks, landscaping, irrigation, signs, open space, berms, and monuments. The Reserves shall be owned and maintained by the developer and/or a Lot Owner's Association and/or successors or assigns and are reserved for the stated uses.

A drainage plan has been developed for this plat. Drainage easements, rights-of-way, or reserves shall remain at established grades or as modified with the approval of the applicable City or County Engineer, and unobstructed to allow for the conveyance of stormwater.

MONARCH LANDING, LLC, a Kansas limited liability company

Kevin Mullen, President
Ritchie Development Corporation, manager

STATE OF KANSAS, SEDGWICK COUNTY} ss:

This instrument was acknowledged before me on this ___ day of _____, 2011, by Kevin Mullen, President, Ritchie Development Corporation, manager, Monarch Landing, LLC, a Kansas limited liability company.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my official seal, the day and year last above written.

Notary Public
My Term Expires: _____

MORTGAGE CERTIFICATE

INTRUST Bank, N.A. holder of a mortgage on the above described property, does hereby consent to the plat of "MONARCH LANDING THIRD ADDITION."

INTRUST Bank, N.A.

Gary D. Schmitt, Executive Vice President

This instrument was acknowledged before me on this ___ day of _____, 2011, by Gary D. Schmitt, Executive Vice President, INTRUST Bank, N.A.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my official seal, the day and year last above written.

Notary Public
My Term Expires: _____

FINAL PLAT

MONARCH LANDING THIRD ADDITION

AN ADDITION TO WICHITA, SEDGWICK COUNTY, KANSAS

PLANNING COMMISSION CERTIFICATE


This plat of "MONARCH LANDING THIRD ADDITION" has been submitted to and approved by the Wichita-Sedgwick County Metropolitan Area Planning Commission, Wichita, Kansas.

Dated this ___ day of _____, 2011

WICHITA-SEDGWICK COUNTY METROPOLITAN AREA PLANNING COMMISSION

Debra Miller Stevens, Chair


John L. Schlegel, Secretary



VICINITY MAP

BENCH MARKS

- BM#2 Railroad spike in north side of power pole, 924' east and 50' south of the South Quarter corner, Sec. 1, T27S, R2E. Elev. = 1373.14 NAVD88
BM#5 Railroad spike in north side of power pole, 1040' west and 51' south of the southeast corner, Sec. 1, T27S, R2E. Elev. = 1369.00 NAVD88





LEGEND

Date of Survey: May 12th, 2011

- Section corner Monument Found
Found survey monument; 3/8" rebar w/ MKEC CLS 39 id cap unless otherwise annotated
Set 3/8" Rebar w/ MKEC CLS 39 id. cap
Measured
Platted
Calculated from Measured
Record description or deed
Utility Easement
Drainage Easement
15' Street Easement

MINIMUM PAD ELEVATIONS LOWEST OPENINGS table with columns for LOTS, BLOCK, and ELEVATION NAVD88. Values: 1 & 2, 3, 1369.5



STREET CENTERLINE CURVE TABLE with columns for CURVE, LENGTH, RADIUS, DELTA, CHORD, BEARING. Data for curves C1 and C2.

STREET CENTERLINE TABLE with columns for LINE, LENGTH, BEARING. Data for lines L1, L2, and L3.



411 N. WEBB ROAD WICHITA, KS. 67206 316 - 684 - 9600