

VALVE BOXES ADJUSTED (70121000)				
STREET	STA	OFFSET	Ex. ELEV.	NEW ELEV.
Broadway	47+40.3	30.2' Lt	1285.59	1285.71
Broadway	50+43.3	13.5' Lt	1285.95	1286.88
Broadway	50+47.0	20.6' Lt	1285.73	1286.75
Pawnee	9+57.3	21.5' Lt	1285.77	1286.67
Pawnee	9+62.6	15.7' Lt	1285.87	1286.97
Pawnee	10+51.6	22.6' Lt	1286.06	1287.01
Pawnee	13+33.5	24.2' Lt	1286.62	1286.90

SS MH ADJUSTED w/NEW RING & COVER (60113000)					
STREET	STA	OFFSET	Ex. ELEV.	NEW ELEV.	REMARKS
Pawnee	8+08.1	12.1' Rt	1284.83	1285.51	Standard
Pawnee	8+15.6	12.2' Rt	1284.91	1285.37	Standard

SWS MH ADJUSTED w/NEW RING & COVER (60113000)					
STREET	STA	OFFSET	Ex. ELEV.	NEW ELEV.	REMARKS
Broadway	52+15.8	22.4' Lt	1285.10	1285.38	Standard
Broadway	52+46.8	24.1' Lt	1285.10	1285.27	Standard
Pawnee	9+45.8	38.1' Rt	1286.29	1286.34	Standard
Pawnee	9+77.3	35.2' Lt	1285.92	1286.83	Standard
Pawnee	10+42.0	14.5' Lt	1286.28	1287.21	Standard
Pawnee	10+69.4	37.5' Rt	1286.85	1287.11	Standard

CONCRETE SIDEWALK 4" (20401004)				
STREET	STATION	SIDE	AREA S. F.	
Broadway	43+91.00 - 49+03.65	Lt	597.2	
Broadway	43+91.00 - 49+03.65	Rt	1,013.1	
Broadway	49+03.65 - 50+85.19	-	1,600.7	
Broadway	50+85.17 - 56+10.00	Lt	989.8	
Broadway	50+85.17 - 56+10.00	Rt	1,515.2	
Pawnee	7+50.00 - 9+03.90	Lt	2,890.8	
Pawnee	7+50.00 - 9+03.90	Rt	2,531.3	
Pawnee	10+93.95 - 13+50.53	Lt	2,239.0	
Pawnee	10+93.95 - 13+50.53	Rt	2,032.4	
Total			15,409.7	

WHEELCHAIR RAMPS (20571000)			
STREET	INTERSECTION	REMARKS	NUMBER
Broadway	Walmart Entrance, ES, S of Pawnee	Standard	2
Broadway	Park Entrance, WS, S of Pawnee	Standard	2
Pawnee	Alley, NS, E of Broadway	Standard	2
Total			6

WHEELCHAIR RAMPS w/DETECTABLE WARNINGS (20572000)			
STREET	INTERSECTION	REMARKS	NUMBER
Broadway	Pawnee & Broadway	Standard	8
Pawnee	West side of Topeka, N & S	Standard	2
Total			10

CONCRETE DRIVEWAY 8" (REINFORCED) (20344008)				
STREET	STATION	SIDE	WIDTH	AREA S. F.
Broadway	41+18.50	Lt	24'	431.43
Broadway	41+77.00	Lt	24'	500.77
Broadway	42+77.50	Lt	24'	503.80
Broadway	46+46.60	Rt	25'	463.64
Broadway	51+10.29	Rt	31'	390.03
Broadway	51+58.38	Rt	31'	397.41
Broadway	51+61.55	Lt	31'	585.50
Broadway	52+80.40	Rt	31'	461.87
Broadway	52+95.45	Lt	31'	629.82
Broadway	53+50.93	Rt	31'	535.18
Broadway	53+65.04	Lt	31'	725.59
Broadway	54+60.91	Rt	31'	674.54
Broadway	54+61.33	Lt	31'	892.00
Broadway	55+57.37	Rt	27'	672.94
Broadway	55+64.51	Lt	31'	460.69
Pawnee	8+38.22	Lt	30'	257.00
Pawnee	11+45.27	Lt	20'	249.91
Pawnee	12+80.31	Lt	24'	607.07
Total				9,439.19

NOTE:
 For Sodding Quantities, see Sodding Plan
 For Erosion Control BMP Quantities, See Erosion Control Plan
 For Pavement Marking Quantities, See Marking & Signing Plan
 For Signing Quantities, See Sign Detail Sheet

REMOVAL OF EXISTING STRUCTURES * (10241000)			
STREET	STATION	OFFSET	ITEM
Broadway	45+58	57' Lt	51' Pipe
Broadway	46+96	43' Lt	SWS Inlet
Broadway	46+96	43' Lt	22' Pipe
Broadway	46+96	45' Rt	SWS Inlet
Broadway	49+50	6' Lt	Tr Manhole
Broadway	49+53	45' Lt	Ped Sig Base
Broadway	49+54	6' Lt	Signal Base
Broadway	49+54	48' Lt	Tr Manhole
Broadway	49+60	51' Rt	Tr Manhole
Broadway	49+60	52' Rt	Ped Sig Base
Broadway	49+64	58' Lt	SWS Inlet
Broadway	49+64	58' Lt	5' Pipe
Broadway	49+64	63' Rt	SWS Inlet
Broadway	49+64	63' Rt	5' Pipe
Broadway	49+94	47' Rt	Signal Base
Broadway	49+94	51' Rt	Tr Manhole
Broadway	50+05	47' Lt	Signal Base
Broadway	50+05	51' Lt	Tr Manhole
Broadway	50+44	45' Lt	Ped Sig Base
Broadway	50+45	48' Lt	Tr Manhole
Broadway	50+46	48' Rt	Ped Sig Base
Broadway	50+47	47' Rt	Tr Manhole
Broadway	50+48	6' Rt	Signal Base
Broadway	50+53	6' Rt	Tr Manhole
Broadway	52+24	33' Rt	SWS Inlet
Broadway	52+24	33' Rt	5' Pipe
Broadway	52+42	33' Rt	SWS Inlet
Broadway	52+42	33' Rt	18' Pipe
Broadway	52+48	33' Rt	SWS Inlet
Broadway	52+48	33' Lt	9' Pipe

* For Information Only Removal of Inlets, Manholes, Storm Sewer Pipe, Light Poles, and etc. shall be SUBSIDIARY to "Removal of Existing Structures."

AC PAVEMENT COLD MILLING (2" NOMINAL) (20211002)		
STREET	STA	AREA S. Y.
Broadway	56+10.00 - 56+30.00	92.6
Total		92.6

A.C. SURFACE COURSE (BM-1B POLY-MOD) 2" (20224002)		
STREET	STA	AREA S. Y.
Broadway	56+10.00 - 56+30.00	92.6
Total		92.6

CONCRETE PAVEMENT (VG) 8" (REINFORCED) (20361008)				
STREET	STA	SIDE	INTERSECTION	AREA S. Y.
Broadway	45+23.06	Rt.	Walmart Entrance	180.0
Broadway	45+58.24	Lt.	Park Entrance	129.2
Total				309.2

CONCRETE PAVEMENT 9" (REINFORCED) (20373009)		
INTERSECTION	AREA S. Y.	
Pawnee/Broadway Sta. 49+03.65 - 50+85.19	2646.9	
Total	2646.9	

CONCRETE PAVEMENT 9" (NRJD) (20372009)		
STREET	STA	AREA S. Y.
Pawnee	7+50.00 - 9+03.70	1,137.5
Pawnee	10+93.95 - 13+50.53	1,934.2
Broadway	41+00.30 - 43+91.00	2,002.1
Broadway	43+91.00 - 49+03.65	4,336.5
Broadway	50+85.19 - 56+10.00	2,960.2
Total		12,370.5

CONCRETE PAVEMENT 8" (REINFORCED) (20373008)			
STREET	STA	SIDE	AREA S. Y.
Pawnee	11+93.67	Lt	65.0
Pawnee	13+59.41	Lt	24.4
Total			89.4

Conc. &/or Asph. Sdwk, Dr, &/or Pkg Lot Removed (10122000)				
STREET	STATION	SIDE	TYPE	AREA S. Y.
Pawnee	7+22.00-9+24.36	Rt	Sidewalk	114.6
Pawnee	7+55.50-9+20.43	Lt	Sidewalk	114.9
Pawnee	8+38.22	Rt	Parking Lot	74.7
Pawnee	10+67.68-12+51.40	Lt	Sidewalk	92.9
Pawnee	10+77.10-12+68.49	Lt	Sidewalk	80.9
Pawnee	11+45.27	Lt	Drive	20.9
Pawnee	11+45.27	Lt	Parking Lot	88.9
Pawnee	11+93.65	Lt	Drive	15.2
Pawnee	11+93.65	Lt	Parking Lot	24.0
Pawnee	12+25.29	Lt	Drive	15.7
Pawnee	12+80.31	Lt	Drive	64.9
Pawnee	12+92.21-13+49.46	Lt	Sidewalk	23.4
Broadway	41+18.50	Lt	Drive	33.8
Broadway	41+18.50	Lt	Sidewalk	10.1
Broadway	41+77.00	Lt	Drive	34.3
Broadway	41+77.00	Lt	Sidewalk	10.2
Broadway	42+77.50	Lt	Drive	34.9
Broadway	42+77.50	Lt	Sidewalk	10.3
Broadway	43+91.00-45+40.62	Lt	Sidewalk	64.6
Broadway	43+91.00-44+98.19	Rt	Sidewalk	58.6
Broadway	45+23.06	Rt	Drive	115.6
Broadway	45+48.60-49+22.70	Rt	Sidewalk	218.5
Broadway	45+58.24	Lt	Drive	122.1
Broadway	45+71.23-99+26.50	Lt	Sidewalk	205.3
Broadway	46+46.60	Rt	Drive	22.1
Broadway	46+46.60	Lt	Parking Lot	27.8
Broadway	50+34.75-56+05.49	Lt	Sidewalk	336.4
Broadway	50+39.62-56+05.49	Rt	Sidewalk	269.0
Broadway	50+86.08	Lt	Drive	55.5
Broadway	51+10+29	Rt	Drive	39.3
Broadway	51+10+29-51+58.38	Rt	Parking Lot	99.0
Broadway	51+58.38	Rt	Drive	39.9
Broadway	51+61.55	Lt	Drive	50.4
Broadway	51+61.55	Lt	Parking Lot	20.0
Broadway	52+80.40	Rt	Drive	40.6
Broadway	52+80.40	Rt	Parking Lot	45.6
Broadway	52+95.45	Lt	Drive	50.3
Broadway	52+95.45	Lt	Parking Lot	45.6
Broadway	53+50.93	Rt	Drive	44.3
Broadway	53+50.93	Rt	Parking Lot	17.2
Broadway	53+65.04	Lt	Drive	56.9
Broadway	53+65.04	Lt	Parking Lot	20.0
Broadway	54+60.91	Rt	Drive	52.7
Broadway	54+61.53	Lt	Drive	69.5
Broadway	55+57.37	Rt	Drive	53.1
Broadway	55+64.51	Lt	Drive	34.5
Total				3153.1

AC PAVEMENT 6" (4" BIT BASE) (20151006) (Parking Lot)				
STREET	STATION	SIDE	TYPE	AREA S. Y.
Pawnee	8+38.22	Rt	Parking Lot	74.7
Pawnee	11+45.27	Lt	Parking Lot	88.9
Broadway	46+46.60	Lt	Parking Lot	27.8
Broadway	51+61.55	Lt	Parking Lot	20.0
Broadway	52+95.45	Lt	Parking Lot	45.6
Broadway	53+50.93	Rt	Parking Lot	17.2
Broadway	53+65.04	Lt	Parking Lot	20.0
Total				294.2

CONCRETE PAVEMENT 6" (REINFORCED) (20373006) (Pk Lt)				
STREET	STATION	SIDE	TYPE	AREA S. Y.
Broadway	51+10+29-51+58.38	Rt	Parking Lot	99.0
Broadway	52+80.40	Rt	Parking Lot	45.6
Total				144.6

AT&T MANHOLES ADJUSTED				
STREET	STA	OFFSET	Ex. ELEV.	NEW ELEV.
Broadway	50+42.4	31.2' Lt	1285.56	1286.53
Broadway	50+69.7	38.2' Lt	1285.68	1286.35