



COORDINATE TABLE					
POINT NO.	NORTH COORDINATE	EAST COORDINATE	STATION	OFFSET	DESCRIPTION
3016	1,694,233.8419	1,623,163.9605	54+26.00	34.00' Lt.	Edge of Pavement P.I.
3017	1,694,309.3224	1,623,234.4068	55+00.00	38.00' Rt.	Edge of Pavement P.I.
3018	1,694,484.1495	1,623,224.2708	56+75.00	31.50' Rt.	Edge of Pavement P.I.
3019	1,694,533.9953	1,623,168.2226	57+26.00	23.50' Lt.	Edge of Pavement P.I.
3020	1,694,535.1385	1,623,223.2108	57+26.00	31.50' Rt.	Edge of Pavement P.I.

See Sh. No. 24 for Sidewalk Coordinate Table

CONTROL POINTS					
POINT NO.	NORTH COORDINATE	EAST COORDINATE	STATION	OFFSET	DESCRIPTION
179	1,694,157.8342	1,623,149.4563	53+50.3102	50.08' Lt.	IRP
184	1,695,101.2063	1,623,130.2472	62+93.88	49.68' Lt.	IRP
185	1,695,161.1730	1,623,129.0524	63+53.86	49.63' Lt.	IRP
305	1,696,429.1556	1,623,152.3280	76+21.08	0.00' Rt.	W Corner of Sec. 10, T27S, R1W
700	1,694,243.8165	1,623,256.9604	54+34.04	59.19' Rt.	#4 bar

Plotted on: Tuesday, September 27, 2011 09:38 AM
 Plot Queue: \\svp\00\VP\FW\LP
 Plot Scale: 40,000,000:000000 Pen Table: \\svp\00\Jobs\4809\Detail\Fig\Coordinate-geom\pen\CC-23x35.pen
 Design Filename: \\svp\00\Jobs\4809\Detail\Fig\Coordinate-geom\geom\ry.dgn



**RIDGE ROAD
COORDINATE GEOMETRY
PLAN**

CITY ENGINEER
JAMES L. ARMOUR, P.E., L.S.

PROJECT NUMBER 472-84817 PHASE I	OCA NUMBER 770005	DATE 11/2011
-------------------------------------	----------------------	-----------------

CITY ENGINEER'S OFFICE
CITY HALL - SEVENTH FLOOR
455 NORTH MAIN STREET
WICHITA, KANSAS 67202-1620
(316) 268-4501

DESIGN	DRAWN
SHEET	
23 of 113	

\\svp\00\Jobs\4809\Detail\Fig\Coordinate-geom\ry.dgn