GENERAL NOTES

1. THE FIELD SURVEY INFORMATION SHOWN ON THE PLANS REPRESENT THE EXISTING TOPOGRAPHIC CONDITIONS AS BEST AS COULD BE DETERMINED. AT LOCATIONS WHERE THE NEW CONSTRUCTION IS TO MATCH EXISTING FEATURES, IT MAY REQUIRE FIELD ADJUSTMENTS OF TRANSITION LENGTHS AND PROFILE GRADES.

2. UTILITY SERVICE LINES, POLES, VALVE BOXES, METERS, ETC. ARE TO BE ADJUSTED AS NECESSARY BY OTHERS PRIOR TO CONSTRUCTION UNLESS THE PLANS SPECIFICALLY CALL FOR THEIR ADJUSTMENT BY THE CONTRACTOR OR UNLESS THE PLANS SPECIFICALLY IDENTIFY A UTILITY TO BE ADJUSTED BY ITS OWNER DURING CONSTRUCTION. EXISTING UTILITIES AND THEIR LOCATION, AS SHOWN ON THE PLANS, REPRESENT THE BEST INFORMATION OBTAINABLE FOR DESIGN. THE PLAN LOCATIONS ARE NOT GUARANTEED AND ADDITIONAL UTILITIES MAY ALSO BE ENCOUNTERED. THE CONTRACTOR WILL BE REQUIRED TO WORK AROUND EXISTING UTILITIES WITHIN THE RIGHT-OF-WAY WHICH DO NOT CONFLICT WITH PROPOSED CONSTRUCTION.

3. RUBBLE FROM THE REMOVAL OF MISCELLANEOUS STRUCTURES AND EXCESS EXCAVATION WHICH IS TO BE WASTED SHALL BE DISPOSED OF ON SITES TO BE PROVIDED BY THE CONTRACTOR. THESE SITES SHALL BE APPROVED BY THE ENGINEER AS TO SUITABILITY, APPEARANCE, AND SITE LOCATION, THAT IN THE OPINION OF THE ENGINEER, WILL LEAVE AN UNSIGHTLY APPEARANCE WILL NOT BE APPROVED.

   ALL DISPOSAL SITES MUST BE APPROVED BY THE KANSAS DEPARTMENT OF HEALTH AND ENVIRONMENT. MATERIAL EITHER STOCKPILED OR DISPOSED OF IN A FLOODPLAIN WOULD REQUIRE A KANSAS STATE BOARD OF AGRICULTURE PERMIT. ANY MATERIALS DUMPED IN WATERS OF THE UNITED STATE OR WETLANDS IS SUBJECT TO U.S. CORPS OF ENGINEERS PERMITTING REGULATIONS. ANY MATERIAL BURIED OR STOCKPILED BEYOND APPROVED CONSTRUCTION LIMITS WOULD REQUIRE ADDITIONAL ARCHAEOLOGICAL INVESTIGATIONS UNLESS BURIED IN A PREVIOUSLY APPROVED BORROW LOCATION.

4. CONTRACTOR WILL BE REQUIRED TO PROVIDE A MINIMUM ADVANCE NOTICE OF FORTY-EIGHT(48)HOURS TO UTILITY COMPANIES PRIOR TO STARTING ANY EXCAVATION AS FOLLOWS:

   KANSAS ONE CALL 1-800-344-7233 OR 687-2470(LOCAL WICHITA)

   THE CONTRACTOR MUST NOTIFY THE FOLLOWING IN CASE OF AN EMERGENCY.

COX COMMUNICATION	262-4270 OR 263-2061
SBS	1-800-870-8390
KANSAS GAS SERVICE	1-888-482-4950
WESTAR	1-800-383-1183
AQUILA	1-800-303-0752
CITY OF WICHITA(WATER & SEWER)	268-4555

   THE CONTRACTOR SHALL NOTIFY PIPELINE COMPANIES AT LEAST 24 HOURS IN ADVANCE OF ANY WORK BEING PERFORMED ACROSS AND/OR ADJACENT TO PIPELINES.

5. TREES AND SHRUBS IN PUBLIC RIGHT-OF WAY WHICH ARE IN DIRECT CONFLICT WITH PROPOSED NEW CONSTRUCTION SHALL BE REMOVED BY THE CONTRACTOR WITH THE ENGINEERS APPROVAL. TREES AND SHRUBS WHICH ARE NOT IN DIRECT CONFLICT WITH PROPOSED NEW CONSTRUCTION SHALL BE SAVED AND PROTECTED FROM DAMAGE.

6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING PROPERTY IRONS. THE CONTRACTOR WILL BE REQUIRED TO REESTABLISH ANY PROPERTY IRONS WHICH ARE DAMAGED OR DESTROYED BY HIS CONSTRUCTION OPERATIONS. SUCH IRONS SHALL BE ESTABLISHED BY A LICENSED LAND SURVEYOR IN ACCORDANCE WITH STATE LAWS.

7. THE CONTRACTOR SHALL GIVE ALL PROPERTY OWNERS AND/OR TENANTS OF DEVELOPED PROPERTY DIRECTLY ABUTTING THE CONSTRUCTION OF THIS PROJECT A MINIMUM OF TEN(10) DAYS ADVANCE NOTICE PRIOR TO START OF CONSTRUCTION.

8. THE CONTRACTOR MUST EXAMINE THE CONSTRUCTION SITE PRIOR TO BIDDING AND BE SATISFIED AS TO THE WORK SHOWN FOR COMPLETION. AFTER BIDS HAVE BEEN RECEIVED, THE CONTRACTOR SHALL NOT ASSERT THAT THERE WAS A MISUNDERSTANDING OF THE QUANTITIES OF WORK OR OF THE NATURE FOR THE WORK TO BE COMPLETED.

9. THE CONTRACTOR SHALL NOT START WORK ON THE PROJECT UNTIL THE PROJECT INSPECTOR IS ASSIGNED TO THE PROJECT AND IS PRESENT ON THE SITE. ANY WORK DONE WITHOUT INSPECTION WILL BE REQUIRED TO BE UNCOVERED FOR INSPECTION.

10. THE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL IN ACCORDANCE WITH THE CURRENT ADDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND KDOT STANDARDS TO ENSURE A SAFE WORK ZONE FOR THE TRAVELING PUBLIC.

11. MAILBOXES WITHIN THE LIMITS OF THE PROJECT SHALL BE REMOVED AND REPLACED BY THE CONTRACTOR AS APPROVED BY THE ENGINEER. CONTRACTOR WILL BE REQUIRED TO MAKE SATISFACTORY PROVISIONS FOR MAIL DELIVERY TO PROPERTIES AFFECTED BY THIS PROJECT DURING CONSTRUCTION.

12. THE CONTRACTOR WILL BE RESPONSIBLE FOR REMOVING AND REPLACING EXISTING STREET SIGNAGE AT THE BEGINNING AND END OF CONSTRUCTION. THE CONTRACTOR SHALL COORDINATE HIS ACTIVITIES WITH THE DEPARTMENT OF OPERATIONS AND MAINTENANCE FOR TEMPORARY TRAFFIC SIGNALIZATION AND REMOVAL OF INSTALLATION OF STREET SIGNAGE.

13. ALL LAWN/TURF AREAS DISTURBED BY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS SHALL BE RESTORED WITH SOD AND INSTALLATION OF EROSION CONTROL MAT. ALL WORK SHALL BE IN ACCORDANCE WITH THE CITY OF WICHITA STANDARD SPECIFICATIONS AND THE CITY OF WICHITA ADMINISTRATIVE REGULATIONS WHICH GOVERNS CLEANUP AND RESTORATION OR REPLACEMENT FOLLOWING CONSTRUCTION. ALL COST SHALL BE PAID FOR THROUGH THE LUMP SUM BID ITEM FOR "SODDING".

14. AREAS BENEATH THE PAVEMENT SHALL BE PROOF ROLLED WITH APPROVED EQUIPMENT TO IDENTIFY ANY SOFT AREAS, WHICH SHALL BE REMOVED OR AERATED TO PROVIDE A STABLE SUBGRADE. THIS WORK SHALL BE CONSIDERED SUBSIDIARY TO OTHER EARTHWORK ITEMS.

15. SAW CUTTING OF PAVEMENT SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED SUBSIDIARY TO OTHER BID ITEMS ON THE PROJECT. SAW CUTTING OF EXISTING PAVEMENT SHALL BE FULL DEPTH OF PAVEMENT.

16. THE BID ITEM "CLEARING AND GRUBBING" SHALL INCLUDE REMOVAL OF ALL GRASS AND OTHER VEGETATION WITHIN THE LIMITS OF CONSTRUCTION AND THE RIGHT OF WAY LIMITS. NO BURNING WILL BE ALLOWED ON THE PROJECT.

17. HIGH GROUND WATER MAY BE ENCOUNTERED DURING STORM SEWER CONSTRUCTION WHICH MAY REQUIRE DEWATERING. DEWATERING SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE SUBSIDIARY TO OTHER STORM SEWER BID ITEMS.

18. TEMPORARY SHORING AND/OR BRACING OF EXCAVATION SLOPES SHALL BE PROVIDED AS NECESSARY DURING CONSTRUCTION. TEMPORARY SHORING AND/OR BRACING SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE SUBSIDIARY TO OTHER STORM SEWER BID ITEMS.

19. THE CONTRACTOR SHALL PROVIDE ACCESS TO ALL ACTIVE ENTRANCES DURING CONSTRUCTION WHENEVER POSSIBLE. TEMPORARY SURFACING (GRAVEL) SHALL BE PROVIDED AND PLACED AS DIRECTED BY THE ENGINEER.

20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR AND MAINTENANCE OF THE ROADWAY, SIGNS AND ALL OTHER INCIDENTALS NECESSARY FOR THE MAINTENANCE OF TRAFFIC DURING CONSTRUCTION.

21. EXISTING PAVEMENT MARKINGS ON WOODLAWN SHALL BE REMOVED OR MASKED WHILE TRAFFIC IS SHIFTED. REPLACE PAVEMENT MARKINGS AFTER COMPLETION OF THE PROJECT.

22. SEE PROJECT SPECIAL PROVISION FOR TRAFFIC CONTROL.

Project Survey Control Data

Horizontal Project Datum:
Elevation = 377.972
Latitude = 37°40'45"
Project Coordinates x 0.999885228 =
State Plane Coordinates
Vertical Project Datum:
The National Geodetic Vertical Datum Of 1929
Datum Benchmark = USC&GS A-237 (1934)
Elevation = 401.303

At Wichita, 10.4' [3.17 m] South Of The Northwest Corner Of The Union Station, 28' [8.53 m] East Of The East Rail Of The East Track 2.3' [0.70 m] Above The Ground, 3 1/2 Rails South Of The Center Line Of Douglas Avenue Viaduct, Set Vertically In The West Wall Of The Railroad Station, In Section 21, Township 21 South, Range 1 East Of The 6th P.M.

LIST OF UTILITIES

Telephone
AT&T
154 North
Broadway
Room 210
Wichita, KS 67202
(316) 268-2008

Gas
Kansas Gas Service
1021 East 26th St.North
Wichita, KS 67219
(316) 832-3122

Power & Street Lights
Westar
1900 E. Central
P.O. Box 202
Wichita, KS 67214
(316) 261-6824

Sanitary Sewer
City of Wichita
455 N. Main, 8th Floor
Wichita, KS 67202
(316) 268-4555

Cable TV
Cox Communication
801 E. Douglas
Wichita, KS 67202
(316) 262-4270,
Ext. 169

Water
City of Wichita
455 N. Main
Wichita, KS 67202
(316) 268-4555

Traffic Signals
City of Wichita
455 N. Main, 7th Floor
Wichita, KS 67202
(316) 268-4448

Storm Sewers
City of Wichita
455 N. Main, 8th Floor
Wichita, KS 67202
(316) 268-4498

LEGEND

G = GAS MAIN
W = WATER MAIN
SS = SANITARY SEWER
SWS = STORM WATER SEWER
UGE = UNDER GROUND ELECTRIC
UGT = UNDER GROUND TELEPHONE

B.M. . . . . BENCH MARK
TELE. PED . . . . . TELEPHONE PEDESTAL
CATV . . . . . CABLE TELEVISION PEDESTAL
F.H. . . . . FIRE HYDRANT
G.M. . . . . GAS METER
. . . . . HIGH LINE POLE
ICV . . . . . IRRIGATION CONTROL VALVE
L.P. . . . . LIGHT POLE
. . . . . POWER POLE
. . . . . SIGN
W.M. . . . . WATER METER
W.V. . . . . WATER VALVE
SS M.H. . . . . SANITARY SEWER MANHOLE
SWB M.H. . . . . SOUTHWEST BELL MANHOLE
SWS M.H. . . . . STORM WATER SEWER MANHOLE
CB M.H. . . . . CATCH BASIN MANHOLE

REVISED

SEAL:

Cook, Flatt & Strobel ENGINEERS, P.A.

CFS PROJECT NO: 08-6270

CITY OF WICHITA, KANSAS
WOODLAWN ROAD
KELLOGG TO WILLOWBROOK

DATE: Mar. 2009 DESIGNED BY: GAP DRAWN BY: JMR CHECKED BY: GAP

SHEET TITLE: GENERAL NOTES & UTILITY OWNERS

PROJECT NUMBER 472-84911

FINAL PLANS

SHEET NUMBER: 2 of 36

J:\2008Proj\086270\DWGS\02 General Notes.dwg 3/14/2012 - 11:25am