



**EROSION CONTROL & SEEDING PLAN**  
SCALE: 1"=50'

**EROSION CONTROL NOTES**

1. EROSION CONTROL IS TO MEET ALL FEDERAL, STATE, COUNTY & LOCAL CODE STANDARDS.
2. CONTRACTOR SHALL PROVIDE AND PRESERVE EROSION PROTECTION THROUGHOUT PROJECT CONSTRUCTION. THE PLAN PROVIDED HERE IS FOR FINAL PROTECTION, VARIOUS PHASES OF THIS PLAN SHALL BE IMPLEMENTED OR MODIFIED TO CONTROL EROSION. MODIFICATIONS OF THE PLAN SHALL BE APPROVED BY THE OWNERS REPRESENTATIVE.
3. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND IMPLEMENTING ALL EROSION CONTROL.
4. CONTRACTOR SHALL INSTALL AND MAINTAIN A STABILIZED CONSTRUCTION ENTRANCE AT A LOCATION DETERMINED BY THE ENGINEER.
5. EROSION CONTROL MAT SHALL BE NORTH AMERICAN GREEN SC-150 OR APPROVED EQUAL. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

**CRIMPING NOTES**

1. ONCE TOPSOIL HAS BEEN PLACED, DISC/SCARIFY SOIL PRIOR TO SPREADING PRAIRIE HAY.
2. SPREAD PRAIRIE HAY (2 TONS/AC.) AND IMMEDIATELY CRIMP INTO TOPSOIL WITH SUITABLE MECHANICAL EQUIPMENT.

**EROSION CONTROL LEGEND**

- PROPOSED STORM SEWER LINE
- 1360— PROPOSED CONTOURS
- ◐ CURB INLET FILTER (5)
- — — — — BACK OF CURB PROTECTION (1850 L.F.)

**PAVING PLANS**  
**KRUG SOUTH ADDITION**  
**PHASE 3**

**EROSION CONTROL PLAN**  
SHEET TITLE  
**472-85056**  
PROJECT NUMBER

**DFL / JWC / GJA**  
DESIGNED DRAWN CHECKED

ISSUED  
**July 2012**  
REVISED

SHEET NO.  
**13 of 23**

PLOTTED: Tuesday, July 10, 2012 @ 02:28PM

J:\CIVIL\05291\DWG\PAV\PHASE 3\05291\_EROSION-PH3.DWG