



**WATER MAIN REPLACEMENT PLANS FOR
EASTBOROUGH SOUTH**

SERVICE CONNECTIONS

SHEET TITLE
448-90213
PROJECT NUMBER

DFL / JWC / JRA
DESIGNED / DRAWN / CHECKED

ISSUED
August 2012

REVISED

SHEET NO.
5 of 40

GENERAL NOTES

- ALL METERS LISTED IN THE FOLLOWING METER TABLES SHALL HAVE NEW SETTERS AND SERVICE TAPS INSTALLED TO THE PROPOSED WATER MAINS.
- ALL EXISTING AUTOMATIC READ METERS WILL BE REPLACED AS PART OF THIS PROJECT.
- SOME OLDER MANUAL READ METER SETTERS EXIST AT ADDRESSES WITHIN THIS PROJECT. IF OLD SETTERS ARE FOUND TO CONTAIN METERS, THE CONTRACTOR SHALL REPLACE THE SETTER, METER AND SERVICE TAP TO THE PROPOSED WATER MAIN. IF OLD SETTERS DO NOT CONTAIN METERS, THE SETTER SHALL BE REPLACED, A NEW SERVICE TAP SHALL BE INSTALLED TO THE PROPOSED MAIN, AND THE SETTER SHALL REMAIN EMPTY.
- IT IS POSSIBLE THAT A FEW METERS MAY BE UNCOVERED THAT ARE NOT SHOWN IN THE FOLLOWING METER TABLES AND WERE NOT PREVIOUSLY LOCATED BY SITE SURVEY OR OTHER SITE INSPECTIONS. SHOULD THOSE METERS BE CONNECTED TO EXISTING WATER LINES, A NEW SETTER AND SERVICE TAP TO THE PROPOSED MAIN MAY NEED TO BE INSTALLED. THE CONTRACTOR SHALL CONTACT CITY OF WICHITA WATER UTILITIES (316-268-4555) FOR VERIFICATION.
- EXISTING LANDSCAPING, HARDSCAPING, SOD, ETC. THAT IS DISTURBED DURING WATER SERVICE CONSTRUCTION SHALL BE REPLACED IN LIKE KIND IMMEDIATELY FOLLOWING CONSTRUCTION.

SERVICE CONNECTION SCHEDULE							
ADDRESS	ACCOUNT NUMBER	BASELINE STATION	BASELINE OFFSET	LINE NO.	LONG	SHORT	COMMENTS
MISSION ROAD							
* 46	161692	23+92.58	19.07' RT.	2		1	
51	31084	12+81.72	25.48' RT.	3		1	
51	-----	13+30.99	24.63' RT.	3		1	
51	82937	13+32.79	21.90' RT.	3		1	
48	141167	13+41.01	17.93' LT.	3	1		
48	29149	13+85.88	14.92' LT.	3	1		
* 48	141168	11+57.22	16.55' LT.	4	1		
55	30072	14+64.22	26.21' RT.	3		1	
57	31267	15+61.21	24.41' RT.	3		1	
50	28552	16+10.13	15.14' LT.	3	1		
50	88560	16+15.77	14.41' LT.	3	1		
61	29744	16+91.91	23.61' RT.	3		1	
52	61894	17+57.90	15.09' LT.	3	1		
52	63409	17+69.10	13.17' LT.	3	1		
63	32026	18+02.19	26.56' RT.	3		1	
63	32026	18+77.73	27.01' RT.	3		1	
65	28833	20+36.60	24.43' RT.	3		1	
56	47566	21+83.71	19.57' LT.	3	1		
67	40474	22+29.32	22.64' RT.	3		1	
58	36485	24+43.74	24.09' LT.	3	1		
60	38189	25+72.61	25.84' LT.	3	1		
71	39288	26+15.52	29.46' RT.	3		1	
62	39085	26+76.57	25.19' LT.	3	1		
64	38799	27+28.26	24.50' LT.	3	1		
73	50542	27+35.57	26.99' RT.	3		1	
75	40473	28+52.65	29.75' RT.	3		1	
77	59604	29+58.67	25.32' RT.	3		1	
66	54124	29+94.97	20.35' LT.	3	1		
79	61151	30+23.70	22.37' RT.	3		1	
68	74865	30+96.51	14.67' LT.	3	1		
81	61885	31+16.88	26.33' RT.	3		1	
TOTAL					14	17	

* METER IS ADJACENT TO A STREET DIFFERENT FROM HOUSE ADDRESS.

SERVICE CONNECTION SCHEDULE							
ADDRESS	ACCOUNT NUMBER	BASELINE STATION	BASELINE OFFSET	LINE NO.	LONG	SHORT	COMMENTS
DOUGLAS AVE.							
1	----	10+31.14	32.27' RT.	1		1	
* 1	65947	54+68.86	27.54' RT.	9		1	
2	60636	12+63.40	21.06' RT.	1		1	
3	29080	14+33.44	20.63' RT.	1		1	
1	29841	14+43.14	21.58' LT.	1	1		
5	43923	15+40.19	23.04' RT.	1		1	
4	29642	16+54.43	24.90' LT.	1	1		
4	-----	16+56.49	24.29' LT.	1	1		
6	30937	18+62.32	22.12' LT.	2	1		
6	30937	18+68.58	24.39' LT.	2	1		
8	56378	20+33.25	22.99' LT.	2	1		
8	56378	20+45.19	19.78' LT.	2	1		
* 9	28759	10+99.71	24.70' RT.	3		1	
* 9	29126	11+31.12	24.80' RT.	3		1	
14	43025	24+71.60	23.64' LT.	2		1	
16	40766	25+68.41	28.10' LT.	2		1	
13	42561	26+23.72	22.42' RT.	2		1	
13	42561	26+38.85	22.91' RT.	2		1	
20	47563	27+95.81	17.67' LT.	2	1		
15	38753	28+27.53	25.98' RT.	2	1		
22	86003	29+16.45	18.53' LT.	2	1		
17	39468	29+51.16	23.25' RT.	2		1	
24	47562	29+69.63	21.10' LT.	2	1		
19	45097	30+33.11	21.47' RT.	2		1	
19	65165	30+36.76	22.43' RT.	2		1	
26	42811	31+24.29	26.96' LT.	2	1		
19	45097	31+43.20	24.49' RT.	2		1	
HAMPTON ROAD							
12	30310	10+87.48	23.15' LT.	1	1		
12	30562	12+38.29	27.01' LT.	1	1		
11	49062	12+42.34	16.87' RT.	1		1	
14	30450	12+82.10	20.15' LT.	1	1		
13	77178	12+84.19	13.55' RT.	1		1	
13	75059	14+18.94	13.20' RT.	1		1	
16	39693	14+61.88	27.11' LT.	1	1		
15	29434	14+99.22	16.43' RT.	1		1	
18	29842	15+35.79	24.82' LT.	1	1		
15	29938	15+76.64	17.49' RT.	1		1	
18	136614	15+87.56	20.18' LT.	1	1		
26	28824	16+95.51	27.26' LT.	1	1		
21	30451	21+35.24	21.55' RT.	1		1	
21	30725	21+96.42	18.50' RT.	1		1	
25	56368	23+24.55	18.50' RT.	1		1	
25	58327	23+80.36	23.45' RT.	1		1	
* 29	40074	14+36.11	25.54' LT.	7		1	
TOTAL					20	24	

* METER IS ADJACENT TO A STREET DIFFERENT FROM HOUSE ADDRESS.