



Sta. 144+94 Install
42"x27"x81' CRP (RCPHE)
with End Sections
(Rotate 6° Lt.)
Remove Exist. 36" RCP
See Sh. No. 63, 101

Sta. 141+12, 27' Lt.
Adjust SWS Manhole
from Elev. 1323.86
to Elev. 1324.10

SE 1/4 Sec. 28, T26S, R1E

NE 1/4 Sec. 33, T26S, R1E

REMOVAL OF EXISTING STRUCTURES *		
STATION	SIDE	ITEM
139+59	Rt.	4-Posts
139+92	Lt.	MH, 30" x 121 LF RCP East
141+16	Rt.	Sign
141+46	Lt.	Sign
141+73	Lt.	18" CMP
141+83	Rt.	12" RCP
142+01	Lt.	Sign
142+34	Rt.	Sign
144+95	Cln.	36" RCP

* For Information Only

BM#56 Chiseled "C" on center of face of Inlet on W side of Bridgeport Circle, on N side of 37th St. N. 59' Lt. & Sta. 141+50 Elev. = 1325.01

- Utilities**
- Communications
 - Gas
 - Power
 - Sanitary Sewer
 - Telephone
 - Television
 - Water
 - LightCore
 - Kansas Gas Service
 - Westar Energy
 - Wichita Water Utilities
 - AT&T, Wichita Central Unit
 - Cox Communications
 - Wichita Water Utilities

LEGEND

Pavement Removal

No.	Revision	By	Date
37TH STREET NORTH			
PLAN			
STA. 139+00 TO STA. 145+00			
GARY JANZEN, P.E.-CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-84692			
PEC PROFESSIONAL ENGINEERING CONSULTANTS, P.A. 303 SOUTH TOPEKA WICHITA, KS 67202 316-262-2691 www.pec1.com			
Designed by	JPS	Job No.	08207
Drawn by	SVB	Date	August, 2013
			Sh. 12 of 193

Plotted By: svb Date: 8/15/2013 5:40:35 PM
FILE: I:\2008\08207\Plan\08207-PL139.dgn