

GABIONS		
Sta. to Sta.		Cu. Yds.
WEST BRANCH		
10+00	10+25	83
10+25	10+55	75
10+55	10+90	58
10+90	11+27	86
11+27	11+57	75
11+57	12+20	200
12+20	1+15	715
1+15	1+33	69
1+33	1+42	38
1+42	15+89	735
15+89	16+13	140
16+13	16+85	432
16+85	17+35	292
17+35		19
EAST BRANCH		
10+12	10+23	31
10+23	10+42	32
10+42	10+75	94
10+75	12+34.5	155
12+34.5	12+72	41
12+72	12+78	15
12+78	12+82	13
12+82	12+85	11
12+85	12+93	33
12+93	12+94	5
12+94	14+08	619
14+08	14+32	144
14+32	16+30	1,353
16+30	16+64	204
16+64	18+90	1,318
18+90	19+00	50
19+00		14
ACCESS LAKE		
10+25	10+76	83
10+75	11+06	20
Sub-Total		7,252
RENO MATTRESS		
WEST BRANCH		522
EAST BRANCH		468
ACCESS LAKE		35
Sub-Total		1,015
Total		8,267

3							
2							
1							
NO.	DATE		REVISIONS		BY	APP'D	
CITY OF WICHITA							
SUMMARY OF QUANTITIES							
SHEET NO.	OF	SCALE	APP'D				
DESIGNED		DETAILED	QUANTITIES	TRACED			
DESIGN CK.		DETAIL CK.	QUAN.CK.	TRACE CK.			

FENCE (CHAIN LINK) (4') (Plastic Coated)								
STA. TO STA.		SIDE	LIN. FT.	POST			GATE (12')	REMARKS
				COR.	END	PULL		
10+00	17+45	LT	421	4	2			WEST BRANCH DRY CREEK
10+00	17+45	RT	960	12	2			WEST BRANCH DRY CREEK
12+91	19+10	RT	718	12	2			EAST BRANCH DRY CREEK
12+91	19+10	LT	491	9	4		1	EAST BRANCH DRY CREEK
TOTAL			2,590	37	10		1	

REMOVE AND RESET FENCE/GATE (WOOD)						
STATION TO STATION		LOCATION	SIDE	LIN. FT.	EACH	REMARKS
16+50	17+35	WEST BRANCH DRY CREEK	LT	87		REMOVE & RESET EXISTING FENCE
154+19		EAST BOUND FRONTAGE Rd.	RT		1	REMOVE & RESET EXISTING GATE (15')
TOTAL				87	1	

PAVEMENT REMOVAL				
STATION TO STATION		LOCATION	AREA SQ. YDS.	SAWCUT LIN. FT.
70+21	70+92	Lincoln	327	181
70+92	99+95	Bluff Area Outfall	8,437	5,636
57+01	58+14	Pinecrest	577	93
15+83	17+35	W. Br. Dry Creek	132	313
TOTAL			9,473	6,223

FLOWABLE FILL					
STATION TO STATION		SIZE	TYPE	LENGTH LIN. FT.	REMARKS
—	—	8"	Water	48	<i>E. Side Lincoln/Broadview</i>
70+80.5	Lt. & Rt.	12"	Water	32	<i>Bluff Outfall</i>
70+21	77+78.4	6'x3'	Storm	757	<i>Bluff Outfall</i>
70+78.4	99+87.6	54"	Storm	2,209	<i>Bluff Outfall</i>
77+77	Lt. & Rt.	8"	San.	20	<i>Bluff Outfall</i>
87+11.5	Lt. & Rt.	2"	Water	20	<i>Bluff Outfall</i>
87+51.0	Lt. & Rt.	2"	Water	20	<i>Bluff Outfall</i>
12+20	12+51	8"	San.	31	<i>Line 13</i>
10+00	10+70.5	27"	San.	71	<i>Line 15</i>
10+00	10+54.2	8"	San.	44	<i>Line 14</i>
TOTAL				3,252	

CURB & GUTTER/SIDEWALK CONSTRUCTION					
STATION TO STATION		SIDE	CURB & GUTTER LIN. FT.	SIDEWALK SQ. FT.	REMARKS
70+21	70+92	Lt. & Rt.	95	88	Bluff Area Outfall
94+08 to 96+00 Belmont		Lt.	192		
57+01	58+14	Lt. & Rt.	243		Pinecrest (Includes Orme)
15+83	17+35	Rt.	154		W. Br. Dry Creek
TOTAL			684	88	