


TYLER

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+25.58	22.35	0.91				
1+50	25.36	0.77	21.58	0.76	21.58	0.76
2+00	19.14	2.44	41.20	2.97	62.78	3.73
2+50	19.07	2.04	35.38	4.15	98.16	7.88
3+00	19.51	1.58	35.72	3.35	133.88	11.23
3+50	17.75	2.42	34.50	3.71	168.38	14.94
4+00	18.26	1.98	33.34	4.08	201.72	19.02
4+50	28.20	0.52	43.02	2.32	244.74	21.34
5+00	23.50	0.17	47.87	0.64	292.62	21.97
5+50	22.42	0.13	42.52	0.28	335.13	22.25
6+00	19.54	0.32	38.85	0.42	373.98	22.68
6+50	18.14	1.77	34.89	1.94	408.87	24.61
7+00	18.60	2.22	34.02	3.69	442.88	28.31
7+50	18.80	1.91	34.63	3.82	477.51	32.13
8+00	18.26	2.58	34.32	4.16	511.83	36.29
8+50	18.44	2.85	33.99	5.03	545.82	41.32
9+00	19.17	3.00	34.83	5.41	580.65	46.73
9+50	17.79	2.41	34.23	5.01	614.87	51.74
10+00	17.78	3.04	32.94	5.05	647.81	56.79
10+50	17.43	2.37	32.60	5.01	680.41	61.80
11+00	17.81	3.98	32.63	5.88	713.04	67.67
11+33.66	20.22	1.33	23.70	3.31	736.74	70.98
11+93.64	20.25	0.69	44.95	2.25	781.69	73.23
12+00	22.12	0.70	4.99	0.16	786.68	73.39
12+50	18.42	2.51	37.54	2.96	824.22	76.36
13+00	18.34	4.68	34.04	6.65	858.26	83.01
13+50	21.56	1.96	36.94	6.15	895.20	89.15
14+00	17.80	3.88	36.44	5.40	931.65	94.56
14+38.66	18.08	4.65	25.69	6.10	957.33	100.66
			0.00	0.00	957.33	100.66

EARTHWORK QUANTITIES
TYLER PAVING
NEWTON, KANSAS



Ruggles & Bohm, P.A.

Engineering, Surveying, Land Planning

924 North Main
Wichita, Kansas 67203
www.rbkansas.com

(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN
MWS

DRAWN
TEB

REVIEW

UTILITY

DRAWING FILE
EARTHWORK

PROJECT NUMBER
472-83713/83693

DATE
Apr. 7, 2003

REVISION
14

DATE
14