Curve No. FC7500

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9500	101+27.46	36.00' Rt.	1,685,752.4874	1,649,019.9854	–	–	P.C.
9501	101+29.22	31.76' Rt.	1,685,756.7623	1,649,021.6628	–	–	½ Pt.
9502	101+33.46	30.00' Rt.	1,685,758.5990	1,649,025.8718	–	–	P.T.

Curve No. FC7501

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9503	101+65.29	30.00' Rt.	1,685,759.1962	1,649,057.6955	1,685,751.1976	1,649,057.8456	P.C.
9504	101+79.39	35.82' Rt.	1,685,753.6450	1,649,071.9031	1,685,747.8669	1,649,066.3702	½ Pt.
9505	30+49.80	15.00' Rt.	1,685,739.6913	1,649,078.0648	1,685,739.4947	1,649,070.0672	P.T.

Curve No. FC7502

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9506	30+58.15	15.00' Rt.	1,685,731.3379	1,649,078.2701	–	–	P.C.
9507	30+62.40	16.76' Rt.	1,685,727.0534	1,649,076.6176	–	–	½ Pt.
9508	30+64.15	21.00' Rt.	1,685,725.1923	1,649,072.4194	–	–	P.T.

Curve No. FC7507

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9521	108+81.54	36.00' Rt.	1,685,766.6366	1,649,773.9348	–	–	P.C.
9522	108+83.30	31.76' Rt.	1,685,770.9115	1,649,775.6122	–	–	½ Pt.
9523	108+87.54	30.00' Rt.	1,685,772.7482	1,649,779.8212	–	–	P.T.

Curve No. FC7508

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9524	109+10.04	30.00' Rt.	1,685,773.1703	1,649,802.3132	1,685,765.1717	1,649,802.4633	P.C.
9525	109+24.19	35.87' Rt.	1,685,767.5695	1,649,816.5724	1,685,761.8112	1,649,811.0188	½ Pt.
9526	30+50.05	20.50' Rt.	1,685,753.5224	1,649,822.6855	1,685,753.3829	1,649,814.6867	P.T.

Curve No. FC7509

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9527	30+57.31	20.50' Rt.	1,685,746.2636	1,649,822.8120	–	–	P.C.
9528	30+61.56	22.26' Rt.	1,685,741.9910	1,649,821.1288	–	–	½ Pt.
9529	30+63.31	26.50' Rt.	1,685,740.1600	1,649,816.9175	–	–	P.T.

Curve No. FC7513

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9539	112+61.30	36.00' Rt.	1,685,773.8883	1,650,153.6365	–	–	P.C.
9540	112+63.06	31.76' Rt.	1,685,778.1638	1,650,155.3122	–	–	½ Pt.
9541	112+67.30	30.00' Rt.	1,685,780.0022	1,650,159.5204	–	–	P.T.

Curve No. FC7514

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9542	112+99.28	30.00' Rt.	1,685,780.6152	1,650,191.4948	1,685,772.6167	1,650,191.6482	P.C.
9543	113+12.03	35.29' Rt.	1,685,775.5710	1,650,204.3392	1,685,769.8143	1,650,198.7839	½ Pt.
9544	30+48.08	13.00' Rt.	1,685,762.9144	1,650,209.8374	1,685,762.7829	1,650,201.8385	P.T.

Curve No. FC7515

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9545	30+56.44	13.00' Rt.	1,685,754.5626	1,650,209.9748	–	–	P.C.
9546	30+60.68	14.76' Rt.	1,685,750.2916	1,650,208.2874	–	–	½ Pt.
9547	30+62.44	19.00' Rt.	1,685,748.4648	1,650,204.0742	–	–	P.T.

Curve No. FC7516

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9548	30+62.21	19.00' Lt.	1,685,749.3168	1,650,242.0653	–	–	P.C.
9549	30+60.45	14.76' Lt.	1,685,751.0042	1,650,237.7944	–	–	½ Pt.
9550	30+56.21	13.00' Lt.	1,685,755.2174	1,650,235.9675	–	–	P.T.

Curve No. FC7517

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9551	30+47.92	13.00' Lt.	1,685,763.5110	1,650,235.8312	1,685,763.6425	1,650,243.8301	P.C.
9552	113+48.57	35.25' Rt.	1,685,776.3062	1,650,240.8762	1,685,770.7510	1,650,246.6329	½ Pt.
9553	113+61.28	30.00' Rt.	1,685,781.8036	1,650,253.4837	1,685,773.8051	1,650,253.6370	P.T.

Curve No. FC7518

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9554	113+80.57	30.00' Rt.	1,685,782.1733	1,650,272.7684	–	–	P.C.
9555	113+84.81	31.76' Rt.	1,685,780.4976	1,650,277.0439	–	–	½ Pt.
9556	113+86.57	36.00' Rt.	1,685,776.2895	1,650,278.8823	–	–	P.T.

Curve No. FC7519

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9557	116+50.57	36.00' Rt.	1,685,781.3499	1,650,542.8338	–	–	P.C.
9558	116+52.33	31.76' Rt.	1,685,785.6255	1,650,544.5095	–	–	½ Pt.
9559	116+56.57	30.00' Rt.	1,685,787.4638	1,650,548.7177	–	–	P.T.

Curve No. FC7520

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9560	116+77.03	30.00' Rt.	1,685,787.8561	1,650,569.1794	1,685,779.8576	1,650,569.3328	P.C.
9561	116+91.18	35.86' Rt.	1,685,782.2686	1,650,583.4331	1,685,776.5051	1,650,577.8850	½ Pt.
9562	30+50.01	13.00' Rt.	1,685,768.2380	1,650,589.5592	1,685,768.0867	1,650,581.5606	P.T.

Curve No. FC7521

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9563	30+58.36	13.00' Rt.	1,685,759.8906	1,650,589.7171	–	–	P.C.
9564	30+62.60	14.76' Rt.	1,685,755.6155	1,650,588.0403	–	–	½ Pt.
9565	30+64.36	19.00' Rt.	1,685,753.7782	1,650,583.8317	–	–	P.T.

Curve No. FC7531

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9593	129+40.21	36.00' Rt.	1,685,806.3889	1,651,832.2450	–	–	P.C.
9594	129+41.97	31.76' Rt.	1,685,810.6649	1,651,833.9196	–	–	½ Pt.
9595	129+46.21	30.00' Rt.	1,685,812.5044	1,651,838.1273	–	–	P.T.

Curve No. FC7532

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9596	129+56.88	30.00' Rt.	1,685,812.7117	1,651,848.7958	1,685,804.7132	1,651,848.9513	P.C.
9597	129+71.03	35.86' Rt.	1,685,807.1297	1,651,863.0491	1,685,801.3640	1,651,857.5032	½ Pt.
9598	129+76.88	50.00' Rt.	1,685,793.1040	1,651,869.1806	1,685,792.9486	1,651,861.1821	P.T.

Curve No. FC7533

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9599	132+02.70	41.03' Rt.	1,685,806.4575	1,652,097.7777	1,685,798.4667	1,652,094.3944	P.C.
9600	132+11.41	44.86' Rt.	1,685,802.7982	1,652,103.5620	1,685,796.8984	1,652,098.1591	½ Pt.
9601	132+15.66	53.37' Rt.	1,685,794.3689	1,652,107.9779	1,685,793.2859	1,652,100.0516	P.T.

PRINTS ISSUED

DATE	PURPOSE	NO.
12.02.16	FOR BID	

DOUGLAS AVE.
STREETSCAPE
IMPROVEMENTS
WICHITA, KS

LKArchitecture

Architecture • Engineering • Planning • Interior Design • Landscape Architecture

LK Architecture Inc. ©
345 RIVERVIEW,WICHITA,KS 67203
Phone (316) 268-0230 Fax: (316) 268-0205

CONTACT: Jeffery A. Best, ASLA

PROJECT NUMBER:
15749.01

SHEET TITLE:
COORDINATE GEOMETRY

SHEET NUMBER:
C10

PEC PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
303 SOUTH TOPEKA WICHITA, KS 67202
316-262-2691 www.pec1.com