

AC PAVEMENT 7" (5" BIT. BASE)				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
14+03.55	16+06.58	203.0	Varies 904.9	
18+07.03	18+06.72	50.7	Varies 60.5	
18+11.70	18+12.10	64.1	Varies 79.5	
21+35.43	51+92.76	3057.3	Varies 19257.6	
52+12.63	62+63.54	1050.9	Varies 4542.7	
TOTALS (S.Y.)				24845.2

*Medians on Kellogg

*AC PAVEMENT 6" (4" BIT. BASE)				
STATION to STATION	SIDE	WIDTH (FT)	S.Y.	
14+03.55	17+56.58	Lt.	5.0	212.6
14+03.55	14+40.98	Rt.	5.0	20.7
14+66.31	15+48.95	Rt.	5.0	45.7
15+74.21	17+59.23	Rt.	5.0	118.4
TOTALS (S.Y.)				397.4

*Shoulders South of Kellogg

*AC PAVEMENT 5"				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
22+74.32	22+74.32	7.2	27.8	49.5
28+14.18	28+15.77	35.5	24.7	69.2
41+55.50	41+55.89	30.0	25.2	90.5
50+01.65	50+01.56	40.6	56.7	125.2
50+02.60	50+02.60	20.0	31.0	53.9
54+20.29	54+20.29	44.0	44.4	217.5
56+72.34	56+72.34	9.7	38.0	29.2
TOTALS (S.Y.)				635.0

*Sideroad Transitions

CONCRETE PAVEMENT (9"X)(REINFORCED)				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
16+06.58	17+60.41	153.8	Varies	1081.7
18+58.75	21+35.43	276.7	Varies	2425.2
51+92.76	52+12.63	19.9	Varies	123.7
TOTALS (S.Y.)				3630.6

CONCRETE PAVEMENT (8"X)(REINFORCED)				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
19+90.35	20+14.08	3.0	11.1	
20+53.70	20+81.08	3.0	9.8	
22+55.70	22+60.35	3.0	4.8	
22+60.89	22+63.36	Varies	10.5	
TOTALS (S.Y.)				36.2

*3.0' Apron Behind Curb & Gutter at QT Entrance
*Kellogg Drive Entrance to QuikTrip

CONCRETE PAVEMENT (VG)(8"X)(REINFORCED)				
STATION	SIDE	WIDTH (FT)	S.Y.	
22+74.32	Rt.	Varies	132.2	
28+14.18	Rt.	Varies	112.4	
41+55.50	Rt.	Varies	114.0	
50+01.78	Lt.	Varies	263.4	
50+02.60	Rt.	Varies	166.1	
54+20.29	Lt.	Varies	212.8	
TOTALS (S.Y.)				1000.9

*CRUSHED ROCK BASE 5" REINFORCED				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
22+74.32	22+74.32	7.2	27.8	58.1
28+14.18	28+15.77	35.5	24.7	96.7
41+55.50	41+55.89	30.0	25.2	125.5
50+01.65	50+01.56	40.6	56.7	150.2
50+02.60	50+02.60	20.0	31.0	69.5
54+20.29	54+20.29	44.0	44.4	257.9
56+72.34	56+72.34	9.7	38.0	38.2
TOTALS (S.Y.)				796.1

*For Sideroad Transitions

CRUSHED ROCK BASE 6" REINFORCED				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
16+06.58	17+60.41	153.8	Varies	1081.7
18+58.75	21+35.43	276.7	Varies	2754.3
20+14.08	19+90.35	29.3	3.0	11.1
20+53.70	20+81.08	25.6	3.0	9.8
22+55.70	22+60.35	14.8	3.0	4.8
51+92.76	52+12.63	19.9	Varies	139.2
TOTALS (S.Y.)				4000.9

*Driveway Aprons for QuikTrip

CRUSHED ROCK BASE 7" REINFORCED				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
20+33.87	20+33.87	Varies	Varies	344.9
22+60.89	22+63.36	Varies	Varies	10.5
22+74.32	22+74.32	Varies	Varies	141.6
28+14.18	28+16.42	Varies	Varies	121.0
41+55.50	41+55.50	Varies	Varies	122.5
50+01.78	50+01.78	Varies	Varies	274.5
50+02.60	50+02.60	Varies	Varies	176.4
54+20.29	54+20.29	Varies	Varies	223.1
56+72.34	56+72.34	Varies	Varies	147.1
TOTALS (S.Y.)				1551.1

CRUSHED ROCK BASE 8" REINFORCED				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
14+03.55	16+06.58	203.0	Varies	904.9
18+05.00	114.8	Varies	140.0	
21+35.43	51+92.76	3057.3	Varies	21472.7
52+12.63	62+63.54	1050.9	Varies	5126.1
TOTALS (S.Y.)				27643.7

*Medians on Kellogg

*CRUSHED ROCK BASE 9" REINFORCED				
STATION to STATION	LENGTH (FT)	WIDTH (FT)	S.Y.	
14+03.55	17+56.58	382.7	6.0	254.6
14+03.55	14+40.98	37.3	6.0	25.1
14+66.31	15+48.95	82.3	6.0	55.4
15+74.21	17+59.23	213.1	6.0	141.9
TOTALS (S.Y.)				477.0

*Base for 6" Asphalt Shoulders

CONCRETE RAMP NOSE SECTION (MEDIAN)			
STATION	SIDE	EA.	
18+77.78	€	1	
20+86.86	€	1	
TOTALS (EA.)			2

PIPE, ABANDONED IN PLACE			
STATION to STATION	L.F.		
16+95.52	17+15.67	44.6	
58+49.49	58+55.77	50.2	
TOTALS (L.F.)			94.8

CONCRETE SIDEWALK 4"					
STATION to STATION	SIDE	LENGTH (FT)	WIDTH (FT)	S.F.	
18+71.55	20+09.88	Rt.	138.3	6.0	868.0
20+57.86	22+52.45	Rt.	373.7	6.0	1283.9
22+96.81	24+59.50	Rt.	139.2	6.0	835.4
45+07.78	49+76.88	Rt.	469.1	6.0	2838.0
50+28.27	56+41.76	Rt.	613.5	6.0	3714.9
TOTALS (S.F.)					9540.2

CONCRETE SIDEWALK 5"					
STATION to STATION	SIDE	LENGTH (FT)	WIDTH (FT)	S.F.	
18+70.40	36+30.95	Lt.	1760.6	10.0	17818.9
36+50.23	49+65.79	Lt.	1315.6	10.0	13150.7
50+35.56	53+87.08	Lt.	351.5	10.0	3807.7
TOTALS (S.F.)					34777.3

CONCRETE SIDEWALK 4" THICKENED EDGE				
STATION to STATION	SIDE	LENGTH (FT)	S.F.	
24+34.60	27+96.66	Rt.	364.5	
28+30.94	29+28.99	Rt.	100.9	
29+63.30	31+67.99	Rt.	204.7	
32+07.99	41+41.14	Rt.	938.2	
41+69.85	45+07.78	Rt.	343.1	
TOTALS (L.F.)				1951.4

CONCRETE SIDEWALK 5" THICKENED EDGE				
STATION to STATION	SIDE	LENGTH (FT)	S.F.	
54+53.51	62+63.54	Lt.	815.1	
TOTALS (L.F.)				815.1

CONCRETE DRIVEWAY 8" REINFORCED				
STATION	SIDE	WIDTH (FT)	S.F.	
14+53.64	Rt.	18.0	411.4	
15+64.41	Rt.	18.0	381.9	
20+33.87	Rt.	Varies	2496.1	
27+91.60	Rt.	12.0	187.9	
29+45.49	Rt.	15.0	694.8	
31+87.99	Rt.	22.0	350.0	
36+40.56	Lt.	15.0	526.7	
56+72.34	Rt.	Varies	1043.9	
TOTALS (S.F.)				6092.7

BRICK PAVERS					
STATION	SIDE	STATION	SIDE	S.Y.	
18+71.43	Rt.	18+70.52	Lt.	127.5	
18+87.78	€	20+86.86	€	188.0	
52+02.69	Rt.	52+02.69	Lt.	61.4	
TOTALS (S.Y.)					376.9

CONCRETE C&G, COMB. TYPE I (6" & 1-1/2")				
STATION to STATION	SIDE	LENGTH (FT)	S.F.	
18+59.39	49+48.33	Lt.	3135.8	
18+60.90	19+91.46	Rt.	255.7	
20+80.09	22+38.96	Rt.	249.4	
22+86.67	22+86.90	Rt.	22.3	
23+17.24	27+77.93	Rt.	460.7	
28+03.26	28+05.02	Rt.	35.6	
28+26.51	28+25.10	Rt.	35.5	
28+50.43	41+19.00	Rt.	1268.6	
41+44.34	41+45.47	Rt.	44.0	
41+66.37	41+67.23	Rt.	44.0	
41+92.00	49+57.83	Rt.	765.9	
49+73.96	49+75.27	Lt.	31.6	
49+88.16	49+88.58	Rt.	20.0	
50+16.61	50+17.00	Rt.	20.0	
50+28.02	50+28.94	Lt.	31.6	
50+47.33	56+56.51	Rt.	633.9	
50+53.11	53+69.08	Lt.	316.0	
53+99.41	53+98.71	Lt.	51.3	
54+40.92	54+41.18	Lt.	52.2	
54+71.51	62+63.54	Lt.	792.3	
56+56.84	56+57.14	Rt.	9.7	
56+87.21	56+94.25	Rt.	13.5	
56+98.42	58+45.08	Rt.	185.8	
TOTALS (L.F.)				8475.4

CONCRETE C&G, COMB. TYPE II (6-5/8" & 1-1/2")				
STATION to STATION	SIDE	LENGTH (FT)	S.F.	
56+31.51	57+12.54	Rt.	81.0	
TOTALS (L.F.)				81.0

CONCRETE C&G, COMB. TYPE III (8" & 1-1/2"), MEDIAN				
STATION to STATION	SIDE	LENGTH (FT)	S.F.	
18+87.84	20+86.86	Lt.	199.1	
18+87.84	20+86.86	Rt.	199.1	
50+01.81	50+01.66	Lt.	91.0	
TOTALS (L.F.)				489.2

WHEELCHAIR RAMPS W/ DETECTABLE WARNINGS				
STATION	OFFSET	SIDE	EA	
18+70.40	72.17'	Lt.	1	
18+71.55	72.69'	Rt.	1	
20+09.88	67.59'	Rt.	1	
20+57.86	67.65'	Rt.	1	
20+73.56	89.23'	Rt.	1	
22+52.45	55.77'	Rt.	1	
22+96.81	49.12'	Rt.	1	
27+94.59	47.95'	Rt.	1	
28+33.78	47.92'	Rt.	1	
41+37.26	52.49'	Rt.	1	
41+73.72	52.51'	Rt.	1	
49+65.28	50.58'	Lt.	1	
49+76.88	47.00'	Rt.	1	
50+28.27	47.00'	Rt.	1	
50+36.02	50.95'	Lt.	1	
52+02.69	36.50'	Rt.	1	
52+02.69	36.50'	Lt.	1	
53+87.08	47.49'	Lt.	1	
54+53.51	47.50'	Lt.	1	
56+41.76	33.50'	Rt.	1	
TOTALS (EA.)				20

CONCRETE FLUME			
STATION to STATION	WIDTH (FT)	L.F.	
53+68.05	53+69.62	Varies 9.8	
TOTALS (L.F.)			9.8

RIPRAP, LIGHT STONE			
STATION	SIDE	S.Y.	
18+76.26	Lt.	12.3	
29+24.01	Lt.	200.6	
50+70.63	Rt.	7.3	
57+45.28	Rt.		