



FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	97 N 0229-01 CMQ-N022 (901)	2002	34	62



Phase 2 permanent widening, south half of Harry.

Phase	Handling of Traffic	Major Construction Items	Remarks
2	Move traffic to the north half of Harry.	New pavement constructed on the south half of Harry. (Complete paving project). Complete remaining storm sewer system.	Contractor to maintain access to properties. Paving operations shall be phased at entrances to allow continued access. Existing traffic movements will be utilized during construction with grade differences being adjusted temporarily with the use of asphalt ramps. No more than two (2) consecutive side streets (S) may be closed at any time.

General Notes

All signs and pavement markings conflicting with this traffic control shall be covered or removed as directed by the engineer.


As the various construction activities progress, certain situations may arise which will preclude adhering to the original construction sequences or which in the opinion of the contractor, would readily adapt themselves to a more efficient phasing operation. Should this occur, the contractor may submit to the engineer an alternate plan for approval.

Two way traffic will be maintained on Harry Street at all times. Asphalt used in the in the construction of any temporary pavement shall be standard City of Wichita base mix consistency with thickness determined in the field. NO COLD PATCH OR MILLINGS ALLOWED.

Contractor shall maintain existing drainage system nearly as possible during construction, or supplement the existing system with temporary pipes. Temporary pipes shall be removed or filled per City Standards before final construction.



HARRY
Construction Staging and Sequencing – Phase 2
WICHITA, KANSAS



Ruggles & Bohm, P.A.

Engineering, Surveying, Land Planning

924 North Main
Wichita, Kansas 67203
www.rbkansas.com

(316) 284-8008
(316) 284-4821 fax
E-mail: info@rbkansas.com

DRAWING FILE
BASE-traffic
[const_sequencing2]

PROJECT NUMBER
472-83686

DESIGN
MWS
DRAWN
MWS
REVIEW
UTILITY

DATE
May 4, 2004

SHEET
34
OF
62