

	BY	DATE
REFERENCES NOTED		
REFERENCES CHECKED		

- Kansas One-Call* *316-687-2470 or 1-800-DIG-SAFE*

<i>Cox Communications</i>	262-4270 or 263-2061
<i>Kansas Gas Service</i>	383-8650
<i>KGE Electric</i>	383-8600
<i>Peoples Natural Gas Company</i>	942-8350 or 263-8161
<i>Southwestern Bell Telephone Company</i>	1-571-2611
<i>City of Wichita Water Department</i>	268-4908
<i>City of Wichita Sewer Maintenance</i>	268-4071

- 11. All salvageable drainage pipes, manhole rings and covers, and inlet grates shall be carefully removed and stockpiled at locations within the right-of-way as directed by the Engineer for removal by City personnel.*
- 12. Contractor shall arrange for the replacement of section monuments as indicated on the plans according to the monument box detail on sheet 3.*
- 13. Mailboxes within the limits of the project which are in direct conflict with proposed new construction shall be removed by the contractor with the Engineer's approval and placed in the owner's yard. This work shall be completed according to the special provision for mailbox adjustments. All mailboxes within the project limits shall have a non-hazardous support, and are to be re-installed by the Contractor.*
- 14. Connection of proposed storm sewer to existing storm sewer and existing structure shall be Subsidiary to new pipe being connected to. Also pipe plugs to be Subsidiary to the project.*
- 15. Driveways replaced with this project shall be a minimum of 3.65m in width.*
- 16. Neither the City of Wichita nor the contractor shall be responsible for moving and resetting fences that are on the public right of way. The property owner shall be notified prior to construction to move the fence. If the fence is not removed by the time of construction, the contractor shall remove the fence and it will become the property of the contractor.*
- 17. Contractor to contact Wichita Metro Transit Authority (WMTA) prior to construction to arrange removal and replacement of bus stop benches.*
- 18. Contractor shall maintain two-way traffic during the project for the entire length of the project. All Traffic control shall be Subsidiary to the bid item 'Traffic Control'.*
- 19. The Contractor shall adjust Water Valve Boxes and Fire Hydrants as directed by the Engineer at the price bid for said adjustments. The Water Department shall field locate water valves one time during construction when requested by the Contractor. It shall be the Contractor's responsibility to preserve such field locations during the construction process. Water valves, water valve boxes or fire hydrants damaged during construction shall be repaired by the Contractor at his own expense.*
- 20. The Contractor shall adjust Monitor Wells to match new construction. Coordination of well adjustments shall be planned with the Kansas Department of Health and Environment. Contact Kyle Parker, 337-6045 prior to construction.*

KGE
1900 East Central
P.O. Box 208
Wichita, KS 67202
316-261-6251
Contact: Russ Chitwood

*Kansas Gas Service
1021 East 26th Street North
P.O. Box 208
Wichita, KS 67201
316-832-3121
Contact: Charlene Lawless*

*Cox Communications
701 East Douglas
Wichita, KS 67202
316-262-4270
Contact: Behrouz Dahem*

Southwestern Bell Telephone Co.
154 North Broadway
Wichita, KS 67202
316-268-2245
Contact: Greg Sharpe

*Stormwater Utility
City of Wichita
City Hall – 8th Floor
455 North Main
Wichita, KS 67202
316-268-4498
Contact: Chris Carrier*

Dept. of Water & Sewer
City of Wichita
City Hall - 8th Floor
455 North Main
Wichita, KS 67202
316-268-4555
Contacts: LaDonna Lawrenz (Sewer)
Bill Perkins (Water)

*Traffic Engineering
City of Wichita
City Hall - 7th Floor
455 North Main
Wichita, KS 67202
316-268-4446
Contact: Mike Tallman*

*Sedgwick County Emergency
Management Agency
535 N. Main, Suite B10
Wichita, KS 67203-3702
316-383-7546
Contact: Jack Kegley*

Wichita Metro Transit Authority (WMTA)
777 E Waterman St.
Wichita, KS 67202-4615
316-265-1450
Contact: Al Hill

Kansas Department of Health and Environment
316-337-6045
fax 316-337-6023
Contact: Kyle Parker

CENTRAL & RIDGE ROAD INTERSECTION IMPROVEMENTS GENERAL NOTES						
	824 NORTH MAIN WICHITA, KANSAS 67203 http://www.srb.com - web		316-266-8008 FAX 266-4621 E-MAIL esrb@esrb.com		REVISED	
	SAVOY, RUGGLES & BOHM, P. A. ENGINEERING & SURVEYING					New Plan General Notes 2
	PROJECT NUMBER 472-76-245-83057-000-000-001					
DRAWN JRA	DESIGN CMB	REVIEW	DATE DEC 13, 2000	UTILITY SRB JOB 1218T	New Plan General Notes 118	