













	BY	DATE
REFERENCES NOTED		
REFERENCES CHECKED		



STATE	PROJECT NO.	YEAR	SHEET NO	TOTAL SHEETS
KANSAS	472-83519-PHASE II	2003	8	9



- NOTE:
1. ANCHOR BOLTS FOR THE SIGNAL POLE SHALL BE TACK WELDED TOGETHER IN A 400 OR 500 MM DIA. BOLT PATTERN (ON CENTERS AS SHOWN) TO MAINTAIN REEDED BOLT CONFIGURATION PATTERN AND TO AID IN VERTICAL POSITIONING WHILE CONCRETE BASE IS POURED.
2. USE ANTI-SIZEOUP GROUND ON ALL THREADS.
3. 3.7 m x 20 mm GROUND ROD TO BE POSITIONED BEFORE POURING BASE.
4. CLASS 'A' CONCRETE SHALL BE USED TO CONSTRUCT BASE.
5. CONSTRUCT A 150 mm THICK x 914 mm SQUARE CONCRETE CAP AFTER POLE HAS BEEN ERECTED & PLUMBED. CHAMFER EDGES 25 mm. MUST BE APPROVED BY DING BEFORE POURING.
6. CONDUIT SHALL HAVE PLASTIC (OR METAL) BUSHING (ABOVE BASE) TO PREVENT CABLE CHAFING.
7. USE #6 BARE COPPER GROUND CONDUCTOR FROM CLAMP TO GROUND ROD IN ACCESS HOLE.

PROJECT DESCRIPTION	
STEEL SIGNAL POLE ASSEMBLY DETAILS	
PROJECT NUMBER	
472-83519-PHASE II	
DRAWN BY: T.M.	APPROVED BY
DATE: FEB. 96	REVISD BY: T.M.
DATE: MAY97	
CITY OF WICHITA	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF TRAFFIC ENGINEERING	SCALE
WM. G. MCKINLEY TRAFFIC ENGINEER	NO SCALE