

[illegible]

RECAPITULATION OF MATERIALS		
ITEMS	TOTAL	UNIT
Sign Face, (High Intensity HA Reflective Sheeting)	7.67	m ²
Steel "U" Channel Sign Post	—	m
Breakaway Sign Post, 45 mm x 45 mm	61.80	m
Breakaway Anchor Sleeve, 60 mm x 60 mm x 450 mm	10.80	m
Breakaway Sign Post Anchor, 50 mm x 50 mm x 900 mm	21.60	m

PAVEMENT INSTALLATION SEQUENCE

1. SIGN POST ANCHOR DRIVEN INTO SUBGRADE PRIOR TO THE PLACEMENT OF THE PAVEMENT.
2. ANCHOR SLEEVE DRIVEN INTO SUBGRADE OVER THE SIGN POST ANCHOR PRIOR TO THE PLACEMENT OF THE PAVEMENT.
3. INSERT SIGN POST INTO THE SIGN POST ANCHOR AND BOLT IN PLACE.

GROUND INSTALLATION SEQUENCE

1. SIGN POST ANCHOR DRIVEN INTO THE GROUND.
2. ANCHOR SLEEVE DRIVEN INTO THE GROUND OVER THE SIGN POST ANCHOR.
3. INSERT SIGN POST INTO THE SIGN POST ANCHOR AND BOLT IN PLACE.

NOTE: IN ALL INSTALLATIONS THE FIRST HOLE ABOVE THE FINISHED GRADE LEVEL IN ALL THREE UNITS MUST BE IN LINE FOR INSERTION OF THE BOLT.

ALL BOLTS AND NUTS FOR FASTENING THE SIGNS AND SIGN POST ASSEMBLY SHALL COMPLY WITH SECTION 1614 AND ALL WASHERS SHALL COMPLY WITH SECTION 1614 OF THE STANDARD SPECIFICATION FOR STATE ROAD AND BRIDGE CONSTRUCTION (1990 EDITION) AND SHALL BE SUBSIDIARY ITEM.



SIGN DESCRIPTION			
CLASSIFICATION	TYPE	SIZE	AREA
R1-1	STOP SIGN	750 x 750	0.56 m ²
R2-1	SPEED LIMIT	600 x 750	0.45 m ²
OM-1	OBJECT MARKER	450 x 450	0.20 m ²
W1-1R	RIGHT ARROW	450 x 450	0.20 m ²
W3-3	SIGNAL	750 x 750	0.56 m ²
W3-3P	SIGNAL AHEAD	450 x 600	0.27 m ²
W5-4	BIKEWAY NARROWS	450 x 450	0.20 m ²

NOTE: ALL LETTER, NUMBER, & SYMBOL SIZES, SPACING, & COLORS AND THE SIGN COLORS SHALL CONFORM TO THE CURRENT "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."

ALL SIGN MATERIAL TO BE 0.002 mm ALUMINUM.

WICHITA, KANSAS			
SIGNING DETAILS			
JOB NO.	DATE:	CH'KD:	
SCALE: NONE	DRAWN:	APP'VD:	SH. 69 OF 107