

INLET & MANHOLE DATA

ROUTING SEQUENCE		LOCATIONS OF INSTALLATIONS			CONSTRUCT OR INSTALL										DIMENSIONS				ELEVATIONS		INFLOW CONDUITS						OUTFLOW CONDUITS		FOR INFORMATION ONLY						REMARKS	
		STATION	ROUTE IDENTIFICATION	DISTANCE LEFT/RIGHT	INLET (TY.12) (CURB)	INLET (TY.12) (SPEC)	INLET (TY.22) (CURB)	INLET (TY.1A) (CURB)	REINF. CONC. M.H.		M.H. (STD.) (TY.B)	END SECT. *	G & F A (TYPE)	L & F A (TYPE)	L. (FT.)	W. (FT.)	H. (FT.)	HT. (FT.)	TOP	FLOOR	SIZE DIRECTION	FLOWLINE (ELEV.)	SIZE DIRECTION	FLOWLINE (ELEV.)	SIZE DIRECTION	FLOWLINE (ELEV.)	SIZE DIRECTION	FLOWLINE (ELEV.)	NO STEP	CAST IRON (LBS.)	STRUC. STEEL (LBS.)	REINF. STEEL (LBS)	CLASS'S A' CONC. (MISC.) (CU.YD.)	CL. III EXC. (CU.YD.)		
35	36	77+00.00	WEBB	25.5' LT.				1						11'-4"	4'-4"			223.62	218.62									15"-E.	219.05							
36	39	77+00.00	WEBB	36.5' RT.										11'-4"	4'-4"			222.97	218.47	15"-W.	218.78							18"-N.	218.53							
37	38	81+25.00	WEBB	25.5' LT.				1						11'-4"	4'-4"			221.92	216.92									21"-E.	217.00							
38	39	81+25.00	WEBB	25.5' RT.				1						11'-4"	4'-4"			221.92	215.92	21"-W.	216.78							30"-E.	216.03							
39	41	81+27.75	WEBB	39.08' RT.					1					5'-8"	5'-2"					30"-W.	216.00	18"-S.	217.00					36"-N.	215.50							
40	40A	86+27.50	WEBB	25.5' LT.				1						6'-4"	4'-4"			222.32	217.90									15"-NW.	218.40							
41	43	88+66.50	WEBB	36.5' RT.				1						11'-4"	7'-4"			221.01	211.66	36"-S.	213.16							48"-N.	212.16							
42	43	88+75.00	WEBB	25.5' LT.				1						11'-4"	4'-4"			221.32	212.00									23"x14"-E.	212.50							
43	44	88+83.50	WEBB	36.5' RT.				1						11'-4"	7'-4"			221.01	211.51	23"x14"-W.	212.23	48"-S.	212.10					36"-N.	212.00							
44	45	89+87.50	WEBB	40.17' RT.					1					5'-8"	5'-8"			222.00	211.00	36"-S.	211.19							36"-E.	211.09							
45	46	5+84.00	AIRPORT PL.							1				5'-0"	DIA.			220.7	206.52	36"-W.	206.52							36"-E.	206.52							
46		0+00.00	AIRPORT PL.								1																	36"-E.	202.00							
		TOTALS						8	2		1	1																								

CONDUIT DATA

ROUTING SEQUENCE		LOCATIONS OF INSTALLATIONS			CONSTRUCT OR INSTALL		CONDUIT FLOW LINES		SEWER EXCAVATION		STORM SEWERS (LIN. FT.)										END SECTIONS (EACH)				AASHTO CONC. CLASS	METAL PIPE GAGE					REMARKS
		STATION	ROUTE IDENTIFICATION	DISTANCE RT./LT.	TYPE OF CONDUIT		LENGTH (FEET)	INFLOW (ELEV.)	OUTFLOW (ELEV.)	ROCK (CU.YDS.)	COMMON (CU.YDS.)	REINF. CONC.										REINF. CONC.		CORR. METAL							
FROM	TO				SIZE	MATERIAL						15"	18"	21"	30"	36"	48"	1.5Sq.Ft									15"	18"	36"		
35	36	77+00.00	WEBB	25.5' LT.	15"	RCP	67	219.05	218.78			67																			
36	39	77+00.00	WEBB	36.5' RT.	18"	RCP	425	218.53	217.00				425																		
37	38	81+25.00	WEBB	25.5' LT.	21"	RCP	56	217.00	216.78					56																	
38	39	81+25.00	WEBB	25.5' RT.	30"	RCP	12	216.03	216.00						12																
39	41	81+27.75	WEBB	39.08' RT.	36"	RCP	739	215.50	213.16							739															
40	40A	86+27.50	WEBB	25.5' LT.	15"	RCP	29	218.40	218.25			29																			
41	43	88+66.50	WEBB	36.5' RT.	48"	RCP	17	212.16	212.10							17															
42	43	88+75.00	WEBB	25.5' LT.	1.5Sq.Ft.	RCPHE	68	212.50	212.23								68														
43	44	88+83.50	WEBB	36.5' RT.	36"	RCP	104	212.00	211.19							104															
44	45	89+87.50	WEBB	40.17' RT.	36"	RCP	590	211.09	206.52							590															
45	46	5+84.00	AIRPORT PL.		36"	RCP	584	206.52	202.0							584															
46		0+00.00	AIRPORT PL.																	1											