

FHWA REGION NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	87N-0094-01	1998	117	202

STA. TO STA.		ROADWAY	SIDE	WDTH (m)	QUANTITY (m²)	REMARKS
+134.228	+222.365	Central	Lt.	1.8	165.3	Qty. Includes Sidewalk Ramp
+240.653	+245.074	Central	Lt.	1.8	14.9	Qty. Includes Sidewalk Ramp
+291.649	+292.971	Central	Lt.	1.8	2.4	
+298.724	+314.658	Central	Lt.	1.8	28.9	Qty. Includes Sidewalk Ramp
+332.054	+335.541	Central	Lt.	1.8	22.5	Qty. Includes Sidewalk Ramp
+342.851	+353.531	Central	Lt.	1.8	19.2	
+423.489	+416.296	Central	Lt.	1.8	78.0	Qty. Includes Sidewalk Ramp
+434.583	+496.188	Central	Lt.	1.8	83.1	Qty. Includes Sidewalk Ramp
+503.498	+520.148	Central	Lt.	1.8	40.6	Qty. Includes Sidewalk Ramp
+541.708	+563.612	Central	Lt.	1.8	48.0	Qty. Includes Sidewalk Ramp
+571.162	+581.025	Central	Lt.	1.8	17.8	
+586.969	+601.412	Central	Lt.	1.8	26.0	
+609.559	+631.526	Central	Lt.	1.8	52.1	Qty. Includes Sidewalk Ramp
+651.149	+681.594	Central	Lt.	1.8	67.6	Qty. Includes Sidewalk Ramp
+690.719	+702.329	Central	Lt.	1.8	20.9	
+702.329	+715.578	Central	Lt.	1.5	21.5	
+729.830	+740.311	Central	Lt.	1.5	15.7	
+754.385	+757.395	Central	Lt.	1.5	4.5	
+77.812	+786.907	Central	Lt.	1.5	22.6	Qty. Includes Sidewalk Ramp
+786.907	+791.652	Central	Lt.	1.8	15.2	Qty. Includes Sidewalk Ramp
+814.703	+848.259	Central	Lt.	1.8	71.3	Qty. Includes Sidewalk Ramp
+853.021	+880.061	Central	Lt.	2.4	69.6	Qty. Includes Sidewalk Ramp
+881.707	+902.534	Central	Lt.	2.4	58.0	Qty. Includes Sidewalk Ramp
+920.821	+931.581	Central	Lt.	2.4	32.7	
+938.976	+986.328	Central	Lt.	2.4	113.6	
+995.331	+1024.739	Central	Lt.	2.4	70.6	
+1024.739	+1034.303	Central	Lt.	1.5	16.4	
10.39.863	+153.687	Central	Lt.	2.4	31.9	
+1053.687	+1058.295	Central	Lt.	2.1	9.9	
+1064.491	+1073.739	Central	Lt.	2.4	22.0	
+1079.938	+1085.759	Central	Lt.	2.4	14.0	
+1092.960	+1114.910	Central	Lt.	2.4	52.7	
+1122.231	+1133.504	Central	Lt.	2.1	22.73	
+1133.504	+1143.015	Central	Lt.	2.4	22.8	
+1152.510	+1187.524	Central	Lt.	2.4	97.5	Qty. Includes Sidewalk Ramp
+1205.812	+1257.713	Central	Lt.	2.4	140.4	Qty. Includes Sidewalk Ramp
+1267.119	+1309.826	Central	Lt.	2.4	96.5	
+1319.225	+1365.648	Central	Lt.	2.4	111.4	
+1374.754	+1398.827	Central	Lt.	2.4	57.9	
+1407.727	+1424.668	Central	Lt.	2.4	38.4	
+1433.769	+1489.119	Central	Lt.	2.4	136.5	Qty. Includes Sidewalk Ramp
+1503.567	+1641.548	Central	Lt.	2.4	334.8	Qty. Includes Sidewalk Ramp
+106.276	+142.400	Central	Rt.	1.8	63.6	Qty. Includes Sidewalk Ramp
+151.568	+287.940	Central	Rt.	1.8	251.4	Qty. Includes Sidewalk Ramp
+306.220	+335.046	Central	Rt.	1.8	58.7	Qty. Includes Sidewalk Ramp
+338.691	+386.717	Central	Rt.	1.8	91.6	Qty. Includes Sidewalk Ramp
+403.066	+410.479	Central	Rt.	1.8	18.3	Qty. Includes Sidewalk Ramp
+415.047	+482.457	Central	Rt.	1.8	126.4	Qty. Includes Sidewalk Ramp
+498.992	+513.698	Central	Rt.	1.8	32.4	
+521.090	+572.273	Central	Rt.	1.8	92.1	
+576.003	+583.809	Central	Rt.	1.8	14.2	
+591.213	+605.846	Central	Rt.	1.8	26.4	
+613.625	+664.131	Central	Rt.	1.8	90.9	
+671.358	+695.103	Central	Rt.	1.8	42.7	
+699.853	+717.072	Central	Rt.	1.8	31.0	
+721.899	+741.672	Central	Rt.	1.8	35.6	
+746.256	+775.105	Central	Rt.	1.8	51.9	
+780.337	+792.275	Central	Rt.	1.8	28.1	
+813.174	+819.083	Central	Rt.	1.5	17.2	
+1010.012	+1034.755	Central	Rt.	1.5	42.1	
+1043.669	+1050.700	Central	Rt.	1.5	12.6	Qty. Includes Sidewalk Ramp
+1087.100	+1091.259	Central	Rt.	1.8	14.9	Qty. Includes Sidewalk Ramp
+1203.316	+1209.827	Central	Rt.	1.8	22.2	Qty. Includes Sidewalk Ramp
+1282.216	+1288.540	Central	Rt.	1.5	18.7	
+1299.635	+1307.437	Central	Rt.	1.5	21.9	Qty. Includes Sidewalk Ramp
+1401.971	+1441.481	Central	Rt.	1.8	76.3	Qty. Includes Sidewalk Ramp
+1446.631	+1486.725	Central	Rt.	1.8	79.3	Qty. Includes Sidewalk Ramp
+1505.013	+1527.790	Central	Rt.	1.8	46.3	Qty. Includes Sidewalk Ramp
+1538.290	+1550.976	Central	Rt.	1.8	22.8	Qty. Includes Sidewalk Ramp
+1609.792	+1647.250	Central	Rt.	1.8	82.7	Qty. Includes Sidewalk Ramp
+442.078	+457.673	Sheridan	Rt.	1.3	19.5	Qty. Includes Sidewalk Ramp
+463.568	+485.391	Sheridan	Rt.	1.3	27.5	
+513.818	+533.558	Sheridan	Lt.	1.5	29.6	Qty. Includes Sidewalk Ramp

CONCRETE PAVEMENT (200 mm UNIF) (A.E.)			
STATION	SIDE	QUANTITY (m ²)	REMARKS
+130.353	Lt.	60.8	Commercial Driveway
+146.977	Rt.	61.8	Commercial Driveway
+288.087	Lt.	42.3	Commercial Driveway
+295.869	Lt.	39.4	Commercial Driveway
+339.223	Lt.	51.4	Commercial Driveway
+412.725	Rt.	35.0	Commercial Driveway
+499.819	Lt.	54.6	Commercial Driveway
+517.382	Rt.	78.6	Commercial Driveway
+531.202	-	112.3	Q JOANN (N) (V.G. Pavm't)
+567.429	Lt.	54.4	Commercial Driveway
+584.054	Lt.	44.8	Commercial Driveway
+587.300	Rt.	53.8	Commercial Driveway
+605.553	Lt.	58.0	Commercial Driveway
+609.746	Rt.	58.3	Commercial Driveway
+640.924	-	112.3	Q GOW (N) (V.G. Pavm't)
+667.754	Lt.	55.0	Commercial Driveway
+686.124	Rt.	65.5	Commercial Driveway
+722.705	Lt.	39.9	Commercial Driveway
+747.384	Lt.	39.3	Commercial Driveway
+764.620	Lt.	40.3	Commercial Driveway
+777.949	Rt.	43.0	Commercial Driveway
+827.278	Rt.	37.3	Commercial Driveway
+863.724	Rt.	41.7	Commercial Driveway
+935.279	Lt.	46.3	Commercial Driveway
+948.094	Rt.	39.4	Commercial Driveway
+979.003	Rt.	37.6	Commercial Driveway
+990.832	Lt.	55.8	Commercial Driveway
1+037.010	Lt.	36.2	Commercial Driveway
1+039.216	Rt.	74.9	Commercial Driveway
1+061.394	Lt.	41.1	Commercial Driveway
1+076.836	Lt.	38.2	Commercial Driveway
1+089.360	Lt.	45.2	Commercial Driveway
1+115.644	Rt.	23.9	Commercial Driveway
1+118.570	Lt.	50.9	Commercial Driveway
1+39.939	Rt.	23.1	Commercial Driveway
1+147.766	Lt.	61.2	Commercial Driveway
1+170.897	Rt.	21.7	Commercial Driveway
1+215.100	Rt.	25.3	Commercial Driveway
1+260.700	Rt.	30.7	Commercial Driveway
1+262.400	Lt.	56.4	Commercial Driveway
1+276.100	Rt.	31.3	Commercial Driveway
1+293.893	Lt.	51.8	Commercial Driveway
1+304.900	Lt.	53.1	Commercial Driveway
1+352.907	Rt.	32.0	Commercial Driveway
1+370.117	Lt.	49.8	Commercial Driveway
1+392.845	-	127.0	Q EDWARDS (S) (V.G. Pavm't)
1+403.277	Lt.	47.4	Commercial Driveway
1+429.219	Lt.	48.3	Commercial Driveway
1+495.875	-	107.4	Q RICHMOND (S) (V.G. Pavm't)
1+496.323	Lt.	48.8	Commercial Driveway
1+532.924	Rt.	42.9	Commercial Driveway
1+557.925	Rt.	40.3	Commercial Driveway
+460.600	Rt.	39.9	Sheridan
+537.400	Lt.	53.0	Sheridan
+563.500	Lt.	27.0	Sheridan
TOTALS		2787.7	

COMBINED CURB & GUTTER (A.E.)							
STA. TO STA.		ROADWAY	SIDE	TYPE I (150mm) (m)	TYPE III (150mm) (m)	TYPE III (200mm) (m)	REMARKS
							Includes Gutter Section Through Drives
+118.628	+150.00	Central	Lt.	31.384			
+118.628	+150.00	Central	Rt.	31.167			
+150.00	+219.261	Central	Lt.	89.123			Incl'd Return @ McComas
+243.611	+309.373	Central	Lt.	85.636			Incl'd Return @ McComas
+150.00	+285.027	Central	Rt.	146.979			
+309.373	+310.738	Central	Lt.	19.910			Incl'd Return @ Kessler
+335.113	+413.331	Central	Lt.	113.561			Incl'd Returns @ Kessler & West Ridge
+437.682	+450.00	Central	Lt.	29.165			Incl'd Return @ West Ridge
+309.373	+382.834	Central	Rt.	102.005			Incl'd Return @ Knight
+407.182	+450.00	Central	Rt.	59.525			Incl'd Return @ Knight
+450.00	+519.122	Central	Lt.	69.075			
+543.431	+600.00	Central	Lt.	56.560			
+450.00	+478.55	Central	Rt.	44.696			
+502.621	+600.00	Central	Rt.	113.709			Incl'd Return @ West Ridge
+600.00	+630.400	Central	Lt.	30.386			Incl'd Return @ West Ridge
+653.276	+750.00	Central	Lt.	96.738			
+600.00	+750.00	Central	Rt.	150.000			
+750.00	+787.052	Central	Lt.	67.727			Incl'd Return @ Zoo Blvd
+815.424	+851.283	Central	Lt.	49.737			Incl'd Return @ Zoo Blvd
+750.00	+788.554	Central	Rt.	52.935			Incl'd Return @ Sheridan
+818.514	+899.818	Central	Rt.	95.731			Incl'd Return @ Sheridan
+899.818	+924.230	Central	Lt.	29.769			Incl'd Returns @ Mt Carmel
+924.230	+1050.00	Central	Lt.	125.770			
+899.938	+905.262	Central	Rt.	5.446			
+909.958	+988.710	Central	Rt.	86.968			
+1013.74	+1050.00	Central	Rt.	56.926			
+1050.00	+1183.327	Central	Lt.	151.179			Incl'd Return @ St. Paul
+1196.661	+1210.561	Central	Lt.	18.021			Incl'd Return @ St. Paul
+1050.00	+1086.699	Central	Rt.	55.228			Incl'd Return @ Clayton
+1111.044	+1183.178	Central	Rt.	104.973			Incl'd Returns @ Clayton & St. Paul
+1196.912	+1210.490	Central	Rt.	14.314			Incl'd Return @ St. Paul
+1210.561	+1350.00	Central	Lt.	139.417			
+1210.490	+1282.624	Central	Rt.	88.931			Incl'd Return @ Gordon
+1307.040	+1350.00	Central	Rt.	58.896			Incl'd Return @ Gordon
+1350.00	+1508.062	Central	Lt.	158.329			
+1350.00	+1380.656	Central	Rt.	30.620			
+1404.958	+1483.800	Central	Rt.	78.803			
+1508.062	+1638.767	Central	Lt.	130.438			
+1508.062	+1588.244	Central	Rt.	92.148			
+1613.629	+1639.574	Central	Rt.	38.977			
+1527.698	+1639.158	Central	Lt.			114.626	Incl'd Return @ Meridian Median
+1527.698	+1639.158	Central	Rt.			110.452	Median
+430.00	+481.900	Sheridan	Rt.	52.052			
+518.323	+581.317	Sheridan	Lt.	56.769			
+515.519	+549.249	Sheridan	Rt.	37.406			Incl'd Return @ Zoo Blvd
+000.00	+114.839	Zoo Blvd	Rt.	114.839			
+120.00	+131.720	Zoo Blvd	Rt.	23.481			Incl'd Return @ Mt Carmel
+034.325	+085.409	Zoo Blvd	Lt.		54.22		

STA. TO STA.		ROADWAY	SIDE	WIDTH (m)	QUANTITY (m ²)	REMARKS
+819.083	+821.097	Central	Rt.	1.5	2.6	
+833.398	+857.541	Central	Rt.	1.5	36.2	
+869.840	+906.973	Central	Rt.	1.5	54.4	
+909.958	+940.766	Central	Rt.	1.5	44.9	
+955.448	+971.668	Central	Rt.	1.5	24.3	
+986.098	+993.279	Central	Rt.	1.5	21.0	Qty. Includes Sidewalk Ramp
+1050.700	+1087.100	Central	Rt.	1.5	53.3	
+1220.325	+1241.173	Central	Rt.	1.8	37.5	
+1249.956	+1254.518	Central	Rt.	1.8	8.2	
+1266.818	+1269.916	Central	Rt.	1.8	5.6	
+1307.437	+1339.476	Central	Rt.	1.8	57.5	
+1359.272	+1382.727	Central	Rt.	1.8	47.6	Qty. Includes Sidewalk Ramp
+1565.149	+1590.600	Central	Rt.	2.6	70.6	Qty. Includes Sidewalk Ramp
TOTALS					463.7	

CONCRETE PAVEMENT (160 mm UNIF) (A.E.)			
STATION	SIDE	QUANTITY (m ²)	REMARKS
+247.300	Lt.	31.6	Residential Driveway
+355.573	Lt.	31.8	Residential Driveway
+336.819	Rt.	29.6	Residential Driveway
+374.810	Lt.	28.5	Residential Driveway
+574.200	Rt.	41.3	Residential Driveway
+697.478	Rt.	36.2	Residential Driveway
+714.485	Rt.	40.6	Residential Driveway
+743.960	Rt.	35.3	Residential Driveway
1+245.900	Rt.	21.7	Residential Driveway
1+343.900	Rt.	20.9	Residential Driveway
1+443.922	Rt.	26.2	Residential Driveway
+440.600	Rt.	24.5	Sheridan
Cul-De-Sac		181.9	Mt. Carmel (S)
1+000.985		26.5	Residential Driveway on Custer(W)
1+000.985		27.8	Residential Driveway of Custer(E)
TOTALS		604.4	

PROJECT NUMBER 472 - 82906					PROJ NUMBER 95 05 E026
					DIRECTORY
DESIGN KWR	DRAWN KWR	APPROVED JFB	DATE NOV 98	SCALE NONE	SHEET NAME TABLSUM2

SUMMARY OF QUANTITIES
CONCRETE QUANTITIES
CENTRAL AVENUE - WEST ST TO MCLEAN

BAUGHMAN COMPANY P. A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

SHEET
117
— OF —
202

