

BILL OF MATERIALS		
ITEM	UNIT	QTY
POLE MOUNTED CONTROLLER & CABINET	EACH	-
PEDESTAL MOUNTED CONTROLLER & CABINET	EACH	-
PAD MOUNTED CONTROLLER & CABINET	EACH	1
TRAFFIC SIGNAL HEAD (SEE CHART A) W/ MOUNTING HARDWARE	EACH	10
TRAFFIC SIGNAL POLE (SEE CHART B) STEEL	EACH	4
TRAFFIC SIGNAL POLE (SEE CHART B) ALUMINUM	EACH	-
TRAFFIC SIGNAL PEDESTAL ALUMINUM 10'	EACH	-
PEDESTRIAN SIGNAL HEAD w/ MOUNTING HARDWARE	EACH	8
CONCRETE CONTROLLER PAD	EACH	1
CONCRETE FOOTING - PEDESTAL	EACH	-
CONCRETE FOOTING - POLE	EACH	4
CONDUIT ELBOW 90°	EACH	As Req'd.
CONDUIT ELBOW 90° 3"	EACH	As Req'd.
BACK PLATE 5" - 3 SECTION	EACH	8
BACK PLATE 5" - 4 SECTION	EACH	-
BACK PLATE 5" - 5 SECTION	EACH	2
SERVICE BOX	EACH	4
JUNCTION BOX	EACH	2
GROUND ROD & CLAMP	EACH	6
CONDUIT CLAMP	EACH	As Req'd.
TRAFFIC SIGNAL LAMP 135 WATT	EACH	50
TRAFFIC SIGNAL LAMP 60 WATT	EACH	-
CLASS 4 - WOOD POLE	EACH	-
ENTRANCE HEAD	EACH	-
METER & BOX	EACH	1
GUY WIRE GUARD	EACH	-
GUY WIRE CLAMP	EACH	-
THIMBLE EYE ANCHOR ROD	EACH	-
POWER DISCONNECT w/ 40 amp BREAKER	EACH	1
PEDESTRIAN PUSHBUTTON W/SIGN	EACH	8
DETECTOR LOOP WIRE No. 14 A.W.G. 1/C (TYPE THNN)	LIN. M	1775
LEAD-IN WIRE No. 6 A.W.G. 1/C (TYPE THNN)	LIN. M	130
MULTI-CONDUCTOR CABLE No. 14 A.W.G. 5/C	LIN. M	65
MULTI-CONDUCTOR CABLE No. 14 A.W.G. 7/C	LIN. M	200
MULTI-CONDUCTOR CABLE No. 14 A.W.G. 2/C	LIN. M	250
SHIELDED DETECTOR LEAD-IN No. 14 A.W.G. 2/C	LIN. M	As Req'd.
6 Pr #19 AWG COMM CABLE (Interconnect)	LIN. M	-
CONDUIT 20mm	LIN. M	97
CONDUIT 30mm	LIN. M	70
CONDUIT 50mm	LIN. M	13
CONDUIT 75mm	LIN. M	104
STANDARD 1C #8 (GROUND)	LIN. M	130
TETHER WIRE 1/4" ASTM A475 SIEMENS-MARTIN	LIN. M	-
GRADE MIN.	-	-
REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT **	L.S.	1
STREET NAME SIGNS	EACH	4
LEFT TURN YIELD ON GREEN W/MOUNTING HARDWARE (R10-12)	EACH	2

CHART B - TRAFFIC SIGNAL POLES				
STATION	ARM SIZE	NO. OF SIGNALS ON ARM	SIGNAL SPACING ON ARM	TYPE
0+789.9 (*)	12.0m	3	Varied	A,I
0+794.6	8.0m	2	Varied	A,I
0+813.0 (*)	11.0m	2	Varied	A,I
0+815.0	12.0m	3	Varied	A,I

* Joint Use Pole

GENERAL NOTES

1. SIGNAL TIMING BY THE CITY OF WICHITA. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING AND INSTALLING THE CONTROLLER, CABINET, CONCRETE BASE, AND FOR ALL EQUIPMENT NECESSARY FOR THE COMPLETE AND SATISFACTORY OPERATION OF THE TRAFFIC SIGNAL, WHETHER SAID EQUIPMENT IS SPECIFICALLY MENTIONED OR NOT.
2. LENGTHS GIVEN ARE TO CENTERLINE OF POLE/BOX AND DO NOT INCLUDE LENGTHS FOR ELBOWS AND RISERS.
3. SIGNAL HEADS, PEDESTRIAN SIGNALS, TRAFFIC SIGNS & ETC. INCLUDE ALL BRACKETS, HARDWARE & OTHER INCIDENTALS NECESSARY FOR INSTALLATION.
4. SEE CITY OF WICHITA STANDARD SPECIFICATIONS FOR ADDITIONAL WIRING NOTES.

RECAPITULATION OF TRAFFIC SIGNAL QUANTITIES		
BID ITEM	QUANTITY	UNIT
TRAFFIC SIGNAL INSTALLATION (CENTRAL & SHERIDAN)	1 (LUMP SUM)	L.S.





CHART A - TRAFFIC SIGNAL HEADS



SPECIAL FINISH FOR TRAFFIC SIGNAL EQUIPMENT:

The traffic signal controller cabinet, brackets, sign blank backs, signal backs and other exposed surfaces shall be shop painted with an aerosol lacquer cellulose ester to match the traffic signal pole color. The Contractor shall submit two copies of the proposed coating system to the City for approval to application.

TRAFFIC SIGNAL POLE EXTERIOR COATING:

In addition to being galvanized, all exterior surfaces shall be coated with a zinc rich epoxy powder to a minimum dry film thickness of 2.0 mils. The coating shall be electrostatically applied and partially cured in a gas fired convection oven by heating the steel substrate to a minimum of 250 degrees fahrenheit.

The powder primed surface shall be coated with an intermediate coat of polyester powder to a minimum dry film thickness of 2.0 mils. The coating shall be electrostatically applied and cured by heating the substrate in a convection oven to minimum of 350 degrees and a maximum of 400 degrees fahrenheit.

The intermediate coat shall be top coated with one coat of high-build acrylic polyurethane enamel to a minimum dry film thickness of 2.0 mils. The coating shall be electrostatically applied and cured by heating the substrate in a convection oven to a minimum of 225 degrees fahrenheit. The final top coating color shall be BLACK.

Type 170 Controller System to include:

1. Model 170E controller unit complete with WAIKS (Latest Revisions) traffic program on 412B2 system memory module and Model 400 Modem
2. One (1) Model 332 Cabinet complete with all accessories & shall include:
 - A. One (1) Model 210ECL or 210MS Conflict Monitor with software.
 - B. Four (4) Model 430 Transfer Relays.
 - C. Two (2) Model 204 Flashing Units.
 - D. Six (6) Model 200 Switch Packs.
 - E. Three (3) Model 242 DC Isolators.
 - F. One (1) Surge Arrester.
 - G. Eight (8) Model 222 (C-400) 2 Channel Loop Detectors

1. QUANTITIES ARE FOR INFORMATION ONLY. The Contractor shall supply and install all necessary materials and equipment for the complete installation and operation of the traffic signal system whether specifically mentioned or not.
2. ** Removal of existing traffic signal equipment shall include removal of foundations, service boxes, and junction boxes. See construction traffic control regarding removal of existing signals.

