

"□" Cut center of north
Headwall of RCBC in N. R/W of
Maple 570' East of centerline
of City View.
Elev. = 187.91 (City Datum)

Sta 0+36.3, End Line 3B
Construct std. type 1A
curb inlet. (5'x3')
Top Elev. = 172.80✓

Sta 7+88.7 to Sta 8+51.7
Install 63.0 L.F. flowable fill
per City specs.

CAUTION!
Ex. 8" Water Crossing

+54.7
Sta 8+51.7, Line 3
Construct std. type 1A
curb inlet. (10'x5')
Top Elev. = 173.09 ✓

Sta 11+18.4, Line 3
Construct std.
manhole. (5' Dia.)
Top Elev. = 176.70 ✓

Remove & Replace Erosion Blanket & Re-seed.

Sta 11+52.4, Line 3
End construction of 30" RCP.
Construct Inlet-MH (5'x5' O.D.).
Inlet-MH shall have an extra
6" concrete lining bottom of
structure. Install 7.0 S.Y. light
stone rip-rap as indicated.
Top Elev. = 174.00 ✓

Static Pool = 174.0
Bottom = 167.0

Scale: 1" = 20' Horizontal
1" = 5' Vertical
• = Iron

