

PLANT SCHEDULE

TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE
ZEL MUS	2	Zelkova serrata 'Musoshino'	Sawleaf Zelkova	B & B	3"Cal

PAVER SCHEDULE

PAVER A	QUANTITIES	NOTES
PAVER A (NEW) CONCRETE HOLLAND PAVER 8 x 4 COLOR: RED BASE: CONCRETE (4/SHEET13)	EST. INSTALL: 6,225 SF.	PAVESTONE 601 N.E. PAVESTONE DR. P.O. BOX 6770 LEE'S SUMMIT, MO 64064 TEL. 816.524.9900 www.pavestone.com
PAVER B (SALVAGED) SALVAGED CONCRETE HOLLAND PAVER 8 x 4 COLOR: RED BASE: CONCRETE (4/SHEET13)	EST. SALVAGE: 852 SF. EST. INSTALL: 836 SF. EST. OVERRUN: 196 SF.	*175 SF. OF PAVER IN FRONT OF THE COURTYARD MARRIOTT TO BE REMOVED AND RESET WITH THE EXISTING BASE TO REMAIN IN PLACE. (SEE SHEET 10)
PAVER C (SALVAGED) SALVAGED CONCRETE HOLLAND PAVER 8 x 4 COLOR: RED-BLACK BLEND BASE: SEE PLAN	EST. SALVAGE : 1,867 SF. EST. INSTALL: 285 SF. EX. OVERRUN: 43 SF.	
PAVER D (SALVAGED) SALVAGED CONCRETE HOLLAND PAVER 8 x 4 COLOR: SABLE BROWN BASE: CONCRETE (4/SHEET13)	EST. SHOWN: 981 SF. EST. OVERRUN: 48 SF.	BELGARD TEL. 877.235.4273 www.belgard.com *ONLY USED ON NORTH SIDE OF MOSLEY ST. & DOUGLAS INTERSECTION

- PAVER SCHEDULE NOTES:**
- QUANTITIES ON PLAN TAKE PRECEDENCE OVER THOSE IN SCHEDULE. IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL QUANTITIES.
 - SALVAGED PAVERS - THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING SALVAGE PAVER QUANTITIES ONCE DEMOLITION HAS FINISHED.
 - PRIOR TO PURCHASING FINAL PAVER QUANTITIES CONTRACTOR TO PROVIDE PAVER SAMPLES FOR ONSITE APPROVAL BY ARCHITECT.
 - ALL SALVAGED AND UNUSED PAVERS TO BE PALLETIZED AND WRAPPED, THEN TRANSPORTED TO CITY OF WICHITA YARD FOR STORAGE.
CITY STORAGE YARD
360 N. GILDA ST.
WICHITA, KS 67212
 - ESTIMATED OVERRUN - THE AREA TWO LINEAR-FEET BEYOND WORK ZONE SHOWN IN PLANS. ALL SIDEWALK WORK BEYOND TWO-LINEAR FEET MUST BE APPROVED BY THE PROJECT MANAGER.

SITE AMENITIES SCHEDULE


LIGHT BOLLARD (SEE 9/SHEET13) MANUFACTURER: PHILIPS HADCO PRODUCT: TB361 BOLLARD COLOR: BLACK REFER: ELECTRICAL DRAWINGS	REF. DETAIL 9/SHEET 13 QUANTITY: 6	PHILIPS HADCO 100 CRAFTWAY DRIVE LITTLTOWN, PA 17340 TEL. 717.359.7131 www.lightingproducts.philips.com
SECURITY BOLLARD (SEE 8/SHEET13) MANUFACTURER: RELIANCE-FOUNDRY PRODUCT: R-7530 COLOR: BLACK	REF. DETAIL 8/SHEET 13 QUANTITY: 46	RELIANCE-FOUNDRY CO. UNIT 207 6450-148TH ST. SURREY, BRITISH COLUMBIA, CANADA V3S0T7 TEL. 604-547-0460 www.reliance-foundry.com
PROP. BACKLESS BENCHES (SEE 12/SHEET14) MANUFACTURER: DUMOR PRODUCT: 92-60-3AR ATTACHMENT: SURFACE MOUNT COLOR: BLACK	REF. DETAIL 12/SHEET 14 QUANTITY: 28 REMOVED & REINSTALLED: 1	DUMOR SITE FURNISHINGS TEL. 800.598.4018 WWW.DUMOR.COM SALES@DUMOR.COM
PROP. BIKE RACK (SEE 11/SHEET14) MADRAX POST & RING W/ BALL CAP (PARBC-2-SF-P) ATTACHMENT: SURFACE MOUNT COLOR: BLACK	REF. DETAIL 11/SHEET 14 QUANTITY: 29	GRABER MANUFACTURING INC. 1080 UNIEK DR. WAUNAKEE, WI 53597 TEL: 800-448-7931 www.madrax.com
PROP. TRASH RECEPTACLE (SEE 13/SHEET14) MANUFACTURER: VICTOR STANLEY PRODUCT: RB-36 W/ DOME LID ATTACHMENT: SURFACE MOUNT COLOR: BLACK	REF. DETAIL 13/SHEET 14 QUANTITY NEW: 7 REMOVED & REINSTALLED: 2	VICTOR STANLEY P.O. DRAWER 330 DUNKIRK, MD 20754 TEL. 301-855-8300 http://www.victorst Stanley.com
TREE GRATES (SEE 10/SHEET13) MANUFACTURER: NEENAH FOUNDRY PRODUCT: METROPOLITAN COLLECTION (R-8707) W/ FRAME NF-85006060 (CAST IN PLACE FRAME)	REF. DETAIL 11/SHEET 13 QUANTITY: 6	NEENAH FOUNDRY 2121 BROOKS AVE. NEENAH, WI 54956 TEL. 920-725-7000 http://www.nfco.com
CUSTOM BENCH (SEE SHEET15) MANUFACTURER: LANDSCAPE FORMS PRODUCT: SF2622-001 MOUNTING: SURFACE	REF. DETAIL SHEET 15 QUANTITY: 3	LANDSCAPE FORMS 7800 E MICHIGAN AVE. KALAMAZOO, MI 49048 TEL. 269-381-0396 http://www.landscapeforms.com

- SITE AMENITIES SCHEDULE NOTES:**
- QUANTITIES ON PLAN TAKE PRECEDENCE OVER THOSE IN SCHEDULE. IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL QUANTITIES SHOWN.
 - CONTRACTOR TO USE AMENITIES SHOWN, OR APPROVED EQUIVALENT. ANY ALTERNATIVE PRODUCTS FROM THOSE LISTED SHALL BE SUBMITTED TO THE ARCHITECT PRIOR TO BID FOR APPROVAL.
 - PROVIDE CUT SHEETS AND/OR SHOP DRAWINGS OF ALL LISTED ITEMS FOR REVIEW.
 - ALL WORK AND MATERIALS FOR INSTALLATION OF SITE AMENITIES IS SUBSIDIARY TO THOSE ITEMS.
 - QUANTITIES SHOWN IN THE PLANS TAKE PRECEDENCE OVER THOSE SHOWN IN THE SCHEDULE.

A SITE ARCHITECTURAL PLAN

- REMOVE EXISTING SIDEWALK CONCRETE PAVING TO NEAREST CONTROL JOINT.
- EXISTING PLANTER POTS IN WORK AREA. RELOCATE FOR WORK AND RESET ONCE ALL WORK HAS FINISHED.

1"=10'-0"



Tran Systems
245 NORTH WACO
SUITE 222
WICHITA, KANSAS 67202
PHONE: 316-303-3000
FAX: 316-303-0166

LKArchitecture, Inc.
345 NORTH RIVERVIEW ST.
SUITE 200
WICHITA, KANSAS 67203
PHONE: 316-268-0230

**2ND STREET IMPROVEMENTS
SANTA FE TO WASHINGTON IN OLD TOWN**
WICHITA, KANSAS
CITY OF WICHITA

REVISIONS:	MARK	DATE	DESCRIPTION

PROJ NO: 472-85284
SCALE: 1" = 10'-0"
DATE: 07/13/2018
DESIGNED BY: WAWELLS
DRAWN BY: WAWELLS
CHECKED BY: JABEST

SHEET TITLE:
SITE ARCHITECTURAL Plan

SHEET NO.
9
SHEET 9 OF 103