

PEREGRINE/KITE

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.00	0.00				
0+50	0.00	133.22	0.00	123.35	0.00	123.35
0+60.16	0.00	127.21	0.00	49.01	0.00	172.36
1+00	0.00	83.99	0.00	155.80	0.00	328.16
1+47.38	0.32	77.44	0.28	141.63	0.28	469.79
1+50	0.22	79.09	0.02	8.31	0.30	478.11
1+66.92	0.00	89.85	0.06	57.48	0.36	535.58
1+75	0.00	92.82	0.00	29.25	0.36	564.83
1+93.63	0.00	92.75	0.00	31.38	0.36	596.21
2+00	0.00	89.37	0.00	57.55	0.36	653.76
2+10.49	0.00	89.07	0.00	35.53	0.36	689.29
2+25	0.00	84.37	0.00	46.79	0.36	736.08
2+41.67	0.00	83.19	0.00	50.74	0.36	786.83
2+50	0.00	84.33	0.00	25.17	0.36	812.00
2+64.81	0.00	86.52	0.00	45.55	0.36	857.35
3+00	0.04	63.74	0.03	97.32	0.39	955.87
3+50	8.93	37.67	8.31	93.31	8.70	1049.77
3+71.01	12.39	34.76	8.30	28.19	17.00	1077.96
3+75	12.96	34.22	1.77	5.59	18.77	1083.54
4+00	19.82	27.25	14.64	31.03	33.41	1114.56
4+25	32.71	18.83	23.95	23.34	57.35	1137.90
4+50	52.79	4.16	39.36	11.49	96.72	1149.39
4+60.07	64.13	1.00	21.83	0.91	118.54	1150.31
4+75	73.63	0.78	38.50	0.38	157.05	1150.68
5+00	76.82	1.52	71.12	0.73	228.17	1151.42
5+25	69.22	3.62	69.70	1.67	297.87	1153.08
5+27.50	68.47	3.84	6.62	0.24	304.49	1153.33
5+50	66.51	4.08	56.24	3.30	360.72	1156.63
6+00	81.71	2.17	137.24	5.79	497.97	1162.42
6+50	94.47	0.17	163.13	2.17	661.10	1164.59
7+00	87.06	0.13	168.08	0.28	829.18	1164.87
7+12.13	85.12	0.10	38.66	0.05	867.84	1164.92
7+25	83.99	0.02	39.25	0.04	907.09	1164.95
7+33.02	83.03	0.00	24.30	0.00	931.39	1164.96
7+50	93.77	0.00	54.76	0.00	986.15	1164.96
7+75	111.07	0.00	34.15	0.00	1080.30	1164.96
8+00	128.79	0.00	111.25	0.00	1191.55	1164.96
8+19.19	137.60	0.00	95.29	0.00	1286.85	1164.96
8+50	141.29	0.00	159.13	0.00	1445.98	1164.96
9+00	122.20	0.00	243.97	0.00	1689.95	1164.96
9+48.97	92.62	0.68	194.83	0.61	1884.78	1165.57
9+50	91.66	0.81	3.39	0.03	1888.17	1165.61
9+75	71.24	4.35	72.96	2.86	1961.13	1168.47
10+00	57.48	8.33	57.73	6.37	2018.85	1175.44
10+23.12	52.81	8.39	45.89	8.47	2064.75	1183.91
10+50	60.84	5.70	56.58	7.01	2121.33	1190.93
10+66.39	63.40	4.21	37.72	3.01	2159.05	1193.94
11+00	66.14	2.31	80.62	4.06	2239.67	1198.00
11+00.61	66.22	2.28	1.50	0.05	2241.17	1198.05
11+34.40	67.85	0.75	83.88	1.89	2325.05	1199.94
11+50	80.00	0.04	42.72	0.23	2367.77	1200.17
12+00	111.99	0.00	177.77	0.04	2545.54	1200.22
12+50	115.60	0.00	210.73	0.00	2756.28	1200.22
12+79.31	105.72	0.43	120.11	0.23	2876.39	1200.45
13+00	94.67	1.85	73.43	1.10	2949.82	1201.55
13+23.81	83.99	2.62	75.39	2.47	3025.21	1204.02
13+25	83.17	2.80	3.53	0.15	3028.73	1204.17
13+50	69.26	6.38	67.77	5.29	3096.50	1209.46
13+52.36	68.53	6.50	5.80	0.70	3102.30	1210.16
13+75	79.26	1.55	59.78	4.21	3162.08	1214.36
13+80.91	82.52	0.50	17.14	0.28	3179.22	1214.65
14+00	94.48	0.00	60.83	0.20	3240.05	1214.84
14+25	113.07	0.00	93.94	0.00	3333.99	1214.84
14+50	124.49	0.00	107.83	0.00	3441.82	1214.84
14+67.09	119.63	0.00	75.99	0.00	3517.81	1214.84
15+00	92.83	0.00	129.46	0.00	3647.27	1214.84
15+50	48.23	6.00	130.62	5.56	3777.89	1220.40
16+00	18.35	26.52	61.65	30.11	3839.54	1250.51
16+14.59	10.02	32.03	7.66	15.81	3847.20	1266.33
16+48.80	3.11	45.60	8.32	49.19	3855.52	1315.51
16+50	2.96	46.00	0.13	2.03	3855.65	1317.54
16+82.59	0.00	74.98	1.78	73.01	3857.44	1390.55
17+00	0.00	88.97	0.00	52.87	3857.44	1443.42
17+50	0.00	98.37	0.00	173.46	3857.44	1616.87
18+00	0.00	112.15	0.00	194.92	3857.44	1811.80
18+04.70	0.00	129.50	0.00	21.05	3857.44	1832.85
18+50	0.00	115.51	0.00	205.52	3857.44	2038.37
18+63.81	0.00	112.41	0.00	58.28	3857.44	2096.65
			0.00	0.00	3857.44	2096.65

LANNERS CIRCLE

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.00	0.00				
0+32.84	51.46	2.21	31.29	1.34	31.29	1.34
0+50	50.82	1.76	32.51	1.26	63.80	2.61
0+67.50	48.91	1.97	32.32	1.21	96.11	3.82
0+75	47.77	1.56	13.75	0.36	109.87	4.18
0+88.38	48.87	0.86	25.50	0.45	135.37	4.63
1+00	50.56	0.49	20.28	0.28	155.66	4.90
1+50	57.02	0.17	99.61	0.61	255.26	5.52
2+00	43.60	1.97	93.16	1.98	348.42	7.50
2+16.06	47.76	0.03	27.17	0.60	375.59	8.10
2+25	52.51	0.00	16.56	0.01	392.15	8.11
2+50	66.13	0.00	55.68	0.00	447.82	8.11
2+75	77.49	0.00	69.45	0.00	516.27	8.11
2+99.73	80.27	0.00	74.24	0.00	590.51	8.11
3+00	80.28	0.00	0.81	0.00	591.32	8.11
3+50	59.66	0.02	129.57	0.02	720.90	8.12
3+57.88	55.65	0.13	16.82	0.02	737.72	8.15
3+91.88	35.12	3.14	57.15	2.06	794.87	10.20
4+00	30.83	5.19	9.92	1.25	804.79	11.45
4+25.88	26.45	8.05	27.45	6.34	832.24	17.80
4+44.62	27.09	8.51	18.58	5.75	850.82	23.54
4+50	27.03	8.58	5.43	1.58	856.25	25.12
4+75	25.78	10.09	24.53	8.31	880.78	33.43
5+00	27.02	9.99	24.46	9.27	905.24	42.70
5+25	28.09	9.78	25.48	9.36	930.72	52.06
5+50	30.18	9.15	26.84	9.30	957.57	61.36
5+75	32.76	7.53	28.91	8.44	986.47	69.80
5+92.87	35.69	5.60	22.43	4.84	1008.91	74.64
6+00	39.55	4.49	9.94	1.33	1018.84	75.98
6+50	45.82	2.66	79.05	6.62	1097.89	82.59
7+00	18.89	19.02	59.92	20.07	1157.81	102.67
7+50	0.85	50.53	18.28	64.40	1176.09	167.07
7+70.19	0.24	56.87	0.41	40.16	1176.50	207.23
7+85.52	0.00	74.37	0.07	37.25	1176.57	244.48
8+00	0.00	128.62	0.00	54.43	1176.57	298.91
8+13.43	0.00	234.40	0.00	90.25	1176.57	389.16
8+48.93	0.00	509.80	0.00	489.24	1176.57	878.40
8+50	0.00	0.00	0.00	10.15	1176.57	888.55
8+63.43	0.00	0.00	0.00	0.00	1176.57	888.55
			0.00	0.00	1176.57	888.55

OSPREY CIRCLE

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.00	0.00				
0+37.20	0.00	63.05	0.00	43.44	0.00	43.44
0+50	0.04	60.08	0.01	29.18	0.01	72.62
1+00	1.54	40.87	1.46	93.47	1.47	166.09
1+50	1.84	44.57	3.13	79.11	4.60	245.20
2+00	0.27	59.63	1.95	96.48	6.55	341.68
2+50	0.00	82.97	0.25	132.03	6.80	473.72
3+00	0.00	97.71	0.00	167.29	6.80	641.01
3+50	0.00	112.16	0.00	194.32	6.80	835.33
4+00	0.00	98.61	0.00	195.16	6.80	1030.49
4+50	0.00	91.17	0.00	173.72	6.80	1206.21
5+00	0.00	91.68	0.00	169.31	6.80	1375.52
5+50	0.00	71.17	0.00	150.79	6.80	1526.31
5+68.44	0.00	72.17	0.00	48.95	6.80	1575.26
5+75	0.00	71.96	0.00	17.86	6.80	1593.12
6+00	0.00	60.90	0.00	62.86	6.80	1655.98
6+25	0.26	49.59	0.12	52.56	6.92	1708.54
6+50	0.92	41.58	0.50	43.63	7.42	1752.17
6+75	1.66	35.54	1.11	37.03	8.53	1789.20
7+00	0.66	38.69	1.00	35.40	9.53	1824.60
7+07.08	0.46	39.09	0.14	10.42	9.66	1835.02
7+19.57	0.54	37.36	0.23	17.67	9.89	1852.70
7+34.90	1.69	30.24	0.63	19.19	10.53	1871.88
7+50	4.18	24.52	1.64	15.32	12.17	1887.20
7+62.80	7.21	19.14	2.70	10.35	14.87	1897.55
7+98.30	27.12	10.41	22.57	19.43	37.44	1916.98
8+00	28.92	10.08	1.76	0.65	39.21	1917.62
8+12.80	0.00	0.00	6.86	2.39	46.06	1920.01
			0.00	0.00	46.06	1920.01

LANNERS COURT

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.00	0.00				
0+34	55.49	2.52	34.94	1.58	34.94	1.58
0+50	67.36	1.98	36.40	1.33	71.34	2.92
+62.63	77.18	1.07	33.80	0.71	105.14	3.63
+78.35	90.45	0.05	28.00	0.12	133.94	3.95
1+00	105.01	0.00	23.08	0.02	232.31	3.97
+105.86	107.73	0.00	20.52	0.00	253.40	3.97
+141.36	128.26	0.00	20.52	0.00	431.07	3.97
1+50	0.00	0.00	0.00	0.00	431.07	3.97
+155.86	0.00	0.00	0.00	0.00	431.07	3.97