




NOTE:

ALL POND SLOPES ABOVE ELEVATION 1346.0 SHALL RECEIVE PERMANENT KANSAS PREMIUM BLEND FESCUE SEEDING DURING FALL PLANTING SEASON (AUGUST 15 - SEPTEMBER 30)

CORE TRENCH

The core trench shall be constructed along the proposed dam centerline over the entire length of the dam. The core trench shall be excavated to a depth of at least 3 feet below the bottom of the concrete box and the natural grade along the dam alignment. The core trench should have a width of about 12 feet to accommodate construction equipment such as a dozer. To allow for construction of the west portion of the core trench, removing the existing granular fill from the core trench area will be required. The core trench shall be backfilled with cohesive soils having a plasticity index greater than 25 (such as the on-site fat clays in the reservoir area) and placed and compacted as recommended below. Granular soils and low plasticity clays are not considered suitable for the core trench.

SITE PREPARATION

The contractor shall strip the organic topsoil in the dam embankment area. After performing all cuts and excavations required, the exposed subgrade soils in the proposed dam and core trench areas should be proofrolled to locate zones that are soft or unstable. Proofrolling should be conducted with a loaded, tandem-axle dump truck, scraper, or other heavy, rubber-tired, construction vehicle weighing at least 25 tons. The proofrolling should consist of several overlapping passes over an area in mutually perpendicular directions. The subgrade in areas where excessive rutting or pumping occurs during proofrolling should be removed and replaced with suitable fill, as described below, if it cannot be satisfactorily densified in place.



After proofrolling the subgrade and prior to placing new fill, we recommend the exposed soils be scarified to a depth of about 9 inches. The subgrade moisture should be adjusted to meet the recommendations presented in the "Engineered Fill" section and the subgrade compacted to at least 95% of their maximum dry density (by ASTM D 698). Fill materials could then be constructed on the compacted subgrade.

ENGINEERED FILL

All new fill should consist of approved, on-site or off-site soils that are free of organics and deleterious materials. The soils should be constructed in maximum lifts not exceeding 9 inches in loose thickness and compacted to at least 95% of their maximum dry density as determined by the standard Proctor procedure, ASTM D-698.

The moisture content at which the soils should be compacted is given as follows:

- Cohesive soils with a plasticity index (PI) greater than or equal to 30 should be placed at a moisture content of at least 2% above their optimum moisture content (ASTM D-698).
- Cohesive soils with a PI less than 30 should be placed at a moisture content above their optimum moisture content.
- Granular soils should be placed at workable moisture content.



FINAL

Designed By: J. Ubert / B. Kulla

Drawn By: B. Kulla

Poe Job No.: 1748A

Date: May 2003

POE & ASSOCIATES OF KANSAS, INC.
CONSULTING ENGINEERS
5640 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/685-4114 ■ FAX 316/685-4444

FALCON FALLS - PHASE 1

STREET IMPROVEMENTS

POND GRADING

CITY OF WICHITA, KANSAS

NEIL D. CABLE, P.E. - CITY ENGINEER

C.O.W. Project # 472-83687 O.C.A. # 765872

No.	Date	By	Approved	Revision
1				
2				
3				
4				