



STEPHANIE

Stephanie CY Excavation (unadjusted)				Stephanie CY Compacted Fill (unadjusted)				Stephanie CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+37	14.14	0.00	0.00	0+37	6.35	0.00	0.00	0+37	15.66	0.00	0.00
0+50	9.34	5.65	5.65	0+50	7.44	3.32	3.32	0+50	19.30	8.42	8.42
1+00	4.54	12.85	18.50	1+00	9.24	15.45	18.76	1+00	22.38	38.60	47.02
1+50	0.51	4.68	23.18	1+50	20.38	27.16	45.92	1+50	27.28	46.12	93.14
2+00	6.82	6.80	29.98	2+00	7.98	26.00	71.92	2+00	20.81	44.65	137.79
2+50	0.37	6.66	36.64	2+50	12.70	18.99	90.90	2+50	30.39	47.58	185.36
3+00	0.69	0.98	37.62	3+00	14.88	25.54	116.44	3+00	33.46	59.12	244.49
3+50	0.95	1.52	39.13	3+50	14.21	26.94	143.38	3+50	33.04	61.57	306.06
4+00	6.13	6.56	45.69	4+00	4.24	17.08	160.46	4+00	25.29	54.01	360.07
4+55.32	5.08	12.33	58.02	4+55.32	1.12	6.56	167.02	4+55.32	26.21	46.42	406.48
4+69.74	119.53	41.89	99.91	4+69.74	0.00	0.38	167.40	4+69.74	20.95	10.05	416.54
4+86.32	176.18	115.88	215.79	4+86.32	0.00	0.00	167.40	4+86.32	6.36	6.40	422.94
4+97.64	161.10	89.50	305.29	4+97.64	0.00	0.00	167.40	4+97.64	1.81	1.28	424.21
5+08.95	149.34	79.81	385.09	5+08.95	0.00	0.00	167.40	5+08.95	0.07	0.29	424.50
5+25	96.41	83.59	468.69	5+25	0.00	0.00	167.40	5+25	2.10	0.98	425.48
5+39.93	76.32	49.05	517.74	5+39.93	0.00	0.00	167.40	5+39.93	0.00	0.90	426.39
5+50	74.69	28.01	545.75	5+50	0.00	0.00	167.40	5+50	0.00	0.00	426.39
6+00	49.49	114.65	660.41	6+00	0.00	0.00	167.40	6+00	0.00	0.00	426.39
6+50	19.41	63.80	724.20	6+50	3.72	3.45	170.84	6+50	13.50	12.50	438.89
6+75.52	7.87	12.90	737.10	6+75.52	6.23	4.71	175.55	6+75.52	21.64	16.61	455.50