COMBINED CURB and GUTTER

Sta. to Sta.		Length (ft)	Side
10+29.83	13+02.81	273.0	Lt
13+62.82	16+36.09	19.8	Lt
16+85.85	19+59.02	273.2	Lt
19+59.02	19+73.17	23.0	Lt
20+03.60	20+18.70	23.4	Lt
20+18.70	22+89.87	271.2	Lt
22+89.87	23+09.48	26.3	Lt
10+29.83	13+02.79	273.0	Rt
13+62.82	16+36.09	273.3	Rt
16+85.85	19+58.54	272.7	Rt
19+58.54	19+73.45	19.6	Rt
20+04.53	20+18.92	20.5	Rt
20+18.92	22+89.67	270.8	Rt
22+89.67	23+08.89	26.3	Rt
	Total	2066.1	

CRUSHED STONE SUBGRADE (5")

Sta. to Sta.		Length (LF)	Width (LF)	Area (SY)
10+29.99	13+02.82	272.83	33.00	1000.4
13+62.82	16+36.13	273.31	33.00	1002.1
16+85.85	19+58.92	273.07	33.00	1001.3
20+18.92	22+89.87	270.95	33.00	993.5
22+89.84	23+11.21			988.3
		Total		4985.6

BID ITEMS

Item	Quantity	UM
Paving Items		
Construction Traffic Control	1	L.S.
Clearing and Site Preparation	1	L.S.
Crushed Stone Subgrade (5 inch)	4986	Sq. Yd.
5" Asphalt Pavement (3" Base)	3150	Sq. Yd.
Combined Curb & Gutter	2066	L.F.
Common Excavation	1827	Cu. Yd.
Seeding (TRWPC)	1	LS
Irrigation Sleeve/Sprinkler System Repairs	1	LS
RCVG Pavement (7")	101	Sq. Yd.
Adjustment of Manholes	4	EA
Manhole (Type B)	1	EA.
8" Sanitary Sewer Pipe	264	L.F.
Flowable Fill	26	L.F.
Sidewalk Ramps	3	EA.
Concrete Pavement (6 inch)(Res. Drive)	85	Sq. Yd.

RCVG PAVEMENT (7")

Sta. to Sta.				Area (SY)
22+89.84	23+11.21			100.8
		Total		100.8

CONCRETE PAVEMENT (6")(RES. DRIVE)

Station	Offset	Area (sy)
14+28.53	Left	24.89
15+10.51	Left	29.91
22+18.24	Left	29.91
	Total	84.71

EARTHWORK

Sta. to Sta.		Common Excavation (CY)	Embankment (CY)	Contractor Furnished Excavation (CY)
10+29.99	13+02.82	463.6	10.0	
13+62.82	16+36.13	331.1	21.0	
16+85.85	19+58.92	349.2	8.3	
20+18.92	23+11.19	344.5	27.7	
	Totals	1490.4	67.0	

5" ASPHALT PAVEMENT

Sta. to Sta.		Length (lf)	Width (lf)	Area (sy)
10+29.99	13+02.82	272.83	26.00	788.2
13+62.82	16+36.13	273.31	26.00	789.6
16+85.85	19+58.92	273.07	26.00	788.9
20+18.92	22+89.87	270.95	26.00	782.7
			Total	3149.4

REVISIONS			
DATE	PROJECT NO.	12/02/2003	BY

CITY OF WICHITA

20th STREET
HYDRAULIC TO PIATT

SUMMARY OF QUANTITIES

WICHITA KANSAS

TRANSYSTEMS CORPORATION
245 North Waco, Suite 420
Wichita, Kansas 67202

DESIGNED	I.R.L.	DRAWN	M.P.M.
CHECKED	B. A. L.	DATE	2/2004
SCALE	1" = 20'	SHEET NO.	14

sht\sum\sum\1\100\020\1\8