

NOTE:

ACTUAL FIBER CONNECTIONS, SWITCH CONFIGURATION, AND PORT ASSIGNMENT SUBJECT TO CHANGE. KDOT AND CITY OF WICHITA NETWORK ENGINEER TO APPROVE FINAL FIBER CONNECTION PLANS. CONTRACTOR SHALL WORK WITH ENGINEER TO PROVIDE COMMUNICATION PATH FROM COW CITY HALL TO FIELD DEVICES.

THIS SHEET TO BE COMPLETED BY THE CONTRACTOR, INSPECTOR AND ENGINEER DURING CONSTRUCTION FOR FIELD DOCUMENTATION PURPOSES.

CITY FIBER CASSETTES A & B FOR BOTH THE 144 & 288 ARE PLANNED TO BE PATCHED STRAIGHT ACROSS (e.g. 1 = 1, 2=2, ETC.).

COW 288 (TO CITY HALL)

A	B	C	D	E	F	G	H	I	J	K	L	M											
1	13	25	37	49	61	73	85	97	109	121	133	145	157	169	181	193	205	217	229	241	253	265	277
2	14	26	38	50	62	74	86	98	110	122	134	146	158	170	182	194	206	218	230	242	254	266	278
3	15	27	39	51	63	75	87	99	111	123	135	147	159	171	183	195	207	219	231	243	255	267	279
4	16	28	40	52	64	76	88	100	112	124	136	148	160	172	184	196	208	220	232	244	256	268	280
5	17	29	41	53	65	77	89	101	113	125	137	149	161	173	185	197	209	221	233	245	257	269	281
6	18	30	42	54	66	78	90	102	114	126	138	150	162	174	186	198	210	222	234	246	258	270	282
7	19	31	43	55	67	79	91	103	115	127	139	151	163	175	187	199	211	223	235	247	259	271	283
8	20	32	44	56	68	80	92	104	116	128	140	152	164	176	188	200	212	224	236	248	260	272	284
9	21	33	45	57	69	81	93	105	117	129	141	153	165	177	189	201	213	225	237	249	261	273	285
10	22	34	46	58	70	82	94	106	118	130	142	154	166	178	190	202	214	226	238	250	262	274	286
11	23	35	47	59	71	83	95	107	119	131	143	155	167	179	191	203	215	227	239	251	263	275	287
12	24	36	48	60	72	84	96	108	120	132	144	156	168	180	192	204	216	228	240	252	264	276	288

COW 144 (FROM HUB #1)

A	B	C	D	E	F						
1	13	25	37	49	61	73	85	97	109	121	133
2	14	26	38	50	62	74	86	98	110	122	134
3	15	27	39	51	63	75	87	99	111	123	135
4	16	28	40	52	64	76	88	100	112	124	136
5	17	29	41	53	65	77	89	101	113	125	137
6	18	30	42	54	66	78	90	102	114	126	138
7	19	31	43	55	67	79	91	103	115	127	139
8	20	32	44	56	68	80	92	104	116	128	140
9	21	33	45	57	69	81	93	105	117	129	141
10	22	34	46	58	70	82	94	106	118	130	142
11	23	35	47	59	71	83	95	107	119	131	143
12	24	36	48	60	72	84	96	108	120	132	144

ASSUMED 24 PATCHCABLES NEEDED (DUPLEX)

KANSAS DEPARTMENT OF TRANSPORTATION
 BLDG I- TMC
 CITY OF WICHITA
 PATCH PANEL DETAILS

DATE	BY
REFERENCES NOTED	
REFERENCES CHECKED	