NW¼ Sec. 32, T27E, RIE

McLEAN BLVD.

ARKANSAS RIVER

GREENWAY BLVD.

MAGRUDER'S ADDITION

SE¼ Sec. 29, T27S, RIE

NW¼ Sec. 32, T27E, RIE

NW¼ Sec. 32, T27E, RIE

SCALE 20' 0 20' 40'

Const. Limits

Exist. R/W

℄ Harry Street

℄ Sidewalk B

℄ Sidewalk A

Sec. Line

15" RCP

18" RCP

12" VCP

24" RCP

3" RSC

3" HDPE

City of Wichita FO

Abandoned

Elec.

LP

HH

MH

GV

OHP

Sta. 10+00, 19.37' Rt.
Flexible Expansion Sleeve

Sta. 8+12, 80' Rt.
Install Splice Box
Connect to Existing FO Line

Sta. 12+38, 58' Rt.
Connect to Existing FO Line

Notes:

Utilities shown are from best available information.

The bid item "Fiber Optic Cable Relocation (Lump Sum)" includes all labor, materials, and any incidentals needed to relocate the City of Wichita Fiber Optic Cable as detailed in the plans. See Project Special Provisions for additional information.

UTILITIES

Communication	AT&T
Communication	Cox Communications
Communication	Zayo Group
Electric	Westar Energy
Gas	Black Hills
City Fiber Optic	City of Wichita
Sanitary Sewer	City of Wichita
Stormwater Sewer	City of Wichita
Traffic Signal	City of Wichita
Water	City of Wichita

CITY OF WICHITA

WSP

CITY OF WICHITA FIBER OPTIC LINE

HARRY STREET BRIDGE
OVER ARKANSAS RIVER

REVISIONS

NO.	DATE	DESCRIPTION

PROJ NO:	35838B
SCALE:	AS NOTED
DATE:	.
DESIGNED BY:	--
DRAWN BY:	--
CHECKED BY:	
YEAR:	2019

SHEET NO
II

SHEET II OF 135

Plotted : 10/3/2019 2:11:05 PM File : T:\35838A-COW_HarrySt Bridge\Cadd\Sheets\Roadway\838UTL01.dgn