

SCHEDULE OF STORM SEWER INSTALLATIONS (SMOOTH PIPE SYSTEM)

ROUTING SEQUENCE		LOCATIONS OF INSTALLATIONS			TYPE OF INSTALL		DIMENSIONS			ELEVATIONS			INFLOW CONDUITS				OUTFLOW CONDUITS		PIPE LENGTHS			END SECTIONS	REMARKS			
FROM	TO	STATION	ROUTE	OFFSET	RCMH	SSMH (5')	L (FT.)	W (FT.)	H (FT.)	TOP [⊗]	FLOOR	BOTTOM	CONDUIT SIZE	FLOWLINE ELEV.	CONDUIT SIZE	FLOWLINE ELEV.	CONDUIT SIZE	FLOWLINE ELEV.	24" RCP	30" RCP	54" RCP	30" RC				
SW1-3	SW1-2	7+97.00	Harry Street	25.70' Lt.	1		4'-6"	3'-6"	14'-3"	1293.75	1,280.00	1,279.50	Ex. 24"	1280.48 (NW)					24"	1280.48 (NE)	87			1	Offset stack to NE Corner	
SW1-2	SW1-1	8+14.84	Harry Street	111.73' Lt.		1				1287.54	1,278.04	1,277.37	Ex. 18"	1279.63 (NW)	24"	1279.13 (SW)					41				End two joints to be restrained joints	
SW2-2	SW2-1	12+10.00	Harry Street	76.83' Rt.	1		7'-0"	4'-0"	17'-3"	1293.92	1,277.17	1,276.67	Ex. 54"	1277.74 (NE)					54"	1277.74 (SW)			78		End two joints to be restrained joints	
					</																					