PROJECT CONTROL AND COORDINATE DATA

POINT NO.	ALIGNMENT	STATION	OFFSET (FT.)	SIDE	DESCRIPTION	NORTHING	EASTING
701	Harry	11+45.80	121.13	RT.	End 54" SWS Pipe Sta. 20+00 SWS Line 2	1677755.97	1646607.64
702	Harry	12+10.00	76.83	RT.	CTR. RC Manhole (SWS2-2) Sta. 20+78 SWS Line 2	1677775.67	1646683.12
801	Harry	7+66.21	46.44	RT.	New Signal Pedestal with Ped. Signal and Pushbutton (Pole 1)	1677964.37	1646270.41
802	Harry	7+66.72	50.11	RT.	CTR. Exist. Traffic Signal Manhole	1677960.92	1646269.03
803	Harry	7+76.19	43.50	RT.	Existing Signal Pole and Mast Arm	1677961.12	1646281.93
804	Harry	7+73.09	35.89	RT.	New Signal Pedestal with Ped. Signal and Pushbutton (Pole 2)	1677969.49	1646282.56
811	Harry	8+36.50	32.33	LT.	New RO-I-I Light Pole	1678005.88	1646369.39
812	Harry	9+30.00	27.33	RT.	New RO-I-I Light Pole	1677917.86	1646436.88
813	Harry	10+72.50	32.33	LT.	New RO-I-I Light Pole	1677925.24	1646591.19
814	Harry	11+78.50	27.33	RT.	New RO-I-I Light Pole	1677832.95	1646670.42
901	Harry	8+19.50	55.53	LT.	Begin Northwest Retaining Wall	1678033.49	1646361.34
902	Harry	8+31.50	33.33	LT.	End Northwest Retaining Wall	1678008.53	1646365.04
903	Harry	8+31.50	28.33	RT.	End Southwest Retaining Wall	1677950.57	1646343.97
904	Harry	8+20.50	48.80	RT.	Begin Southwest Retaining Wall	1677935.09	1646326.63
905	Harry	12+01.50	35.92	LT.	End Northeast Retaining Wall	1677884.54	1646713.65
906	Harry	11+83.50	33.33	LT.	Begin Northeast Retaining Wall	1677888.26	1646695.85
907	Harry	11+83.50	28.33	RT.	Begin Southeast Retaining Wall	1677830.30	1646674.78
908	Harry	12+00.47	46.72	RT.	End Southeast Retaining Wall	1677807.22	1646684.45

Note: See Plans for Location of Coordinate Data Points

CITY OF WICHITA

wsp

HARRY STREET BRIDGE
OVER ARKANSAS RIVER

COORDINATE DATA

REVISIONS

NO.	DATE	DESCRIPTION

PROJ NO:	35838B
SCALE:	AS NOTED
DATE:	.
DESIGNED BY:	--
DRAWN BY:	--
CHECKED BY:	-
YEAR:	2019

SHEET NO
4
SHEET 4 OF 135

Plotted : 10/3/2019 2:10:44 PM File : T:\35838A-CCW_HarrySt\Bridge\Cadd\Sheets\Roadway\Details\838CON02.dgn