




Plotted : 10/3/2019 2:16:15 PM File : T:\35838A-COW_HarrySBridge\Cadd\Sheets\Landscape\838LDSCP01.dgn



Notes:
 The Contractor shall have the option to hydro-mulch the areas identified on the plans to be sodded with Buffalo Sod.
 The mulch shall be applied at a rate of 2500 lbs/acre and have 6% tackifier.
 The seed at a rate of 2 lbs/1,000 sf of Buffalo Seed and 1 lbs/1,000 sf of Annual Rye Seed.
 If the Contractor chooses this option they will be required to maintain a warranty for one year.
 See Sh. No. 85 for Recipitation of Landscape quantities.
 See Sh. No's. 86 - 87 for Erosion Control Plans.

SUMMARY OF LANDSCAPE QUANTITIES (FOR INFORMATION ONLY)		
ITEM	QUANTITY	UNIT
Sodding - Buffalo Sod	1	Ac.

- LEGEND**
-  Buffalo Sod
 -  Rip-Rap (Remove & Replace)
 -  Rip-Rap, Light Stone (18")



**HARRY STREET BRIDGE
 OVER ARKANSAS RIVER**
LANDSCAPING PLAN
STA. 100+00 TO STA. 105+00

NO.	DATE	DESCRIPTION

PROJ NO: 35838B
 SCALE: 1" = 20'
 DATE: . . .
 DESIGNED BY: . . .
 DRAWN BY: . . .
 CHECKED BY: . . .
 YEAR: 2019
 SHEET NO
93
 SHEET 93 OF 135