



159TH E CT CY Excavation (unadjusted)			
Station	Area	Volume	Total
-0+50	0.00	0.00	0.00
-0+35	8.73	2.42	2.42
-0+15	24.09	12.15	14.58
0+00	26.94	14.17	28.75
0+25	22.17	22.74	51.49
0+49.99	12.96	16.26	67.75
1+00	13.01	24.06	91.81
1+50	13.08	24.16	115.96
2+00	13.14	24.27	140.24
2+50	13.83	24.99	165.22
3+00	13.82	25.63	190.85
3+50	13.76	25.55	216.40
3+77.84	14.81	14.73	231.12
4+15.83	21.16	25.30	256.43
4+46.26	13.50	19.53	275.95
4+50	13.59	1.88	277.83
5+00	13.45	25.03	302.87
5+50	13.93	25.34	328.21
6+00	13.83	25.67	353.88
6+50	13.05	24.89	378.77
7+00	12.87	24.00	402.77
7+50	12.96	23.92	426.69
8+00	13.15	24.18	450.87
8+50	13.43	24.62	475.48
8+66.27	13.09	7.99	483.48
9+00	25.90	24.36	507.83
9+16.26	26.91	15.90	523.73
9+31.26	24.40	14.25	537.99
9+51.26	8.62	12.23	550.22

159TH E CT CY Loose Fill (unadjusted)			
Station	Area	Volume	Total
-0+50	0.00	0.00	0.00
-0+35	22.49	6.25	6.25
-0+15	10.93	12.38	18.62
0+00	10.17	5.86	24.48
0+25	13.05	10.75	35.24
0+49.99	10.62	10.95	46.19
1+00	10.57	19.63	65.82
1+50	10.52	19.53	85.35
2+00	10.47	19.43	104.78
2+50	10.41	19.33	124.11
3+00	10.36	19.23	143.34
3+50	10.31	19.13	162.48
3+77.84	10.28	10.61	173.09
4+15.83	4.42	10.34	183.42
4+46.26	10.08	8.17	191.59
4+50	10.09	1.40	192.99
5+00	10.20	18.79	211.77
5+50	10.32	19.00	230.77
6+00	10.43	19.21	249.98
6+50	10.55	19.42	269.40
7+00	10.70	19.67	289.07
7+50	10.62	19.74	308.81
8+00	10.62	19.66	328.47
8+50	10.62	19.66	348.14
8+66.27	10.62	6.40	354.54
9+00	10.98	13.49	368.03
9+16.26	9.71	6.23	374.26
9+31.26	10.84	5.71	379.97
9+51.26	21.95	12.14	392.11

159TH CT E