QUANTITIES SHEET

SIGNS, POSTS, & FOOTINGS TO BE INSTALLED ON PROJECT

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 TE-0451-01	2018	119	222

PLAN SHEET NUMBER	PLAN STATION NUMBER	(CL) LOCATION / LATERAL POSITION	SIGN DESIGNATION	SIGN SIZE	SIGN LAYOUT SHEET NUMBER	TYPE OF SIGN			4" X 6" POSTS			3I2.25 ALUMINUM BEAM	U-POSTS		GALVANIZED STEEL BEAM POSTS						CONCRETE FOOTINGS					TYPE OF SIGN STRUCTURE OR SUPPORT MOUNT						MOUNT ABOVE SIGN DESIGNATION
									WOOD		STEEL				W6x9		W10x12		W10x22		WOOD POST	STEEL BEAM POST										
																						A36		A572 (ALT)							
						FLAT SHEET	REINFORCED PANEL	OVERLAY	FLAT SHEET SIGN	REINFORCED PANEL SIGN	STRUCTURAL TUBING		2 LB PER FT	3 LB PER FT	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)		18" DIA.	24" DIA.	30" DIA.	24" DIA.	30" DIA.	OVERHEAD	CANTILEVER	BUTTERFLY	BRIDGE MOUNT	MAST ARM	VERT. SUPPORT	
	99+10	R/S	RI-2	18"x18"		X			X																							
	99+63	L/S	RI-2	18"x18"		X			X																							
	124+96	R/S	W3-1a	18"x18"		X			X																							
	125+96	R/S	RI-1	18"x18"		X			X																							
	126+22	L/S	W11-15, W16-7P, W16-8P	36"x36", 24"x12", 24"x12"		X			X																							
	126+22	L/S	W11-15, W11-15P, W16-8P	36"x36", 24"x18", 24"x12"		X			X																							
	126+76	R/S	W11-15, W16-7P, W16-8P	36"x36", 24"x12", 24"x12"		X			X																							
	126+76	R/S	W11-15, W11-15P, W16-8P	36"x36", 24"x18", 24"x12"		X			X																							
	126+90	L/S	W3-1a	18"x18"		X			X																							
	127+90	L/S	RI-1	18"x18"		X			X																							
	178+14	R/S	W3-1a	18"x18"		X			X																							
	179+14	R/S	RI-1	18"x18"		X			X																							
	179+31	L/S	W11-15, W16-7P, W16-8P	36"x36", 24"x12", 24"x12"		X			X																							
	179+31	L/S	W11-15, W11-15P, W16-8P	36"x36", 24"x18", 24"x12"		X			X																							
	179+62	R/S	W11-15, W16-7P, W16-8P	36"x36", 24"x12", 24"x12"		X			X																							
	179+62	R/S	W11-15, W11-15P, W16-8P	36"x36", 24"x18", 24"x12"		X			X																							
	179+79	L/S	W3-1a	18"x18"		X			X																							
	180+79	L/S	RI-1	18"x18"		X			X																							
	231+14	R/S	W3-1a	18"x18"		X			X																							
	232+14	R/S	RI-1	18"x18"		X			X																							
	232+27	L/S	W11-15, W16-7P, W16-8P	36"x36", 24"x12", 24"x12"		X			X																							
	232+27	L/S	W11-15, W11-15P, W16-8P	36"x36", 24"x18", 24"x12"		X			X																							
	232+62	R/S	W11-15, W16-7P, W16-8P	36"x36", 24"x12", 24"x12"		X			X																							
	232+62	R/S	W11-15, W11-15P, W16-8P	36"x36", 24"x18", 24"x12"		X			X																							
	Parking Lot	-	R7-8	12"x18"		X			X																							
	Parking Lot	-	R7-8	12"x18"		X			X																							

CENTERLINE LOCATION
L - LEFT OF CENTERLINE
R - RIGHT OF CENTERLINE
C - ON THE CENTERLINE

LATERAL POSITION
S - SHOULDER MOUNT
O - OFFSET MOUNT
G - GORE MOUNT
M - MEDIAN MOUNT

NOTE: SEE STANDARD PLAN SHEET TE590 FOR DETAILED SPECIFICATIONS.

NO.	DATE	REVISIONS	BY	APP'D
1	7/23/10	Added Coupler and Coupler/Footing Quantity	D.D.G.	D.B.

FHWA APPROVAL			7/23/2010	APP'D	Steven A. Buckley		
DESIGNED	D.D.G.	DETAILED	K.S.	QUANTITIES		TRACED	B.B.
DESIGN CK.	S.A.B.	DETAIL CK.	D.D.G.	QUAN. CK.		TRACE CK	

~~TE430~~

7/1/03

KDOT Graphics Certified 07-27-2018

KDOT Graphics Certified

Drawn By: $$USERNAME$$ Plotted: $SYTIME$$
File: $$DGNSPEC$$ $$KDOTGRP$$