

SANITARY SEWER EXTENSION

to serve

Consolidation of Lift Stations near 151st & Kellogg

CITY OF WICHITA, KANSAS

Gary Janzen, P.E. City Engineer

Project Number 468-85253

O.C.A. NO. 620787 & 669110

GENERAL NOTES:

1. The Contractor shall comply with all applicable safety regulations. All construction shall be completed following current City Standard Specifications and Special Provisions.

2. Contractor will be required to provide notice to utility companies a minimum of seventy-two (72) hours prior to any excavation, as follows:

Kansas One-Call 687-2470

The Contractor must notify the following in case of an emergency:

AT&T 1-800-246-8464
 Black Hills Energy 1-800-694-8989
 City of Goddard 1-316-648-5899
 City of Wichita Water & Sewer Dept. 1-316-219-8921
 City of Wichita Stormwater 1-316-268-4090
 City of Wichita Traffic 1-316-268-4034
 Cox Communications 1-888-249-3530
 Kansas Fiber Network 1-800-778-9140
 Kansas Gas Service 1-888-482-4950
 OneOK Field Services 1-866-261-1099
 Sedgwick Co. RWD#4 1-316-794-8891
 Westar Energy (now known as Evergy) 1-800-544-4857

3. Utility service lines, poles, etc. are to be adjusted as necessary by others prior to construction unless the plans specifically call for their adjustment by the Contractor or unless the plans specifically identify a utility to be adjusted by its owner during construction. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.

4. Rubble from the removal of miscellaneous structures and excess excavation which is to be wasted shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations, in the opinion of the Engineer, that will leave an unsightly appearance will not be approved. All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain will require a Kansas State Board of Agriculture permit. Any material dumped in waters of the United States or wetlands is subject to U.S. Corps of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits will require additional archaeological investigations unless buried in a previously approved borrow location.

5. Trees and shrubs in public right-of-way which are in direct conflict with proposed new construction shall be removed by the Contractor with the Engineer's approval. Trees and shrubs which are not in direct conflict with proposed new construction shall be saved and protected from damage.

6. The Contractor shall give all property owners and/or tenants of developed property abutting the construction of this project a minimum of ten (10) days written notice prior to start of construction.

7. The Contractor shall be responsible for preserving property irons. The Contractor will be required to re-establish any property irons which are damaged or destroyed by his construction operations. Such irons shall be re-established by a licensed land surveyor in accordance with state laws.

8. If traffic will be impacted by construction, a traffic control plan must be prepared in accordance with Sedgwick County, KS standard specifications and details. Traffic on 151st Street and all publicly owned rights-of-way must be maintained during construction. The Contractor shall be responsible for all traffic control measures to facilitate construction. All construction zone markings and signage shall conform to the latest version of the Manual on Uniform Traffic Control Devices (MUTCD) as published by the US Dept. of Transportation, Federal Highway Administration. All costs associated with construction markings and signage shall be the Contractors responsibility.

10. All elevations shown are NAVD 88, G12B.

11. All areas disturbed during construction that will not be under proposed pavement shall be restored to match existing conditions.

12. The Contractor shall protect from damage and support existing utilities through constructions as approved by the utility owner and the Engineer at the contractors expense.

13. Contractor shall limit the extent of trench openings overnight and weekends to less than 50 feet.

14. All stubs and plugged pipes shall be located with green plastic tape in the same manner as risers.

15. Connecting to Existing Manholes:

Prior to laying sewer lines using existing stubs in existing manholes, the Contractor shall expose and verify the elevation, grade and alignment of existing stubs and notify the Engineer of any deviation from the plans. Where connection to an existing manhole that does not have an existing stub or the stub is unusable due to elevation grade or alignment, the Contractor shall bore cut into existing manhole wall to make connection using approved water stop gasket, and reshape the existing manhole invert to provide smooth flow. The cost to connecting to existing manholes is incidental to the project.

16. Contractor shall provide positive drainage away from all manhole covers.

17. The Contractor shall prevent any construction debris from entering the existing sanitary sewer during construction.

18. The Contractor shall be responsible for maintaining continuous flow of sewage through construction. Contractors proposed method for maintaining sewage flow shall be submitted and approved by the Sewer Maintenance Division (316-268-4073) prior to starting and by-passing of sewage flows.

19. Any over excavation from manhole and pipe removal shall be backfilled with Type 1 Pipe Bedding.

20. No shrink or swell factors have been applied to the earthwork quantities shown on this project. All earthwork quantities are based on raw surface volume comparisons.


21. Excess dirt generated from installation of underground utilities is to be removed from this site.

22. The entire project shall be seeded, fertilized and mulched per the specifications. No rye grass shall be used across Parcel 252713. Buffalo grass seed shall be utilized across this property with fertilizer and mulch at the standard specified rate.

23. When accessing the site through mobile home parks the contractor shall use the defined roads as much as possible. If access requires other means the contractor is responsible for restoring the site. Access to all homes must be maintained at all times.

24. A measured quantity will be bid for temporary fence and only used as directed by the engineer. Temporary fence shall be a 4 ft. tall woven wire (welded wire fence) with a single strand electrical wire running above the woven wire fence with steel posts spaced at 12 ft. maximum spacing. Fencing shall be adequate to contain all livestock and horses. Contractor shall be responsible for all temporary power supply for the fence.

25. All topsoil along the entire project shall be stripped to a minimum depth of 12" and restored during finish grading of the site. This shall be subsidiary to site clearing and restoration.





Benchmarks


POINT #1
 TOP OF VERTICAL RAIL 61' SOUTH OF PATH & 24' EAST OF CENTER LINE OF 151ST STREET W.
 ELEVATION = 1395.56 (NAVD88, G12B)

POINT #2
 SQUARE CUT, WEST END OF STORM SHELTER LOCATED IN MOBILE HOME PARK BETWEEN 151ST AND 155TH STREETS
 ELEVATION = 1401.68 (NAVD88, G12B)

POINT #3
 SQUARE CUT, SOUTH END OF WEST HEADWALL OF BOX CULVERT, 22' NORTH OF CENTER LINE OF AVENUE F & 22' NORTH OF CENTER LINE OF LAKE DR. LOCATED IN MOBILE HOME PARK BETWEEN 155TH AND 167TH STREETS
 ELEVATION = 1408.86 (NAVD88, G12B)



Sheet Number	Sheet Title
1	SS Titlesheet
2	SS Line 1 (1 of 3)
3	SS Line 1 (2 of 3)
4	SS Line 1 (3 of 3)
5	SS Line 2
6	SS Line 3
7	SS Line 4
8	SS Line 5
9	SS Force Main
10	Lift Station Site Plan
11	Lift Station Plan
12	LIFT STATION SECTION
13	Lift Station Details
14	ONLINE DIAGRAM AND ELEVATIONS
15	ELECTRICAL SITE PLAN
16	ELECTRICAL POWER PLAN
17	WET WELL ELEVATION AND MPZ01 PANEL SCHEDULE
18	ELECTRICAL DETAILS I
19	ELECTRICAL DETAILS II
20	ELECTRICAL DETAILS III
21	ELECTRICAL DETAILS IV
22	SCREEN WALL FOUNDATION PLAN, SECTION AND NOTES
23	ORNAMENTAL GATE & MOW STRIP DETAIL
24	Force Main Abandonment
25	Bubble Map SS Pnts
26	Bubble Map Control Pnts
27	Pre-Cast SS MH
28	MH Frame & Cover
29	Vertical Riser
30	Tracer Wire SS
31	Erosion Control Plan
32	BOC
33	Silt Fc
34	Straw Bale
35	SIP
36	SDP



Digitally Signed 11/19/2019

PLANS PREPARED BY



GARVER
 8535 E 21st St, Suite 130
 Wichita, KS 67206
 (316) 264-8008
 www.GarverUSA.com

NOVEMBER 2019