




© 2019 GARVER, LLC
 THIS DOCUMENT, ALONG WITH THE IDEAS AND DESIGNS CONVEYED HEREIN, SHALL BE CONSIDERED INSTRUMENTS OF PROFESSIONAL SERVICE AND ARE PROPERTY OF GARVER, LLC. ANY USE, REPRODUCTION, OR DISTRIBUTION OF THIS DOCUMENT, ALONG WITH THE IDEAS AND DESIGN CONTAINED HEREIN, IS PROHIBITED UNLESS AUTHORIZED IN WRITING BY GARVER, LLC OR EXPLICITLY ALLOWED IN THE GOVERNING PROFESSIONAL SERVICES AGREEMENT FOR THIS WORK.



Digitally Signed 11/19/2019

REV.	DATE	DESCRIPTION	BY



CITY OF WICHITA
 WICHITA, KANSAS
 Consolidation of Lift Stations
 Near 151st St. & W. Kellogg


Erosion Control Plan

JOB NO.: 17264967
 DATE: NOV. 2019
 DESIGNED BY: MTD
 DRAWN BY: MTD

BAR IS ONE INCH ON ORIGINAL DRAWING
 0 1"
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.


DRAWING NUMBER

SHEET NUMBER **31 OF 36**



- Notes
- Contractor to avoid tracking out sediment, dirt and/or debris from the job site. The contractor shall provide construction entrances at all locations along the project where construction vehicles and equipment will be entering and leaving the site. Construction entrances shown on this plan are for informational purposes only. Contractor may change the location of entrances as needed.
 - Sediment barriers shall be installed near all drainage ways that are susceptible to receiving sediment in runoff.
 - All culverts susceptible to sediment and silt from the construction shall have the upstream end protected with sediment control measures.
 - All disturbed areas susceptible to concentrated flow or erosion such as ditch crossings shall have erosion control mat installed.
 - All areas disturbed shall be restored to preexisting conditions including but limited to seeding within 2 weeks of restoration of site.
 - The best management practices (BMPs) shown on this sheet are for information only. The contractor shall adjust all BMPs as needed prevent erosion and sediment from leaving the site.

LIMITS OF CONSTRUCTION



File: L:\2017\17264967 - LS 53 Replacement No. 1\Drawings\C3D\Plan Sheets\SWPPP.dwg Last Save: 11/18/2019 5:09 PM Last saved by: MTDolechek
 Last plotted by: Dolechek, Mark T. Plot Style: --- Plot Scale: 1:2,584.9 Plot Date: 11/19/2019 6:49 AM Plotter used: None