

| AC PAVEMENT 7" (5" BIT. BASE) | | | | | |
|-------------------------------|----------|-------------|------|-----------------|--------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. yds.) | |
| 95+77.00 | 99+19.36 | Maize Rd. | Rt. | Roadway | 456.55 |
| 46+72.25 | 48+50.00 | 29th Street | - | Roadway | 193.29 |
| 52+35.00 | 54+99.24 | 29th Street | - | Roadway | 287.81 |
| TOTAL: | | | | | 937.65 |

| AC PAVEMENT 7" (5" CONCRETE BASE) | | | | | |
|-----------------------------------|----------|-------------|------|-----------------|-------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. yds.) | |
| 46+72.25 | 46+96.10 | 29th Street | Rt. | Pavement | 9.70 |
| 54+75.10 | 54+99.24 | 29th Street | Lt. | Pavement | 4.40 |
| TOTAL: | | | | | 14.10 |

| CONCRETE PAVEMENT, 4" (MEDIAN) | | | | | |
|--------------------------------|----------|-------------|------|-----------------|-------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. yds.) | |
| 47+99.00 | 48+50.00 | 29th Street | Lt. | Median | 8.50 |
| 52+35.00 | 52+85.00 | 29th Street | Rt. | Median | 7.41 |
| TOTAL: | | | | | 15.91 |

| CONCRETE PAVEMENT 9" (REINFORCED) | | | | | |
|-----------------------------------|----------|-------------|------|-----------------|--------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. yds.) | |
| 99+19.36 | 99+70.09 | Maize Rd. | Rt. | Curb Return | 151.04 |
| 51+22.00 | 51+48.00 | 29th Street | Rt. | Curb Return | 63.52 |
| TOTAL: | | | | | 214.56 |

| CRUSHED ROCK BASE 6", REINFORCED | | | | | |
|----------------------------------|----------|-------------|------|-----------------|--------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. yds.) | |
| 99+19.36 | 99+70.09 | Maize Rd. | Rt. | Curb Return | 159.51 |
| 51+22.00 | 51+48.00 | 29th Street | Rt. | Curb Return | 69.05 |
| TOTAL: | | | | | 228.56 |

| CRUSHED ROCK BASE 8", REINFORCED | | | | | |
|----------------------------------|----------|-------------|------|-----------------|----------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. yds.) | |
| 95+77.00 | 99+19.36 | Maize Rd. | Rt. | Roadway | 589.93 |
| 46+72.25 | 48+50.00 | 29th Street | - | Roadway | 273.80 |
| 52+35.00 | 55+05.25 | 29th Street | - | Roadway | 442.45 |
| TOTAL: | | | | | 1,306.18 |

| CONCRETE C & G, TYPE 1 (6" & 1-1/2") | | | | |
|--------------------------------------|----------|-------------|--------------|--------|
| STA. TO STA. | ROADWAY | SIDE | LENGTH (ft.) | |
| 95+77.00 | 99+19.36 | Maize Rd. | Rt. | 342.81 |
| 51+33.40 | 51+48.00 | 29th Street | Rt. | 14.36 |
| TOTAL: | | | | 357.17 |

| CONCRETE C & G, TYPE 3 (8" & 1-1/2") | | | | |
|--------------------------------------|----------|-------------|--------------|--------|
| STA. TO STA. | ROADWAY | SIDE | LENGTH (ft.) | |
| 46+80.31 | 47+18.47 | 29th Street | - | 24.14 |
| 47+99.00 | 48+50.00 | 29th Street | Lt. | 60.00 |
| 52+35.00 | 52+85.00 | 29th Street | Rt. | 100.00 |
| 54+60.49 | 54+99.24 | 29th Street | - | 79.00 |
| TOTAL: | | | | 263.14 |

| CONCRETE C & G, TYPE 3 (8" & 1-1/2") (SPECIAL) | | | | |
|--|----------|-------------|--------------|--------|
| STA. TO STA. | ROADWAY | SIDE | LENGTH (ft.) | |
| 47+18.47 | 47+99.00 | 29th Street | Lt. | 80.56 |
| 52+85.00 | 54+60.49 | 29th Street | Rt. | 175.49 |
| TOTAL: | | | | 256.05 |

| CONCRETE CURB, MONO EDGE | | | | |
|--------------------------|-----------|------|-------------|--------------|
| STATION | ROADWAY | SIDE | TYPE | LENGTH (ft.) |
| 99+70.09 | Maize Rd. | - | Curb Return | 77.52 |
| 95+77.00 | Maize Rd. | - | Drive | 62.44 |
| TOTAL: | | | | 139.96 |

| CONCRETE DRIVEWAY 8", REINFORCED | | | |
|----------------------------------|-----------|------|----------------|
| STATION | ROADWAY | SIDE | AREA (sq. ft.) |
| 95+22.00 | Maize Rd. | Rt. | 2,024.70 |
| TOTAL: | | | 2,024.70 |

| CONCRETE SIDEWALK, 4" | | | | | |
|-----------------------|----------|-------------|------|----------------|--------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. ft.) | |
| 51+16.00 | 51+48.00 | 29th Street | Rt. | Sidewalk | 187.62 |
| TOTAL: | | | | | 187.62 |

| CONCRETE SIDEWALK, 5" | | | | | |
|-----------------------|----------|-----------|------|----------------|----------|
| STA. TO STA. | ROADWAY | OFFSET | TYPE | AREA (sq. ft.) | |
| 95+55.50 | 99+55.50 | Maize Rd. | Rt. | Sidewalk | 4,001.15 |
| TOTAL: | | | | | 4,001.15 |

| STORM WATER STRUCTURES | | | | | |
|------------------------|---------|------------|-----------------------|---------------|--|
| STRUCTURE NAME | STATION | LINE | STRUCTURE TYPE | RIM ELEVATION | CONNECTED PIPES (Flow Elev., Size, Shape, Direction, In or Out) |
| Structure - (286) | ??? | SWS Line 1 | Inlet, Curb (Type 1) | 1351.20 | 1347.77, 15"x15" RCP, Circular, NW, Out |
| Structure - (283) | 0+00.00 | SWS Line 1 | MH, Shallow SWS (6') | 1352.29 | 1346.95, 36"x36" RCP, Circular, N, In 1346.95, 36"x36" RCP, Circular, S, Out 1347.50, 15"x15" RCP, Circular, SE, In |
| Structure - (282) | 0+91.95 | SWS Line 1 | Inlet, Curb (Type 1A) | 1352.09 | 1347.03, 36"x36" RCP, Circular, N, In 1347.03, 36"x36" RCP, Circular, S, Out |
| Structure - (281) | 2+91.92 | SWS Line 1 | Inlet, Curb (Type 1A) | 1352.39 | 1347.19, 36"x36" RCP, Circular, N, In 1347.19, 36"x36" RCP, Circular, S, Out |
| Structure - (284) | 3+66.72 | SWS Line 1 | MH, Shallow SWS (6') | 1352.20 | 1347.25, 36"x36" RCP, Circular, S, Out 1347.25, 29"x45" RCP, Horizontal Elliptical, N, In 1347.62, 15"x15" RCP, Circular, NE, In |