



PAVING IMPROVEMENTS
TO SERVE
FONTANA 5TH - PHASE 2

GARY JANZEN, P.E. - CITY ENGINEER
CITY OF WICHITA PROJECT NO. 472-84802
OCA NO. 768486

Issue:	
JOB NO.	190592-000
DATE	FEBRUARY 2020
PM	BMM
DESIGNED BY	AKL
DRAWN BY	BJS
CHECKED BY	RJS

EROSION CONTROL PLAN



GENERAL NOTES











- CONTRACTOR SHALL INSTALL AND MAINTAIN EROSION PROTECTION THROUGHOUT THE ENTIRE PROJECT. THE FOLLOWING QUANTITIES ARE PROVIDED PER PROJECT. THE FOLLOWING QUANTITIES SHALL BE INCLUDED IN BID ITEMS FOR EACH RESPECTIVE PART. EROSION PROTECTION SHALL BE INCLUDED IN THE BID AS FOLLOWS:

PAVING AND DRAINAGE (472-84802)	
CURB INLET PROTECTION	3 EACH
AREA INLET PROTECTION	5 EACH
BACK OF CURB PROTECTION	3,458 L.F.
TEMPORARY SEEDING	1.2 ACRE
STABILIZED CONSTRUCTION ENTRANCE	2 EACH
SANITARY SEWER (468-84586)	
SILT FENCE BARRIER	2,447 L.F.
STORM WATER DRAIN (468-84589)	
AREA INLET PROTECTION	1 EACH
DITCH CHECK	5 EACH
TEMPORARY SEEDING	1 L.S.
PERMANENT SEEDING	1 L.S.
- THE EROSION CONTROL DEVICES SHOWN ON THIS SHEET ARE CONSIDERED MINIMUM STANDARDS. WHENEVER SEDIMENT ENTERS THE STREETS, STORM SEWERS, DITCHES, OR PONDS, CONTRACTOR WILL INSTALL ADDITIONAL DEVICES, AS NEEDED, TO CORRECT THE PROBLEM.
- THE EROSION CONTROL DEVICES SHOWN HEREON MUST BE IN PLACE AT ALL TIMES DURING CONSTRUCTION UNTIL SUCH TIME AS THE SITE IS REESTABLISHED WITH PAVING OR GRASS. TEMPORARY OR PERMANENT SEEDING AND MULCH WILL BE INSTALLED WHEN EARTHWORK ACTIVITIES CEASE IN AN AREA FOR 14 DAYS OR MORE.
- ANY MUD INADVERTENTLY TRACKED ONTO ANY STREET SHALL BE CLEANED UP BY THE CONTRACTOR, AT THE END OF EACH DAY'S WORK, OR AS DIRECTED BY THE FIELD ENGINEER.
- CONTRACTOR TO FURNISH A TRUCK WASH-OUT PIT TO BE PLACED AT A CONVENIENT LOCATION THAT DOES NOT CONFLICT WITH CONSTRUCTION. CONTRACTOR SHALL CLEAN OUT AND BACKFILL PIT PRIOR TO FINAL INSPECTION. LOCATION SHALL BE APPROVED BY THE FIELD ENGINEER.

SEEDING NOTES

THE CONTRACTOR SHALL APPLY TEMPORARY SEED AND MULCH TO ALL UNPAVED AREAS DISTURBED BY CONSTRUCTION. TEMPORARY SEED (ANNUAL RYEGRASS) AND MULCH PER SPECIFICATIONS. TEMPORARY SEEDING AND MULCHING SHALL BE PAID FOR AT THE LUMP SUM PRICE FOR "SEEDING, TEMPORARY".

LEGEND

-  STABILIZED CONSTRUCTION ENTRANCE
-  BACK OF CURB PROTECTION
-  PROPOSED CURB INLET PROTECTION
-  PROPOSED AREA INLET PROTECTION
-  SILT FENCE DITCH CHECKS (DRAINAGE)
-  SILT FENCE BARRIER (DRAINAGE)
-  SILT FENCE BARRIER (SANITARY SEWER)
-  PROPOSED WATER MAIN
-  PROPOSED SANITARY SEWER LINE
-  PROPOSED STORM WATER SEWER

Sheet: 02-06-2020, 7:05:33 PM, by: BJS
 Plot: Scale: 1:1, 02-21-2020, 11:46:42 AM, by: BJS
 U:\Wichita-Civil\2019\190592\Drawings\190592-000-16-CP402-EROSION CONTROL PLAN