




W. Kellogg (US54)

Notes

1. Contractor to avoid tracking out sediment, dirt and/or debris from the job site. The contractor shall provide construction entrances at all locations along the project where construction vehicles and equipment will be entering and leaving the site. Construction entrances shown on this plan are for informational purposes only. Contractor may change the location of entrances as needed.
2. Sediment barriers shall be installed near all drainage ways that are susceptible to receiving sediment in runoff.
3. All culverts susceptible to sediment and silt from the construction shall have the upstream end protected with sediment control measures.
4. All disturbed areas susceptible to concentrated flow or erosion such as ditch crossings shall have erosion control mat installed.
5. All areas disturbed shall be restored to preexisting conditions including but limited to seeding within 2 weeks of restoration of site.
6. The best management practices (BMPs) shown on this sheet are for information only. The contractor shall adjust all BMPs as needed prevent erosion and sediment from leaving the site.

-  LIMITS OF CONSTRUCTION
-  EROSION CONTROL MAT
-  SILT FENCE

Install Erosion Control Mat Along Slopes of Drainage Ditch (520 SY)

Install Construction Entrance (1 EA) Field Locate

Install Construction Entrance (1 EA) Field Locate

Install Erosion Control Mat Along Slopes Near Drainage Ditch and Adjacent to Pavement (440 SY)

Sanitary Sewer

Install Silt Fence Along Edge of TCE. (1135 LF)

Install Construction Entrance (1 EA) Field Locate

Install Silt Fence Along Edge of TCE or Channel (564 LF)

Install Erosion Control Mat Along Slopes and Along Drainage Ditch (1960 SY)

Zone A
Flood Plain

S 155th Street W

File: L:\2019\19T41008 - CoW Sanitary Sewer to LS47\Drawings\C3D\Plan Sheets\SWPPP.dwg Last Save: 7/6/2020 3:13 PM Last saved by: MTDolechek
Last plotted by: Dolechek, Mark T. Plot Style: --- Plot Scale: 1:2,884.9 Plot Date: 7/24/2020 8:28 AM Plotter used: None



© 2018 GARVER, LLC
THIS DOCUMENT, ALONG WITH THE IDEAS AND DESIGNS CONVEYED HEREIN, SHALL BE CONSIDERED INSTRUMENTS OF PROFESSIONAL SERVICE AND ARE PROPERTY OF GARVER, LLC. ANY USE, REPRODUCTION, OR DISTRIBUTION OF THIS DOCUMENT, ALONG WITH THE IDEAS AND DESIGN CONTAINED HEREIN, IS PROHIBITED UNLESS AUTHORIZED IN WRITING BY GARVER, LLC OR EXPLICITLY ALLOWED IN THE GOVERNING PROFESSIONAL SERVICES AGREEMENT FOR THIS WORK.



Digitally Signed 07/24/2020

REV.	DATE	DESCRIPTION	BY



CITY OF WICHITA
WICHITA, KANSAS
Sanitary Sewer from
Lift Station 47

Erosion Control Plan

JOB NO.: 19T41008
DATE: Jul 2020
DESIGNED BY: MTD
DRAWN BY: MCP

BAR IS ONE INCH ON ORIGINAL DRAWING
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

DRAWING NUMBER

SHEET NUMBER **10** OF **15**