

RECAPITULATION OF BRIDGE QUANTITIES		
BRIDGE NUMBER	STATION	SEE SHEET NO.
43040087610010	25 + 75	24. Proj. 87U-1247-01

[illegible]

COMBINED CURB & GUTTER (AE)						
LOCATION				(AE) Type I (Lin. Ft.)	(AE) ROLL TYPE (Lin. Ft.)	REMARKS
STA. TO STA.		ROADWAY	SIDE			
PROJECT 87U-1247-01						
23 + 30	24 + 94.8	GEO. WASH. BLVD.	LT	165		
23 + 30	24 + 61.2	GEO. WASH. BLVD.	RT	131		
TOTAL:				296		296 TOTAL L.F. CURB & GUTTER

RECAPITULATION OF REMOVAL OF STRUCTURES			
STA.	SIDE	ITEM	QUANTITY
23+85	℄	BRIDGE	1 EACH
27+16	℄	36" R.C.P.	95 L.F.

8" CRUSHED STONE SUBGRADE				
STATION TO STATION		ROADWAY	WIDTH	8" CRUSHED STONE SUBGRADE (S.Y.)
PROJECT 87U-1247-01				
23 + 30	24 + 78	GEO. WASH. BLVD.	51'	839
TOTALS				839

10" CONCRETE PAVEMENT (UNIF)(AE)			
STATION TO STATION	SIDE	QUANTITY	UNIT
24+28.17 TO 24+78.17	☺	277	S.Y.
26+71.83 TO 27+21.83	☺	277	S.Y.
TOTALS		554	

6" CONCRETE PAVEMENT (UNIF) (AE)			
STATION	SIDE	QUANTITY	UNIT
24+43.43	RT.	17	S.Y.
24+87.54	LT.	13	S.Y.
26+62.46	RT.	13	S.Y.
27+06.57	LT.	17	S.Y.
TOTALS		60	

24" ROCK EMBANKMENT		
STATION TO STATION	QUANTITY	UNIT
24+24.90 RT. TO 25+73.46 LT.	646.3	C.Y.
24+86.17 RT. TO 26+09.90 LT.	226.3	C.Y.
25+39.83 RT. TO 26+63.56 LT.	226.3	C.Y.
25+76.29 RT. TO 27+24.84 LT.	646.3	C.Y.
26+94.61 LT. TO 27+42.68 LT.	94.8	C.Y.
TOTALS	1,840	

CONCRETE SAFETY BARRIER (SPECIAL)(AE)		
STATION TO STATION	QUANTITY	UNIT
24+28.53 RT. TO 24+61.53 RT.	33	L.F.
24+62.14 LT. TO 24+95.14 LT.	33	L.F.
26+54.86 RT. TO 26+87.86 RT.	33	L.F.
26+88.47 LT. TO 27+21.47 LT.	33	L.F.
TOTALS	132	

[illegible]

EARTHWORK														
STATION to STATION	EXCAVATION					COMPACTION			THROUGH CUTS NOT SUBGRADED			* EMBANKMENT (CU.YDS.)		▲PLACE. SELECT SOIL CU.YDS.
	COMMON		ROCK		CONTR. FURN. CU.YDS.	TYPE AA MR-5 CU.YDS.	TYPE B MR-90 CU.YDS.		COMM. CU.YDS.	TYPE AA CU.YDS.		INITIAL CONSOL.	SETTLE- MENT	
	CU.YDS.	%	CU.YDS.	VMF										
PROJECT 87U-1247-01														
GEO. WASH. BLVD.														
· 23+30 - 24+78	250	35	15	0			1,740							
24+78 - 27+21 (INCLUDING CHANNEL)	39,425	35	270	0			18,825							

* Subsidiary (See General Note). ▲ See General Note.