

DEAD LOAD DEFLECTIONS (FT.)																
Tenth Point Location	ABUTMENT	0. 1 0	0. 2 0	0. 3 0	0. 4 0	0. 5 0	0. 6 0	0. 7 0	0. 8 0	0. 9 0	PIER	0. 1 0	0. 2 0	0. 3 0	0. 4 0	0. 5 0
Glrder Self Weight	0.000	0.029	0.054	0.072	0.081	0.080	0.070	0.053	0.033	0.014	0.000	-0.005	-0.004	0.000	0.004	0.005
Concrete Slab	0.000	0.085	0.158	0.209	0.235	0.233	0.205	0.157	0.099	0.042	0.000	-0.019	-0.021	-0.016	-0.009	-0.006
Total After Slab Pour	0.000	0.114	0.212	0.281	0.316	0.313	0.275	0.210	0.132	0.056	0.000	-0.024	-0.025	-0.016	-0.005	-0.001
Additional Dead Load	0.000	0.028	0.052	0.070	0.079	0.079	0.069	0.053	0.034	0.014	0.000	-0.004	-0.003	0.001	0.004	0.006
Total Deflection	0.000	0.142	0.264	0.351	0.395	0.392	0.344	0.263	0.166	0.070	0.000	-0.028	-0.028	-0.015	-0.001	0.005


DEAD LOAD DEFLECTIONS

Note:
Deflections were computed for a continuous concrete deck placement from end to end of bridge. Should the Contractor request to use an Alternate Pouring Sequence, details for the Alternate Sequence must be provided to the Engineer prior to Girder fabrication.

DEAD LOAD DEFLECTIONS (FT.) AT FIELD SPLICES			
Field Splice Location	NO. 1	NO. 2	NO. 3
Glrder Self Weight	0.039	0.002	0.039
Concrete Slab	0.117	-0.013	0.117
Total After Slab Pour	0.156	-0.011	0.156
Additional Dead Load	0.040	0.002	0.040
Total Deflection	0.196	-0.009	0.196

Girders shall be fabricated such that after total dead load deflections the girder web will be parallel to the finished slab grade as shown on the Table of Pavement Elevations. After the structural steel is completely erected and false work removed, the camber shall be measured in the field by a profile of each girder. Any deviation in the actual camber and total deflection less girder self weight shall be corrected by varying the depth of the concrete fillets over the girders so that the finished slab elevations shall be constructed to the theoretical grade.

"Glrder Self Weight" refers to the deflection due to the weight of all structural steel.
"Concrete Slab" refers to the deflection due to the slab pour.
"Additional Dead Load" refers to the deflection due to the Latex Surface Course, the Curbs and Future Wearing Surface.
"Total Deflection" refers to the total deflection caused by all dead loads.



CAMBER (FT.)																										
Tenth Point Locatlon	ABUTMENT	0. 1 0	0. 2 0	0. 3 0	0. 4 0	0. 5 0	0. 6 0	0. 7 0	0. 8 0	0. 9 0	PIER	0. 1 0	0. 2 0	0. 3 0	0. 4 0	0. 5 0	0. 6 0	0. 7 0	0. 8 0	0. 9 0	PIER	0. 1 0	0. 2 0	0. 3 0	0. 4 0	0. 5 0
Concrete T-Beams	0.000	0.006	0.013	0.018	0.022	0.023	0.021	0.017	0.012	0.006	0.000	-0.008	-0.017	-0.026	-0.034	-0.041	-0.044	-0.041	-0.031	-0.017	0.000	0.035	0.076	0.119	0.154	0.168
Additional Dead Loads	0.000	0.001	0.003	0.004	0.005	0.006	0.005	0.004	0.003	0.002	0.000	-0.002	-0.005	-0.008	-0.012	-0.015	-0.016	-0.015	-0.012	-0.006	0.000	0.013	0.029	0.046	0.060	0.066
Long Term Deflection	0.000	0.007	0.013	0.017	0.021	0.023	0.021	0.017	0.012	0.007	0.000	-0.008	-0.017	-0.027	-0.036	-0.044	-0.048	-0.046	-0.034	-0.018	0.000	0.038	0.084	0.132	0.171	0.187
Total Deflection	0.000	0.014	0.029	0.039	0.048	0.052	0.047	0.038	0.027	0.015	0.000	-0.018	-0.039	-0.061	-0.082	-0.100	-0.108	-0.102	-0.077	-0.041	0.000	0.086	0.189	0.297	0.385	0.421

DEAD LOAD CAMBER DIAGRAM

I			
No.	Revisions	By	Date
CITY OF WICHITA, KANSAS MICHAEL E. LINDEBAK, P.E.-CITY ENGINEER DOUGLAS AVENUE BRIDGE OVER ARKANSAS RIVER DEAD LOAD DEFLECTIONS & CAMBER CITY OF WICHITA PROJECT NO. 472-82721 PROFESSIONAL ENGINEERING CONSULTANTS, P.A. ENGINEERS WICHITA, KANSAS			
Designed by	P.D.F.	Checked by	R.A.S.
Drawn by	W.L.L.	Date	Sept. 1997
		Job No.	95088-4