

FHWA REGION NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	54-87 TE 0039-01	97	41	43

[illegible]

RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
CONSTRUCTION SIGNS (0 TO 9.25 SQ.FT.)	4	EACH PER DAY
CONSTRUCTION SIGNS (9.26 TO 16.25 SQ.FT.)	17	EACH PER DAY
CONSTRUCTION SIGNS (16.26 SQ.FT. & OVER)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE I OR II)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 4' TO 8')		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 9' TO 14')		EACH PER DAY
CONSTRUCTION WARNING LIGHT (TYPE 'B' HIGH INTENSITY)		EACH PER DAY
REFLECTORIZED DRUM	30	EACH PER DAY
ARROW DISPLAY		EACH PER DAY
TUBULAR MARKERS		EACH PER DAY
VERTICAL PANELS (SINGLE TYPE)		EACH PER DAY
VERTICAL PANELS (BACK TO BACK TYPE)		EACH PER DAY
OBJECT MARKERS		EACH PER DAY
CONCRETE SAFETY BARRIER (TYPE I) (TEMPORARY)		SECTION/DAY
CONCRETE SAFETY BARRIER (TYPE IV) (TEMPORARY)		SECTION/DAY
PAVEMENT MARKING (TEMPORARY)		
4' BROKEN (8.2') (TYPE I TAPE)		STA./LINE
4' SOLID (TYPE I TAPE)		STA./LINE
4' BROKEN (8.2') (TYPE II OR IIA TAPE)		STA./LINE
4' SOLID (TYPE II OR IIA TAPE)		STA./LINE
PAVEMENT MARKING (TEMPORARY STRIPING)		
4' BROKEN (3.3') (TYPE II OR IIA TAPE)		MILE/LINE
4' SOLID (TYPE II OR IIA TAPE)		MILE/LINE
EXISTING PAVEMENT MARKING REMOVAL		LIN. FT.
GLARE SCREEN		LIN. FT.
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
INERTIAL BARRIER SYSTEM		EACH
MODULE F200 (REPLACEMENT)		EACH
MODULE F400 (REPLACEMENT)		EACH
MODULE F700 (REPLACEMENT)		EACH
MODULE F1400 (REPLACEMENT)		EACH
MODULE F2100 (REPLACEMENT)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TEMPORARY TRAFFIC SIGNALS		LUMP SUM
TRAFFIC CONTROL		LUMP SUM
FLAGGER (SET)		HOURL

3	7-8-96	REVISED TEMPORARY TAPE	WPR	NAB
2	7-8-94	REVERSE TYPE I AND TYPE II TAPE DESIGNATIONS	WPR	NAB
1	5-23-94	1994 MUTCD REVISIONS	WPR	NAB
NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY OF DEVICES AND RECAPITULATION OF QUANTITIES

