FHWA REGION NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	BTU-1246-01	1990		

SCALE: 1" = 30'

SE 1/4 Sec.13, T27S, R2W

NE 1/4 Sec.13, T27S, R2W

SW 1/4 Sec.18, T27S, R1W

NW 1/4 Sec.18, T27S, R1W

2 Austrian Pine 6'-8'

2 Lace Bark Elm 2 1/2"-3"

3 Cadda Sugar Maple 2"-2 1/2"

2 Capitol Pear 6'-8'

1 London Plane Tree 2 1/2"-3"

3 Marshall Seedless Ash 2 1/2"-3"

3 Redbud 6'-8'

3 Austrian Pine 6'-8'

1/4 Sec. Line

2 Cadda Sugar Maple 2"-2 1/2"

3 Austrian Pine 6'-8'

3 Austrian Pine 6'-8'

3 Autumn Purple Ash 2 1/2"-3"

119th STREET WEST

Hedge Row

Hedge Row

2 Austrian Pine 6'-8'

4 Marshall Seedless Ash 2 1/2"-3"

3 Austrian Pine 6'-8'

3 Austrian Pine 6'-8'

3 Autumn Purple Ash 2 1/2"-3"

[redacted]

NOTE:

All Stationing shown on this sheet is on the Tangent Line of the curve.

P.C. Station=815+66.88
P.I. Station=820+00.00
P.T. Station=824+32.45 Back
824+33.12 Ahead

[redacted]

NOTE:

1. Landscape contractor is to verify the location of all underground utilities prior to installation of plant material. (including sanitary sewer). Utilities can be flagged by calling 687-2470.

NOTE: PLAN SHEET NOS. 9 & 10 WERE SHEETS IN THE CONSTRUCTION PLANS FOR THE BRIDGE AND ARE INCORPORATED INTO THESE PLANS SINCE THESE SHEETS SHOW PLANTINGS TO BE INSTALLED WITH THIS PROJECT.
TREES ALONG THE CHANNEL ARE TO BE PLANTED BY THE BRIDGE CONTRACTOR.

9/10

REV. 9/11/90

CITY OF WICHITA

119th STREET WEST BRIDGE OVER THE COWSKIN CREEK

LANDSCAPING PLAN I

CITY OF WICHITA PROJ. NO. 472-78-245-XXXXX-000-000-001

BOOKER / FREUND
Engineers Architects Planners

SCALE 1"=30' | DATE April, 1990 | DWG. NO. K9330-01

SURV. | PLOT CADD | DES. | DR. | TR. | CKD. | APP.

K9330B9\LAN01
SCALE 1"=30'