

SUMMARY OF
TRAFFIC CONTROL DEVICES
(EACH PER DAY)

DELINEATORS & CHANNELIZING DEVICES (EACH)							
BARRICADES		DRUMS	PAVEMENT MARKERS			VERTICAL PANELS	
TY I OR TY II	TYPE III (9' TO 14')		TUBULAR	TYPE I	TYPE II	SINGLE	BACK TO BACK
--	12						

LIGHTING DEVICES (EACH)	
CONSTRUCTION WARNING LIGHT (TYPE "B" HIGH INTENSITY)	15
ARROW DISPLAY	
TEMP. TRAFFIC SIGNALS (SETS)	--

CONCRETE SAFETY BARRIER (SECTIONS)	
TYPE I (TEMPORARY)	
TYPE IV (TEMPORARY)	--

[illegible]

ITEM	QUANTITY	UNIT
CONSTRUCTION SIGNS (0 TO 9.25 SQ.FT.)		EACH PER DAY
CONSTRUCTION SIGNS (9.26 TO 16.25 SQ.FT.)		EACH PER DAY
CONSTRUCTION SIGNS (16.26 SQ.FT. & OVER)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE I OR II)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 4' TO 8')		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 9' TO 14')		EACH PER DAY
CONSTRUCTION WARNING LIGHT (TYPE "B" HIGH INTENSITY)		EACH PER DAY
REFLECTORIZED DRUM		EACH PER DAY
ARROW DISPLAY		EACH PER DAY
TUBULAR MARKERS		EACH PER DAY
VERTICAL PANELS (SINGLE TYPE)		EACH PER DAY
VERTICAL PANELS (BACK TO BACK TYPE)		EACH PER DAY
OBJECT MARKERS		EACH PER DAY
CONCRETE SAFETY BARRIER (TYPE I) (TEMPORARY)		SECTION/DAY
CONCRETE SAFETY BARRIER (TYPE IV) (TEMPORARY)		SECTION/DAY
PAVEMENT MARKING (TEMPORARY)		
4" BROKEN (8.2') (TYPE I TAPE)		STA./LINE
4" SOLID (TYPE I TAPE)		STA./LINE
4" BROKEN (8.2') (TYPE II OR IIA TAPE)		STA./LINE
4" SOLID (TYPE II OR IIA TAPE)		STA./LINE
PAVEMENT MARKING (TEMPORARY STRIPING)		
4" BROKEN (3.3') (TYPE II OR IIA TAPE)		MILE/LINE
4" SOLID (TYPE II OR IIA TAPE)		MILE/LINE
EXISTING PAVEMENT MARKING REMOVAL		LIN. FT.
GLARE SCREEN		LIN. FT.
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
INERTIAL BARRIER SYSTEM		EACH
MODULE F200 (REPLACEMENT)		EACH
MODULE F400 (REPLACEMENT)		EACH
MODULE F700 (REPLACEMENT)		EACH
MODULE F1400 (REPLACEMENT)		EACH
MODULE F2100 (REPLACEMENT)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TEMPORARY TRAFFIC SIGNALS		LUMP SUM
TRAFFIC CONTROL		LUMP SUM
FLAGGER (SET)	1	HOURL

Note: The Traffic Control shall be bid at Lump Sum which shall include all materials, labor, and equipment to erect and maintain the traffic control during the project. At the conclusion of the construction the Contractor shall remove all traffic control devices in an orderly manner to adequately control traffic. Ownership of the traffic control devices shall be the Contractor's.

3	7-8-96	REVISED TEMPORARY TAPE	WPR	NAB
2	8-9-94	REVERSE TYPE I AND TYPE II TAPE DESIGNATIONS	WPR	NAB
1	5-23-94	1994 MUTCD REVISIONS	WPR	NAB
NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF DEVICES
AND
RECAPITULATION OF QUANTITIES

TE751 10/13/93

FHWA APPROVAL	8-1-96	APP'D	Nelda A. Buckley
DESIGNED	DETAILED	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRAC CK.