PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
618-34	1998	15	169

P.I. ℄ STA. 56+46.03 (48)

1.	FOUND BAR W/ORANGE CAP	
2.	3 NAILS IN NORTH FACE POWER POLE	90.01' SE
3.	KDOT NAIL & WASHER IN SOUTH FACE POWER POLE	54.20' NE
4.	3 NAILS IN TOP FENCE CORNER POST	50.15' N
5.	PK NAIL IN EAST SIDE CORNER FENCE POST	40.43' N
6.	PK NAIL IN SOUTH SIDE FENCE POST	69.74' NW

COORDINATE TABLE		
POINT NO.	NORTH COORDINATE	EAST COORDINATE
48	576757.9120	377237.7410

Scale: 1"=20'

Sta. 51+50 Construct Curb Inlet (Type 22) Lt. Install 24"x206' Storm Sewer (RCP)(E) See Sh. No. 50, 54 (108)

Sta. 53+60 Construct Curb Inlet (Type 22) Lt. Install 24"x286' Storm Sewer (RCP)(E) See Sh. No. 50, 54 (109)

Sta. 56+50 Construct Curb Inlet (Type 22) Lt. Install 24"x171' Storm Sewer (RCP)(E) See Sh. No. 50, 54 (110)

SW 1/4, Sec. 15, T27S, R2E

SE 1/4, Sec. 15, T27S, R2E

Remove 2-35"x 20" CMP

L. J. Fugit and Wife MI-87

Richard L. Jr. and Penni S. Meisel MI-84

Todd E. Parker MI-81-1

Pond

Water Edge

Top of Pond

Bench

Combined Curb & Gutter (Type I)

Concrete Pavement (6" Uniform)(AE)

Remove 36"x 24" CMMAC

Fence

+89.77, 32.50' Lt. P.C. ℄ Sidewalk

+76.23, 32.50' Lt. P.T. ℄ Sidewalk

+33 ℄ 24" Drive

Gravel

+46.01 R/W= ℄ 60' ℄

+46.02 R/W= ℄ 50' ℄

1/4 Section Line

R/W 50' ℄

R/W 60' ℄

Exist. R/W 50' ℄

Wood Fence

Exist. R/W 40' ℄

Const. Limits

Ovhd. Tel.

Exist. 6" Gas (KGE)(Rec. Info.)

5' Sidewalk

Exist. 4" Steel Waterline, abandoned (Beech) (Rec. Info.)

8" Transite Waterline (Beech)(Rec. Info.)

20" (PCCP) Water (Rec. Info.) ①

Gravel Shoulder

Profile Grade Line

℄ Central Avenue=Section Line

Asphalt

Ovhd. Elec. & TV

Exist. 20" (PCCP) Water ① (Rec. Info.)

Exist. 8" San. Sewer

5' Sidewalk

6'x4' RCB

Exist. 42"x27" CMP

Exist. 29"x18" CMP

Remove 29"x 18" CMP

Remove 42"x 27" CMP

Remove 48"x 33" CMP

9" Bituminous Pavement with 6" Lime Treated Subgrade

7" Bituminous Pavement

Concrete Pavement (6" Uniform)(AE)

Combined Curb & Gutter (Type I)

50' R ℄ Walk (Typ.)

+17.30, 32.50' Rt. P.C. ℄ Sidewalk

+56 ℄ 16" Drive

+95.84, 32.50' Rt. P.T. ℄ Sidewalk

+43.77, 32.50' Rt. P.C. ℄ Sidewalk

+83 ℄ 16" Drive

+22.23, 32.50' Rt. P.T. ℄ Sidewalk

+06.77, 32.50' Rt. P.C. ℄ Sidewalk

+46 ℄ 16" Drive

+85.23, 32.50' Rt. P.T. ℄ Sidewalk

P.I. R.C.B. +18.95 37' Rt.

2" Light Type Surfacing (SA-X)

Henry J. Landwehr and Matilda C. Landwehr Trust MI-144

Brian T. Begley MI-247

Roland W. Hayden and Wife MI-147

Fin. Floor House=1355.56

SS. Mh. Top=1355.42 E. Inv=1343.57 E. Out=1343.48

SS. Mh. Top=1353.93 E. Inv=1342.03 E. Out=1340.30

15" Temp. Const. Esmt.

Spare 24" Elm

Split Rail

Barbed Wire

Woven Wire Fence

6" Elm Row

8" Bush Row

2" Bush Row

Hackberry

Sta. 51+11 Construct Manhole Adjustment Rt. from Elev. 1355.42 to Elev. 1354.77 See Sh. No. 65, 66 (200)

Sta. 51+50 Construct Curb Inlet (Type 22) Rt. Install 15"x142' Storm Sewer (RCP)(E) See Sh. No. 50, 54

NW 1/4, Sec. 22, T27S, R2E (201)

Sta. 53+00 Construct Ditch Inlet (Type I) Rt. Install 6'x4'x598' R.C.B.(E) Connect to 2-7'x7' R.C.B. (210) See Sh. No. 50, 56, 57, 67

Sta. 53+60 Construct Curb Inlet (Type 22) Rt. Install 15"x7' Storm Sewer (RCP)(S) Connect to 6'x4' R.C.B. (203) See Sh. No. 50, 54 (202)

Sta. 54+58 Construct Manhole Adjustment Rt. from Elev. 1353.53 to Elev. 1353.03 See Sh. No. 65, 66

Sta. 56+50 Construct Curb Inlet (Type 22) Rt. Install 15"x7' Storm Sewer (RCP)(S) Connect to 6'x4' R.C.B. (205) See Sh. No. 50, 54 (204)

NE 1/4, Sec. 22, T27S, R2E

UTILITIES

Water	Beech
Water ①	Wichita Water Dept.
Power	Kansas Gas & Electric
Gas	Kansas Gas & Electric
Telephone	Southwestern Bell
Cable TV	Multimedia Cablevision
San. Sewer	Sedgwick County

S1/4 COR. SEC. 15, T27S, R2E (48)
℄ STA. 56+46.03 CENTRAL AVENUE

1.	FOUND BAR W/ORANGE CAP	
2.	3 NAILS IN NORTH FACE POWER POLE	90.01' SE
3.	KDOT NAIL & WASHER IN SOUTH FACE POWER POLE	54.20' NE
4.	3 NAILS IN TOP FENCE CORNER POST	50.15' N
5.	PK NAIL IN EAST SIDE CORNER FENCE POST	40.43' N
6.	PK NAIL IN SOUTH SIDE FENCE POST	69.74' NW

No.	Revisions	By	Date
1			

SEDGWICK COUNTY BUREAU OF PUBLIC SERVICES

CENTRAL AVENUE

STA. 51+00 TO STA. 57+00

PROJECT NO. 618-34 SEDGWICK COUNTY

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
ENGINEERS
WICHITA, KANSAS

Designed by	JPS	Checked by	WDH
Drawn by	BJS/MAF	Date JULY 1997	Job No. 95297-2

i:/1995/95297/002/str51-57.dgn
Drawn by: bjs/maf 12-19-97
Plotted by: DJW