


GENERAL NOTES

1. INLET PROTECTION METHOD MAY BE ANY OF THE APPLICABLE TYPES SHOWN, AT THE CONTRACTORS OPTION.
2. GRAVEL FILTER SHALL BE A DURABLE, WELL-GRADED SAND-GRAVEL OR CRUSHED STONE, MAXIMUM 1-1/2 IN. SIZE. AS AN ALTERNATE GRAVEL FILLED BAGS OF BURLAP OR OTHER FABRIC MAY BE USED. WHERE BAGS ARE USED, THE WIRE SCREEN, WHERE SHOWN, MAY BE OMITTED.
3. FILTER FABRIC, WHERE USED, SHALL BE RESISTANT TO ULTRAVIOLET LIGHT. MATERIALS MAY BE SUPPLIED BY THE FOLLOWING MANUFACTURERS:


MIRAFI, INC.	-	100X
HOECHST FIBERS INDUSTRIES	-	TRAVIRA 1115
EXXON	-	TYPAR 3301 W

MATERIALS SUPPLIED BY THE ABOVE NAMED MANUFACTURERS SHALL BE ACCEPTED UPON VISUAL INSPECTION BY THE ENGINEER. OTHER COMPARABLE MATERIALS MAY BE USED IF APPROVED BY THE ENGINEER.

4. INLET TYPE MAY VARY FROM THAT SHOWN.
5. INLET PROTECTION SHALL BE ERECTED AS SOON AS THE INLET HOOKUP HAS BEEN CONSTRUCTED. MEASURES SHALL BE TAKEN TO PRECLUDE ENTRY OF SEDIMENT INTO THE STORM WATER SEWER SYSTEM DURING STREET CONSTRUCTION.
6. REMOVAL AND DISPOSAL OF ACCUMULATED SILT AND DEBRIS AND/OR REMOVAL AND RECONSTRUCTION OF INLET PROTECTION INSTALLATIONS SHALL BE PERFORMED THROUGHOUT THE PROJECT LIFE WHENEVER DEBRIS REACHES ONE-THIRD THE BARRIER HEIGHT, OR AS DEEMED NECESSARY BY THE ENGINEER. ULTIMATE REMOVAL AND DISPOSAL OF INLET PROTECTION AND DEBRIS WILL BE PERFORMED BY THE DEVELOPER.
7. MEASUREMENT AND PAYMENT: THE ITEM "INLET PROTECTION" SHALL BE MEASURED AND PAID FOR AT THE CONTRACT UNIT PRICE BID PER EACH FOR EACH INLET LOCATION PROTECTED REGARDLESS OF METHOD SELECTED BY THE CONTRACTOR. SAID PRICE SHALL BE CONSIDERED FULL COMPENSATION FOR SEDIMENT, AND DEBRIS REMOVAL AND DISPOSAL, AND ALL LABOR, MATERIALS, TOOLS, AND INCIDENTALS NECESSARY TO COMPLETE THE WORK. RECONSTRUCTION OF INLET PROTECTION INSTALLATION DUE TO DAMAGE BY WIND, FLOOD, FIRE, ETC. OR DUE TO ACTIONS BY THE CONTRACTOR OR OTHERS SHALL BE PERFORMED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER AT NO ADDITIONAL COST.



CURB INLET PROTECTION
GRAVEL AND WIRE MESH FILTER



CURB INLET PROTECTION
BLOCK AND GRAVEL FILTER

ADAPTED FROM: VIRGINIA SOIL AND WATER
CONSERVATION COMMISSION, 1985 AND
DRAINAGE CRITERIA MANUAL, DENVER URBAN
DRAINAGE AND FLOOD CONTROL DISTRICT
9-1-92

FOREST LAKES
PHASE NO. 8
**SEDIMENT AND EROSION
CONTROL STANDARD DETAILS
INLET PROTECTION**

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
ENGINEERS
WICHITA, KANSAS

Designed by	VWB	Checked by	
Drawn by	DEP	Date	FEB, 1994
		Job No.	93695

PLAN		BY	DATE
	SURVISED		
NOTE BOOK	PLOTTED		
NO.	ALIGNMENT CHECKED		
	DATE OF WAY CHECKED		

DRAWING NAME: 32-93694 PH 7/6 SED ERSN
LOCATION: #378
OWNER: CITY OF WICHITA
DATE LAST WORKED ON:

DRAINE DUNN