


SCALE: 1"=20'



- The Bid Item "Pavement Removal" shall include the Removal of all Indicated Asphalt, Curb & Gutter, Islands, and Sidewalk.
- Remove all Traffic Signal Poles, Pedestal, Manholes, Concrete Bases, Conduit, Cabeling, Controller, and Misc. Items Relating to the Traffic Signal Operation. Salvage and Deliver all Items to the C.M.F. at 1801 S. McLean Blvd. Attention: Jim Parks

The Removal and Delivery of the above Items is Considered Subsidiary to the Lump Sum Bid Item "Site Clearing".

- The Bid Item "Asphaltic Concrete Overlay" shall be bid and paid for per Square Yards. The Thickness of the overlay Varies with an Average Thickness of 0'-6", which includes the 2" Asphaltic Concrete Wearing Surface. This Equates to a Volume of Asphalt equal to 1,560 Tons Computed at 145lbs./Cu. Ft.

Note: All Sawed Joints are Subsidiary to the Bid Item "Pavement Removal".

UTILITIES
 Power KGE Electric
 Telephone Southwestern Bell
 Cable TV Cox Communication
 Gas Kansas Gas Service
 Gas Jayhawk Pipeline
 Water City of Wichita
 Storm Sewer City of Wichita

PROJECT SURVEY CONTROL COORDINATE TABLE					
POINT	DESCRIPTION	NORTH	EAST	STATION	OFFSET
10	1/2" IRON PIN	19065.90	19976.45	32+09.58	83.56' LT.

10 = Control Point

- * Match Existing
- Pavement Removal ①
- Overlay on Exist. Pavement
- Constructed by Others

Revisions		By	Date
CITY OF WICHITA, KANSAS			
ROCK ROAD STA.30+00 TO STA.35+50			
Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	BER, PMM	Checked by	
Drawn by	BJS	Date	MARCH 2000
		Job No.	99687-1

DSNR: PMM OPER: BJS SCALE: 1"=20'
 I:/1999/99687/001/ROCK1.DGN 6-29-2000