



KEYED PLAN NOTES:

- ADD. #3
400 PAIR, CATEGORY 3, DIRECT BURIED TELEPHONE CABLE.
- ADD. #3
100 PAIR, CATEGORY 3, DIRECT BURIED TELEPHONE CABLE. [DELIVER CABLE TO OWNER.
4" C WITH PULL ROPE AND CAPS.
- PROVIDE 400 PAIR, DIRECT BURIED SPlice ENCLOSURE. SPlice 400
PAIR TELEPHONE CABLE TO EXISTING 400 PAIR TELEPHONE CABLE.
- PROVIDE 400 PAIR, DIRECT BURIED SPlice ENCLOSURE. ~~SPlice 100~~ DO NOT INSTALL. DELIVER TO OWNER.
~~PAIR TELEPHONE CABLE TO 400 PAIR TELEPHONE CABLE.~~
- PROVIDE 400 PAIR, DIRECT BURIED SPlice ENCLOSURE.
- PROVIDE 100 PAIR, DIRECT BURIED SPlice ENCLOSURE. DO NOT INSTALL. DELIVER TO OWNER.
- UTILITY COMPANY 3 PHASE PRIMARY PEDESTAL. FIELD VERIFY EXACT
LOCATION.
- 4" C. WITH PULL ROPE FOR UTILITY COMPANY PRIMARY ELECTRICAL
SERVICE PER UTILITY COMPANY REQUIREMENTS. PROVIDE 36" RADIUS
PVC COATED RGS SWEEPS.
- CAP CONDUIT AND PROVIDE UTILITY MARKER TO MARK END OF CONDUIT. ONE MARKER WHERE CONDUITS MEET.
- PROVIDE UTILITY MARKER TO MARK DIRECT BURIED SPlice ENCLOSURE
LOCATION. PLACE DIRECTLY ABOVE SPlice ENCLOSURE.
- 2" C WITH PULL ROPE.

		Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003	
Date SEPTEMBER 2005		Job No. 05471-019	